

The VA Medical Center Philadelphia located in Philadelphia, PA has a requirement to provide furniture items and installation for the Social Worker space.

Items needed are listed below:

## **1. New Product Specifications:**

### ***Office and Staff Area Seating:***

- Conforms to ANSI/BIFMA Furniture Emissions Standard (M7.1 / X7.1-2007) for the open plan and private office scenarios and BIFMA e3-2008 (Credit 7.6.1) for the open plan and private office scenarios
- High and mid back with height adjustability range of 16" to 20 ½"
- Fluid motion mechanism which allows for automatic positioning of the seat and back to the appropriate ergonomic angles for proper back and body support
- Overall chair movement of: Seat - backward to 12 degrees forward tilt; Backrest - 128 degree backward to 78 degree forward tilt
- Fingertip adjustable mechanisms which may be utilized from a seated position
- Backrest to seat angle shall never be less than 90 degrees
- Contoured chair back and seat shell made of polypropylene with enclosed inner shell in the back which has built in lumbar support
- 2 1/2" thick CFC-free molded foam that meets or exceeds a density of 1.8 lbs. per cubic foot in the back and 2.5 lbs. per cubic foot in the back
- Black powder coated or polished aluminum five star base with 2 ½" dual wheel casters with hood
- Shall have hard floor and carpet casters
- Crypton Suede Fabric shall be Momentum Textiles, Crypton Suede.
- Vinyl Fabric shall be Grade E 100% Polyurethane vinyl, with Abrasion of 200,000 double rubs, Fire rating, Cal. Tech Bulletin 117 Sec E, UFAC Class 1, BIFMA Class 1; available in at least 15 colors.
- Office task chair shall be available in a tall / high or mid mesh back.
- Staff Area chair shall be available in a mesh mid back.

### ***Freestanding Furniture:***

#### **Floor-Supported Pedestals and Mobile Pedestals**

- Shall meet or exceed ANSI/BIFMA standards and guidelines
- Pedestals shall offer a choice of drawer configurations, 6612, 1212
- Cabinet must be welded and mechanically fastened construction
- Pedestal construction
  - Floor-supported and mobile wrapper shall consist of 22-gauge steel
  - Floor-supported and mobile bins shall consist of 20-gauge steel
- Pulls shall be full-width (easy to locate) and recessed
- Shall have 4 adjustable glides for leveling with 1-5/8" adjustment
- Pedestals steel finish shall be in 18 trim colors which are powder coated
- Drawer slides will be steel ball bearing construction for durability
- Pedestals sizes
  - Floor-supported Depth: 22", 28"
  - Mobile Depth: 22"
  - Width: 15-3/16"
  - Height: 27-3/4"

#### Desk - General

- Work surface shall be capable of supporting loads consistent with ANSI/BIFMA specifications
- Optional grommets available matching trim color
- Freestanding Desks shall include a half modesty panel as standard

#### Desk - Work Surface Construction

- Surfaces shall be 1-1/4" thick with a core of 45 lb. density particleboard
- Writing surface to consist of .028 inch thick horizontal grade high-pressure laminate
- Underside finished with a backer sheet that resists moisture and has a Class A flame spread rating
- Underside to be pre-drilled for attaching supports
- Vinyl edge shall be 3mm thick

#### Desk - Work Surface Dimensions

- Overall Thickness: 1-1/4"
- Rectangular work surfaces shall be available in depths of 24" and 30" and widths ranging from 48" to 72"
- All other shapes in a variety of sizes
- Bow top desk to be available in 36" depth and ranging in width from 60" to 72"

#### Desk - Work Surface Finishes/Edge Trim

- Surface edges to be available in 3mm PVC
- Vinyl edge band may be specified to match or complement work surface finish, providing aesthetic options
- Surface to be available in a range of standard laminates (at least 29), including wood laminates

#### Flipper Units – Fabric Front

- Shall meet or exceed ANSI/BIFMA standards and guidelines
- Units shall be able to span any freestanding desk that matches the size of the flipper unit, increasing product flexibility
- Units shall be 15-5/8" deep and be available in a range of widths including: 30", 36", 42", 48", 60", 66", and 72"
- To be sized to support standard and A-4 sized binders
- Shelf pan shall be 16-gauge roll formed steel
- Available in 18 trim colors with metal components powder coated with a 3 mil. finish
- Shall have a metal backstop
- Door pulls shall be full-width of door (easy to locate) and recessed
- Fabric covered flipper door shall be available with inside storing door receding into the cabinet so the top pan may be utilized as a ANSI/BIFMA tested shelf
- Doors to be equipped with an anti-racking mechanism
- Doors shall be available in fabric covered steel, Grade 2 Fabric
- Units come with a fabric covered, grade 2 fabric, tackable insert which mounts below the shelf
- Doors shall be available with standard locking and the ability to key alike and master key

#### Work Surface Construction

- Surfaces shall be 1 ¼" thick with a core of 45lb. density particleboard
- Writing surface to consist of .028 inch thick horizontal grade high-pressure laminate
- Underside finished with a backer sheet that resists moisture and has a Class A flame spread rating
- Underside to be pre-drilled for bases

#### Finishes/Edge Trim

- Shall have PVC flat t-molding, or 3mm PVC banded
- A T-mold table will have rounded corners. A PVC banded table will have corners that come to a point.
- Vinyl edge band may be specified to match or complement work surface finish, providing aesthetic options
- Surface to be available in a range of standard laminates (at least 29), including wood laminates

#### Work Surface Construction

- Surfaces shall be 1" thick with a core of 45 lb. density particleboard
- Shall be double sided Thermally Fused Laminate
- Underside shall be predrilled for attaching supports
- Vinyl edge shall be 3mm thick

#### Finishes/Edge Trim

- Vinyl edge band may be specified to match or complement work surface finish, providing aesthetic options
- Laminate to have embossed wood grain
- Surface to be available in a range of standard laminates (at least 15), including wood laminates

#### Warranty:

Product shall come with a Limited Lifetime warranty on product.

#### **DISCLAIMER**

This RFI is issued solely for information and planning purposes only and does not constitute a solicitation. All information received in response to this RFI that is marked as proprietary will be handled accordingly. In accordance with FAR 15.201(e), responses to this notice are not offers and cannot be accepted by the Government to form a binding contract. Responders are solely responsible for all expenses associated with responding to this RFI.

End of Document