

**SOLICITATION NUMBER VA101-17-R-0301
PRE- PROPOSAL INQUIRY (PPI) FORM
DBB MACC**

Question No.	Reference (Sect/Para/Page)	QUESTION	GOVERNMENT RESPONSE
59	General Note K on Drawing P1.01	General Note K on Drawing P1.01 states that contractor is to provide shut-off valves at each branch line connecting to the main. Which branches does this refer to? Please provide locations, pipe sizes and quantities. We need at least an approximate number for pricing purposes.	Yes they are required on any new branch that is connected to main. Valves shall be placed in an accessible location. Pipe sizes are shown on the drawings. Also refer to specification section 22 05 23
68	Condition ID: 600130, 600134, 600135, 600136, 600131, 600133 600137, 600138, 600140, 600142, 600143, 600145, 600146, 600147, 600148	Does the concrete deck (between floors and roof) have power lines and conduit in the concrete? If so, will the Government require x-raying be conducted to locate such conduit?	X-ray will be required in building 2J. Also Refer to general conditions specifications for select demolition work
69	Drawing 60-A12.08, Details 9,10,11, and 12.	The referenced details do not provide adequate information for which specific insulation is to be replaced. Please provide approximate pipe size(s), footage and location(s).	Bldg. 60, room 114 Domestic CW 4" 25ft+/- 2-1/2"- 20ft+/- 1-1/2"- 10ft +/- 1" – 10ft +/- Domestic HW 1-1/2"- 15'+/- 2-1/2"- 10ft +/- 1" – 10"+/- Aerco Water Heater needs to be insulated- 10"x 2'x 2" thick
70	Plans and Specifications in general	Is there any known asbestos, lead, mold or other hazardous material that we will be required to abate? If there is, where is it located and what are the approximate quantities for pricing purposes?	All abatement will be done by Government.
74		Bldg. 60 storage tanks – What material are these tanks made of?	Storage tank is made of Steel