

3.5 HARDWARE SETS

- A. Hardware Consultant working on a project will be responsible for providing additional information regarding these hardware sets.
- B. Information below is in addition to contract drawings and specifications. All hardware shall be coordinated with door requirements.
- C. All doors shall have Lever Lockset unless noted otherwise.

Fire Extinguisher Closet

- Hinges,
- Silencer
- Handle

Restrooms (B6 103 and 104)

Each Door to Have:

Hinges	QUANTITY & TYPE AS REQUIRED
1 Keyed Privacy Indicator Lock	
1 Closer	
1 Mop Plate	
1 Floor Stop	
1 Auto Door Bottom	
2 Set Self-Adhesive Seals	

Glass storefront doors (Interior and exterior) and B6A 2nd Floor Exterior

Door

Each Door to Have:

- | | |
|---------------------------------------|---|
| 1 Mortise Locks (Only Exterior Doors) | F07 |
| 1 Power Supply (Only Exterior) | REGULATED, FILTERED, 24VDC,
AMPERAGE AS REQUIRED |
- 120VAC POWER, CONDUIT, AND WIRING BY DIVISION 26. (Only Exterior doors)
 - Card Reader by division 28 (Only Exterior Doors)
 - Key Pad (Only Exterior Doors)
 - Exit Device
 - Closer (B6A Exterior door shall have Hold Open abilities in closer)
 - Hinges as required on glass doors
 - Continuous Hinge (Only 2nd floor exterior door)

- Armor Plate (Only 2nd floor exterior door)

REMAINING HARDWARE BY 084500 ALL-GLASS ENTRANCES AND STOREFRONTS

Double Doors to B6 Rooms 111, 112

- Continuous hinges
 - 1 Office Lock
 - 1 Floor Stop
 - 1 Set Self-Adhesive Seals
 - 3 Silencers
 - Threshold
 - Closer
 - Coordinator
 - Overlapping Astragal with Self-Adhesive Seal

Office Doors (B6-105, 106, 109, 109A, 110, 111, 112) (B6A-101, 107, 108, 109, 110, 111, 114 (x2), 115)

Each Door to Have:

- | Hinges | QUANTITY & TYPE AS REQUIRED |
|---------------------------|-----------------------------|
| 1 Office Lock | |
| 1 Floor Stop | |
| 1 Set Self-Adhesive Seals | |
| 3 Silencers | |

Janitor Closets and small Mechanical rooms (B6 102, 111A, 111B, 112A & B6A 106)

Each Door to Have:

- | Hinges | QUANTITY & TYPE AS REQUIRED |
|----------------|-----------------------------|
| 1 Mortise Lock | |
| 1 Kick Plate | |
| 1 Wall Stop | |
| 3 Silencers | |

