



- GENERAL NOTES:**
1. TECH CONTRACTOR SHALL PROVIDE AND INSTALL CABLE AND CABLE MANAGEMENT FOR ALL VIDEO CAMERAS. VIDEO CAMERAS WILL BE LOCATED FOR FUTURE CAMERA. CAMERAS TO BE PROVIDED AND INSTALLED BY THE COUNTY. COUNCILOR SHALL PROVIDE THE LOCATION REQUIRED TO ACHIEVE APPROPRIATE VIEWING AND POINTING FOR ROUTING DISTANCE.
 2. TECH CONTRACTOR SHALL COORDINATE PAVING SIDE DETAILS WITH THE COUNTY TO PROVIDE ZONE CLOSING AS DESIRED BY VDOT.
 3. TECH CONTRACTOR SHALL PROVIDE AND INSTALL ALL CABLES AND DEVICES FOR NURSE CALL SYSTEM AS REQUIRED.
 4. TECH CONTRACTOR SHALL PROVIDE CAT6 ETHERNET DROPS TO SUPPORT WIRELESS NETWORKING. WIRELESS NETWORKING TO BE PROVIDED BY VDOT.
 5. TECH CONTRACTOR SHALL PROVIDE A CLOSED CIRCUIT VIDEO SYSTEM. VIDEO CAMERAS CABLED TO THE VIDEO MONITORING CENTER OF THE DRIVEWAY IN THE TEMPORARY WAITING ROOM AND DROP OFF AREA.
 6. TECH CONTRACTOR SHALL REFER TO ELECTRICAL SHEETS EDP1 AND E6, FOR DETAILS OF EXISTING WIRING FROM EXISTING SUBSTATION TO TC-1 TO USE EXISTING WIRING. COUNCILOR SHALL PROVIDE IF ROUTING ANY CABLEING FROM THEIR EXISTING TECH CLOSETS.
 7. ALL CEILING MOUNTED DEVICES SHALL BE COORDINATED WITH ALL EXISTING CEILING ENDSURE.

Office of
Construction and
Facilities
Management