


three inches = one foot  
one and one half inches = one foot  
one inch = one foot  
three quarters inch = one foot  
one half inch = one foot  
three eighths inch = one foot  
one quarter inch = one foot  
one eighth inch = one foot

A  
B  
C  
D  
E  
F  
G





SYMBOLS

- PANASONIC NETWORK CAMERA (WV-NW 502S)
- PANASONIC PTZ NETWORK CAMERA (WV-NW964)
- Access Card Reader W/Keypad
- Gun Safe
- Key Lockbox
- 1 HR FIRE RATED BARRIER
- 2 HR FIRE RATED BARRIER

NOTES

- NOTE 1: CONTRACTOR WILL USE PANASONIC NETWORK CAMERAS MODEL WV-NW 502S WHEN REPLACING EXISTING CAMERAS AND INSTALLING NEW CAMERAS.
- NOTE 2: CONTRACTOR WILL USE PANASONIC NETWORK PTZ MODEL WV-NW964 WHEN INSTALLING OUTDOOR CAMERAS.
- NOTE 3: CONTRACTOR WILL USE PANASONIC NDR MODEL WJ-ND400K/8000T2 (8 TERABYTE NETWORK RECORDER).
- NOTE 4: CONTRACTOR WILL USE CAT6 NETWORK CABLE.
- NOTE 5: DO NOT USE THE STAIRWELL TO RUN VERTICAL CONDUIT FROM FLOOR TO FLOOR.
- NOTE 6: ALL WIRING INSIDE STAIRWELLS MUST BE INSTALLED IN CONDUIT.
- NOTE 7: ALL WALL PENETRATIONS THROUGH FIRE RATED BARRIERS WILL BE FIRE STOPPED.
- NOTE 8: VERTICAL CONDUIT RISER MUST BE RUN IN MECHANICAL ROOMS.
- NOTE 9: ALL CAT6 CABLE RUNS WILL BE INSIDE THE CABLE TRAY.
- NOTE 10: CONTRACTOR WILL USE PANASONIC COMPACT NETWORK CAMERA (WV-SW155) FOR ELEVATOR.
- NOTE 11: COORDINATE LOCATION OF ALL CAMERAS WITH COTR PRIOR TO INSTALLATION.
- NOTE 12: CONTRACTOR IS RESPONSIBLE FOR DEMO OF EXISTING CAMERAS AND ANY ASSOCIATED PATCHING, REPAIR, CEILING TILE REPLACEMENT AND ASSOCIATED ANCILLARY WORK.
- NOTE 13: CONTRACTOR WILL INSTALL NEW ACCESS CARD READERS, KEY LOCKBOXES, AND SAFES THAT WILL COMMUNICATE VIA THE EXISTING LENSEL NETWORK.

		CONSULTANTS:	ARCHITECT/ENGINEERS:	NORTH: 			Drawing Title  ARCHITECTURAL  GROUND FLOOR PLAN <small>AND</small>	Project Title  Card Access, Safe, Keylock Box, and Cameras	Project Number 620-11-242			Office of Facilities Management
									Building(s) Number 03			
									Drawing Number			
									Location  Montrose, New York			
									Date 03/15/2012	Checked	Drawn AMM	
Fire and Smoke Barrier Updates	03-19-2008						Approved: Director , VAHMHCS		TY-06			 Department of Veterans Affairs
Square Footage Table	08-14-2007											
Careline Hatching	08-13-2007											
Title Block and Color Table Modifications	07-31-2007											
AS-BUILT (INDUS SYSTEM)	06-30-2005											
Revisions:	Date:							Approved: Chief of Engineering		SHEET 6 OF 13		