

Solicitation No. VA262-12-R-0805 Amendment No. A0002

Attachment No. 1

Scope of Work Addition

Project No. 664-12-210 Renovate Psychiatric Emergency Clinic Rm 2416

- The VA will require contractor to provide and install a total of five (5) Troffer Lights with reflectors. The Troffer lights will be broken down as follows: three (3) 2x2, two (2)-2x4.
- Contractor will relocate the Man Down alarm, currently on the South wall and will be replaced on the same wall.
- No signage will be required to be provided by the contractor, VA will complete all signage work in-house by VA.
- Work hours for this project will be as follows: hours will be 7:00A.M to 4:00 P.M. up until the completion of the construction barrier. Following completion of the construction barrier, will require after hours work due to the high patient traffic at the inpatient waiting room which is operational M-F. VA anticipates that this after hours work will be completed in a total of eight (8) hours time.
- Contractor will build privacy dividers into the new wall, they are steel stud framing, drywall finished and painted. Stainless Steel end caps for protection. Paint will be the same as the wall paint.
- Contractor will install new transaction tops at each window, each approximately 60" wide to be field verified when new wall is laid out to create 3 equal openings, the transaction tops are solid surface. Counter tops will be Brand: LG and Color: Maui Quartz.
- Contract will abate existing black mastic containing asbestos found under the VCT being replaced in Room 2416. The VCT does not contain asbestos, however the mastic below the VCT floor tiling does contain asbestos which will require abatement by contractor.