

SYMBOL LEGEND

	ONE HOUR FIRE BARRIER		EXISTING DOOR TO REMAIN		NEW INTERCOM OUTLET, WALL OUTLET, CONDUIT AND CABLING TO BE PROVIDED BY CONTRACTOR. INTERCOM SETS TO BE PROVIDED AND INSTALLED BY VA (OFOI). REFER TO ELECTRICAL DRAWINGS AND ROOM ELEVATIONS
	TWO HOUR FIRE BARRIER		EXISTING DOOR TO RECEIVE NEW HARDWARE. SEE DOOR SCHEDULE.		NEW OXYGEN MEDICAL GAS OUTLET/VALVE. ADDITIONAL CONTROL VALVE TO BE PROVIDED IN CORRIDOR OUTSIDE EACH SLEEP ROOM. REFER TO ROOM ELEVATIONS AND PLUMBING DRAWINGS.
	SMOKE COMPARTMENT WALL - ONE OR TWO HOUR FIRE RATING		NEW DOOR. SEE DOOR SCHEDULE.		NEW OXYGEN CONTROL BOX - SEE PLUMBING.
	FULL HEIGHT SMOKE RESISTANT		EXISTING PLUMBING FIXTURE TO REMAIN		NEW VACUUM MEDICAL GAS OUTLET/VALVE. REFER TO ROOM ELEVATIONS AND PLUMBING DRAWINGS.
	EXISTING WALL/PARTITION TO REMAIN		NEW PLUMBING FIXTURE. REFER TO PLUMBING DRAWINGS AND SPECS		THERMOSTAT FOR INDIVIDUAL SLEEP ROOM CONTROL.
	NEW NON-RATED WALL/PARTITION: 5/8" TYPE-X GYP. BD. EACH SIDE ON 3-5/8" METAL STUDS (EXCEPT WHERE NOTED OTHERWISE) AT 16" O.C. WITH SOUND BATT ATTENUATION BLANKETS. EXTEND TO DECK/STRUCTURE ABOVE AND SEAL. SEAL TIGHT TO ALL PENETRATIONS. REFER TO DETAIL 2/A6.1		FURNITURE OR EQUIPMENT TO BE PROVIDED/RELOCATED BY OWNER (OFOI)		
	NEW SMOKE TIGHT WALL/PARTITION: 5/8" TYPE-X GYP. BD. EACH SIDE ON 3-5/8" METAL STUDS AT 16" O.C. WITH SOUND BATT ATTENUATION BLANKETS. EXTEND TO DECK/STRUCTURE ABOVE AND SEAL. SEAL TIGHT TO ALL PENETRATIONS. REFER TO DETAIL 2/A6.1		FURNITURE OR EQUIPMENT TO BE PROVIDED/RELOCATED BY OWNER (OFOI)		
	NEW 1-HOUR FIRE RATED BARRIER: 5/8" TYPE-X GYP. BD. EACH SIDE ON 3-5/8" METAL STUDS AT 16" O.C. WITH SOUND BATT ATTENUATION BLANKETS. EXTEND TO DECK/STRUCTURE ABOVE AND SEAL. SEAL TIGHT AND PROTECT ALL PENETRATIONS. SEE MECHANICAL FOR FIRE DAMPER LOCATIONS. ALL DUCTWORK PENETRATIONS TO BE PROTECTED. REFER TO DETAIL 3/A6.1		FLOOR DRAIN - SEE PLUMBING COORDINATE WITH STRUCTURE BELOW.		
	NEW 1-HOUR FIRE RATED BARRIER: 5/8" TYPE-X GYP. BD. EACH SIDE ON 3-5/8" METAL STUDS AT 16" O.C. WITH SOUND BATT ATTENUATION BLANKETS. EXTEND TO DECK/STRUCTURE ABOVE AND SEAL. SEAL TIGHT AND PROTECT ALL PENETRATIONS. SEE MECHANICAL FOR FIRE DAMPER LOCATIONS. ALL DUCTWORK PENETRATIONS TO BE PROTECTED. REFER TO DETAIL 3/A6.1		OVERHEAD CABINETS OR SHELVES		

GENERAL NOTES

- EXISTING DOORS TO BE REPLACED WITH NEW MAY BE DIFFERENT SIZE THEN EXISTING. REMOVE ADDITIONAL WALL AS REQUIRED TO FRAME FOR NEW DOOR AND FRAME. INFILL WALL AS REQUIRED. RELOCATE WALL SWITCHES AND OUTLETS AS REQUIRED.
- REFER TO INFECTION CONTROL PLAN FOR INFECTION CONTROL MEASURES, PHASING AND AREAS REQUIRING AFTER HOURS WORK.
- REFER TO FINISH PLANS FOR EXTENTS OF INTERIOR FINISH REPLACEMENT AND NEW WORK.
- REFER TO MECHANICAL, ELECTRICAL AND PLUMBING DRAWINGS FOR EXTENTS OF WORK FOR THESE SYSTEMS.
- REFER TO PROJECT SPECIFICATIONS. NOTIFY ARCHITECT OF ANY CONFLICT BETWEEN THE WRITTEN SPECIFICATIONS AND THESE DRAWINGS.

KEY NOTES

- NEW FINISHES TO MATCH EXISTING. EXTEND AS REQUIRED TO PROVIDE A SMOOTH TRANSITION TO EXISTING.
- INFILL EXISTING DOOR OPENINGS WITH FINISHES TO ALIGN WITH AND MATCH ADJACENT.
- NEW PLASTIC LAMINATE, BUILT-IN MILLWORK. REFER TO ELEVATIONS AND DETAILS.
- PUSH BUTTON AUTO DOOR OPERATOR.
- NEW PLUMBING FIXTURES
- CCTV MONITOR THIS ROOM BY VA. COORDINATE POWER AND CABLING.
- NEW BUILT-IN MILLWORK WARDROBE
- PREMANUFACTURED ACRYLIC SHOWER
- NEW POWERED SLIDING ALUM. AND GLASS DOOR AND ALUMINUM STOREFRONT. REFER TO ELEVATIONS AND DOOR SCHEDULE.
- OPERABLE PARTITION. SEE DETAILS SHEET A6.1
- NOT USED
- NOT USED
- NOT USED
- RECESSED POWER AND DATA OUTLET IN FLOOR. SEE ELECTRICAL DRAWINGS. IN ADDITION PROVIDE 1" EMPTY CONDUIT TO CEILING PROJECTOR LOCATION.
- EXTEND EXISTING PARTITION TO DECK ABOVE AND SEAL SMOKE TIGHT
- EXISTING GYP. BD. PARTITION TO BE EXTENDED TO DECK ABOVE FOR A 1-HOUR RATED FIRE BARRIER. PROVIDE FIRE DAMPERS PER MECHANICAL DRAWINGS AND SEAL AROUND ALL PENETRATIONS WITH FIRE RATED SEALANT. SEE DETAIL 3 ON SHEET A6.1.
- EXISTING CMU PARTITION TO BE EXTENDED TO DECK ABOVE FOR A 1-HOUR RATED FIRE BARRIER. PROVIDE FIRE DAMPERS PER MECHANICAL DRAWINGS AND SEAL AROUND ALL PENETRATIONS WITH FIRE RATED SEALANT. SEE DETAIL SHEET A6.1.
- POCKET FOR OPERABLE PARTITION. SEE ENLARGED PLAN.
- CHASE FOR RELOCATED PLUMBING LINE.
- NEW ICE MACHINE BY OWNER INSTALLED BY CONTRACTOR. PROVIDE DRAIN, WATER SUPPLY AND POWER.
- NEW LOCKING SLIDING GLASS TRANSACTION WINDOW.
- LOCATE DOOR AS REQ. NOT TO INTERFERE WITH EXISTING CROSS CORRIDOR DOOR
- PROVIDE JUNCTION BOX ABOVE CEILING WITH EMPTY 1" CONDUIT RUN TO RECESSED FLOOR LOCATION ON SAME SIDE OF OPERABLE PARTITION.

