

three inches = one foot
one and one-half inches = one foot
one inch = one foot
three-quarters inch = one foot
one-half inch = one foot
three-eighths inch = one foot
one-quarter inch = one foot
one-eighth inch = one foot

GENERAL CEILING NOTES - NEW WORK

- NEW HVAC DIFFUSERS/GRILL LOCATIONS ARE NOT SHOWN. REFER TO MECHANICAL DRAWINGS FOR EXACT LOCATIONS.
- NEW LIGHT FIXTURE LOCATIONS ARE SHOWN FOR GENERAL REFERENCE ONLY. SEE ELECTRICAL DRAWINGS FOR NEW LOCATIONS.
- NEW SPRINKLER HEAD LOCATIONS ARE NOT SHOWN. NEW SPRINKLER SYSTEM WORK IS TO BE DESIGN-BUILD BY CONTRACTOR. SUBMIT SHOP DRAWINGS FOR APPROVAL AS REQUIRED PER SPECIFICATIONS.
- NEW CEILING HEIGHTS ARE TO MATCH EXISTING UNLESS NOTED OTHERWISE.
- REFER TO INFECTION CONTROL PLANS FOR DUST PARTITION LOCATIONS AND PHASING OF WORK.
- NEW SECURITY SYSTEM TO BE PROVIDED BY OTHERS. COORDINATE THIS WORK WITH THE VA PROJECT MANAGER.

KEY NOTES

- NEW PRIVACY CURTAIN. FIELD VERIFY LENGTHS. VA TO PROVIDE AND INSTALL CURTAINS.
- CURTAIN TRACKS TO BE RELOCATED. COORDINATE WITH VA PROJECT MANAGER.
- PROVIDE NEW CEILING TILE THIS ROOM.
- NEW GYP. BOARD SOFFIT ABOVE OVER-HEAD CABINETS. SEE MILLWORK DETAILS AND SECTIONS.
- NEW EXHAUST DUCT TO RUN BEHIND WALL MOUNTED CABINETS. SEE MILLWORK SECTIONS.
- NOT USED.
- NOT USED.
- BATHROOM EXHAUST FAN. SEE MECHANICAL.
- RELOCATE HVAC DIFFUSER AS REQUIRED FOR NEW CURTAIN TRACKS.
- NOT USED.
- RELOCATE EXISTING LIGHT FIXTURE TO COORDINATE WITH NEW CURTAIN TRACK LOCATIONS.
- RELOCATED EXISTING LIGHTING TRACK SYSTEM. PROVIDE ALL THREADROD SUPPORTS SECURED TO CONCRETE DECK ABOVE. BRACE AS REQUIRED.
- NEW CEILING IN THIS AREA IS TO BE BLACK ACOUSTICAL CEILING TILE AND GRID. HOLD CEILING AS HIGH AS POSSIBLE.
- NEW EXIT SIGN. SEE ELECTRICAL.
- VENTILATION GRILLS EXCEEDING 100 SQ. IN. MUST BE REINFORCED TO PREVENT THEIR REMOVAL FROM ABOVE THE CEILING.
- EXTEND EXISTING AND NEW PARTITIONS TIGHT TO DECK ABOVE AND AROUND DUCT WORK, CONDUIT, ETC. REMOVE AND REPLACE EXISTING CEILING AS REQUIRED FOR ABOVE-CEILING WORK.



SYMBOL LEGEND

----- ONE HOUR FIRE BARRIER

----- TWO HOUR FIRE BARRIER

----- SMOKE COMPARTMENT WALL - ONE OR TWO HOUR FIRE RATING

----- FULL HEIGHT SMOKE RESISTANT

----- EXISTING WALL/PARTITION TO REMAIN

----- NEW FULL HEIGHT PARTITION

EXISTING 2 X 2 ACOUSTICAL SUSPENDED CEILING SYSTEM TO REMAIN.

NEW 2 X 2 ACOUSTICAL SUSPENDED CEILING. REFER TO SPECIFICATIONS.

EXISTING GYPSUM BOARD SOFFIT

NEW PAINTED GYPSUM BOARD SOFFIT

EXISTING 2 X 4 RECESSED FLUORESCENT LIGHT FIXTURE TO REMAIN. REFER TO ELECTRICAL.

NEW OR RELOCATED 2 X 4 RECESSED FLUORESCENT LIGHT FIXTURE. REFER TO ELECTRICAL.

EXISTING HVAC GRILL/DIFFUSER TO REMAIN. REFER TO MECHANICAL. SEE MECHANICAL DRAWINGS FOR NEW HVAC WORK AND DIFFUSER LOCATIONS.

EXISTING CEILING MOUNTED EXIT SIGN.

NEW CEILING MOUNTED EXIT SIGN. SEE ELECTRICAL DRAWINGS FOR QUANTITY AND LOCATIONS. SHADED PORTION INDICATES DIRECTION.

EXISTING SPEAKER TO REMAIN. NEW SPEAKERS ARE TO BE INSTALLED BY VA. COORDINATE THIS WORK WITH VA PROJECT MANAGER.

EXISTING NURSE CALL LIGHT TO REMAIN.

CCTV SECURITY CAMERA TO REMAIN. NEW SECURITY SYSTEM TO BE PROVIDED AND INSTALLED BY OWNER. CONTRACTOR IS TO COORDINATE THIS WORK WITH THE VA PROJECT MANAGER.

CEILING MOUNTED COMMUNICATIONS EQUIPMENT. REMOVE FROM CEILINGS TO BE REMOVED AND RETURN TO OWNER.

NEW CEILING FAN WITH LIGHT KIT. FAN TO BE SUPPLIED AND INSTALLED BY CONTRACTOR. LIGHT KIT TO BE SUPPLIED BY CONTRACTOR AND INSTALLED BY OWNER.

EXISTING PRIVACY CURTAIN TRACK TO REMAIN OR RELOCATED. COORDINATE THIS WORK WITH THE VA PROJECT MANAGER.

NEW PRIVACY CURTAIN TRACK. CURTAINS TO BE PROVIDED AND INSTALLED BY THE VA.

NEW 4 FOOT STRIP FLUORESCENT FIXTURE WITH ACRYLIC COVER. SEE ELECTRICAL DRAWINGS.

MECHANICAL DIFFUSERS/REGISTERS. SEE MECHANICAL PLANS FOR LOCATIONS.

SURFACE MOUNTED LIGHT FIXTURE. SEE ELECTRICAL.

1 **8TH FLOOR REFLECTED CEILING PLAN - NEW WORK**
SCALE: 3/32"= 1'-0"

Revisions

Date

**BIRCHFIELD
PENUEL &
ASSOCIATES,
ARCHITECTS**
2805 CRESCENT AVENUE • SUITE 200 • BIRMINGHAM, ALABAMA 35209

**Department of Veterans Affairs
MEDICAL CENTER
BIRMINGHAM, ALABAMA**

Drawing Title
8th FLOOR
REFLECTED CEILING PLAN
NEW WORK

Project Title
RENOVATE SPACE FOR REHAB
AND PHYSICAL MEDICINE

Building Numbers
Checked
Drawn

Location
VA MEDICAL CENTER BIRMINGHAM, ALABAMA

Date: 08-02-11
VA Project No. 521-10-101
CAD File No. 10709A1.5.dwg

Drawing No.
A3.4
Dwg. of

**Veterans
Administration**

FINAL SUBMITTAL