



WALLS	P-1
BASE	RB-1
FLOORS	EXST

***** VERIFY ALL VA STANDARD FINISHES (NEW AND EXISTING) AND COORDINATE LOCATIONS WITH VA INTERIOR DESIGNER.

KEY NOTES

- | | |
|------|--|
| 7-1 | PATCH RUBBER BASE TO MATCH EXISTING AT AREA OF WORK INDICATED ON PLAN. |
| 7-2 | PATCH VCT AT AREA OF WORK INDICATED ON PLAN, VCT-1. |
| 7-3 | BETWEEN ADOORS, PROVIDE SINGLE PLANK WIDTH BORDER, VIA STANDARD WOOD VISUAL LUXURY VINYL, TILE TO MATCH EXISTING CONDITION. |
| 7-4 | PROVIDE CONTINUOUS HANDRAIL SYSTEM TO MATCH EXISTING BETWEEN OPENINGS, MAX 6" FROM EACH OPENING, WITH MATCHING END CAPS. |
| 7-5 | EXISTING HANDRAIL SYSTEM TO REMAIN WHERE CLEAN, UNDAMAGED, AND AFFECTED BY CONSTRUCTION, WITH MATCHING END CAPS, U.N.O. REPLACE DAMAGED UNITS TO MATCH EXISTING. |
| 7-6 | ADJUST EXISTING HANDRAIL SYSTEM TO FIT BETWEEN OPENINGS, WITH MATCHING END CAPS. |
| 7-7 | PROVIDE CONTINUOUS HANDRAIL SYSTEM TO MATCH EXISTING BETWEEN OPENINGS AND INTERSECTING WALL, MAX 6" FROM OPENING AND WALL, WITH MATCHING END CAPS. |
| 7-8 | INSTALL NEW CONTINUOUS HANDRAIL SYSTEM AND WALL GUARDS WHERE INDICATED ON PLAN, HANDRAILS, HR-1 AND WALL GUARDS, WG-1 SEE SHEET AB-3 FOR DETAILS. |
| 7-9 | IN AREAS AFFECTED BY CONSTRUCTION OR DEMOLITION, REPLACE CEILING GRIDS AND ACOUSTICAL CEILING TILE TO MATCH EXISTING, ACT-1. |
| 7-10 | IN AREAS AFFECTED BY CONSTRUCTION OR DEMOLITION, PATCH CEILING GRID & ACOUSTICAL CEILING TILE TO MATCH EXISTING, ACT-1. |
| 7-11 | SLEEP LAB CORRIDOR AND SLEEP ROOMS TO RECEIVE NEW CEILING GRID & ACOUSTICAL CEILING TILE, ACT-2. |
| 7-12 | NEW RESTROOM TO RECEIVE NEW CEILING GRID AND MOISTURE-RESISTANT CEILING TILE, ACT-3. |
| 7-13 | NEW SLEEP ROOM BATHROOMS TO RECEIVE NEW CEILING GRID AND MOISTURE-RESISTANT CEILING TILE, ACT-4. |