



1. PERFORM TEST AND BALANCE BEFORE CONSTRUCTION BEGINS AND AFTER CONSTRUCTION IS COMPLETE ON ALL FAN COIL UNITS, THAT ARE BEING RELOCATED, REMOVED, OR HAVING THE ATTACHED DUCTWORK ALTERED. TEST FOR EXISTING CHILLED WATER LINES SERVING THIS AREA FOR FLOW RATE AND LOW PRESSURE STEAM RISERS FOR NECESSARY PRESSURE.

- ① EXISTING FAN COIL UNIT TO BE RELOCATED. CAP ALL EXISTING HEATING, COOLING, AND CONDENSATE PIPING AT THE BRANCH FROM THE MAIN.
- ② VERIFY FAN COIL UNIT'S OPERATION BEFORE CONSTRUCTION BEGINS AND AFTER CONSTRUCTION IS COMPLETE. SUBMIT REPORT WITH PRE-CONSTRUCTION FINDINGS.

**KEY PLAN**

**NO SCALE**

**WR** Whitaker & Rawson, Inc.  
3332 Old Montgomery Hwy  
Suite 103 Mark Harris Bldg  
Birmingham, AL 35209

---

Phone: 205-870-0801  
Fax: 205-870-0891

---

[www.whitakerandrawson.com](http://www.whitakerandrawson.com)

---

Mechanical: Doug Rawson  
Direct Line - (205) 870-0801  
Plumbing: Carol Johnson  
Direct Line - (205) 949-5123

**BIRCHFIELD  
PENUEL &  
ASSOCIATES,  
ARCHITECTS**

2805 CRESCENT AVENUE • SUITE 200 • BIRMINGHAM, ALABAMA 35209

Department of Veterans Affairs  
**MEDICAL CENTER**  
BIRMINGHAM, ALABAMA

Drawing Title	Project Title			Date: 08-12-11	Veterans Administration
7TH FLOOR BLOCK "A" HVAC DEMOLITION PLANS	RENOVATE SPACE FOR REHAB AND PHYSICAL MEDICINE			VA Project No. 521-10-101	
				CAD File No. 4608A01	
	Building Numbers	Checked DER	Drawn JRB	DRAWING NO. M1.1-A	
	Location VA MEDICAL CENTER BIRMINGHAM, ALABAMA			Dwg. Of	