



CSO Architects

PROJECT NAME MARION VA MEDICAL CENTER, INDIANA **DATE** 06-01-12
PROJECT NO. 11078 **DWG #** A101
DRAWN BY NW

SUPPLEMENTAL DRAWING

PLAN NOTES- SHEET A101

- 8 NEW 3- $\frac{5}{8}$ " METAL STUDS @ 16" O.C. WITH 5/8" IMPACT-RESISTANT GYPSUM PANEL ONE SIDE FROM FLOOR TO EXISTING WOOD CEILING SYSTEM ABOVE. CONTRACTOR MAY USE 6" STUDS AT HIS OPTION. PROVIDE LATERAL BRACING AS SPECIFIED IN SECTION 09 22 16. ASSUME 5 PSF UNIFORM LOAD ON WALL SURFACE FOR STUD BRACING SIZING.
- 21 REMOVE EXISTING WINDOW AND INSTALL LOUVER IN ITS PLACE. SEE MECHANICAL.
- 22 PROVIDE LOUVER ABOVE NEW WINDOW. MODIFY WINDOW DIMENSIONS TO ACCOMMODATE LOUVER. SEE MECHANICAL.
- 23 IF ALTERNATES 3 OR 4 ARE ACCEPTED PROVIDE WALL CAP IN DIVIDED LIGHT FRAME IN LIEU OF GLASS AND ELIMINATE LOUVER. SEE MECHANICAL.