

1 **OEC 9900 Elite™ Digital Mobile Standard C-arm
PMCare (PMCare Platform with 8 fps digital disk and
12" I.I.)**

High performance mobile C-arm for use in pain management procedures. Provides flexible mechanical features, rotating anode x-ray tube, user-friendly touch screen user interface, and superb image quality.

The physical dimensions and the open design of the C-arm allow the system to be easily transported throughout the hospital and provide unobstructed imaging access around the patient and procedural table.

Digital Image Processing and Workstation

- Dynamic Range Management (DRM) controls for image management
- Four pre-set imaging profiles for optimized anatomical capture
- Dual articulating, high resolution flat screen black & white monitors
- Integrated keyboard touchpad - cursor/tap controls
- DICOM 3.0 interface with send and query/retrieve
- CD/DVD on-board media storage, read/write compatible
- USB 2.0 mass storage device, write only, .jpg/.bmp/.avi file formats

X-ray Generator

- 60 kHz high frequency
- 15kW power
- Up to 120 kVp
- Up to 75mA for radiographic film exposure
- Continuous high level fluoro (HLF) up to 20mA
- Digital spot up to 75 mA
- Full power from standard wall outlet
- Patented battery buffered design

X-ray Tube

- Rotating anode x-ray tube
- 0.3mm and 0.6mm focal spots
- Anode heat capacity: 300,000 HU (per IEC 60613)
- Anode cooling rate: 85,000 HU/min.
- Housing heat capacity: 1,600,000 HU
- Standard housing cooling 22,500 HU/min.

Digital Image Rotation

- Digitally adjusts image display
- Automatic image update
 - Image rotation
 - Image reversal (side-to-side)
 - Image invert (top-to-bottom)
- Image positioning without additional exposure

PreView™ Collimator

- On-screen collimator position indication
- PreView™ iris collimator
- PreView™ Tungsten rotatable double leaf

collimator

- Adjusts collimator without X-ray exposure

Fluoro Mode

- kVp range: 40 -120
- mA range: 0.2 - 10
 - 1.0 - 20 HLF (high level fluoro)
- Auto and manual fluoro modes
- AutoTrak™ ABS varies mA, kVp camera gain

Pulsed Fluoro Mode

- kVp range: 40 - 120
- mA range: 0.2 - 10
- Pulse rate: 1,2,4,8
- Pulse width: 25 or 50ms
- AutoTrak™ ABS, mA, kVp, camera gain
- Reduces X-ray dose to patient and operator

High Level Pulsed Fluoro

- kVp range : 40 - 120
 - mA range: 1 - 40
-

- Pulse rate: 1,2,4,8
- Pulse width: 25 or 50ms
- AutoTrak™ ABS, mA, kVp, and camera gain

Digital Spot Mode

- kVp range: 40 - 120
- mA range: Up to 75
- Automatic exposure termination and automatic image save

Radiographic Mode

- mA range: up to 75
- mAs range: up to 300
- Computer controlled exposure time

12" Image Intensifier

- Tri-Mode 12"/9"/6" (31cm/23cm/15cm) image intensifier
- Minimum central resolution (at the monitor)
 - 12" (31cm): 1.6 lp/mm
 - 9" (23cm): 2.2 lp/mm
 - 6" (15cm): 2.6 lp/mm
- DQE: 65% (typical)

Precision imaging with Dynamic Range Management (DRM) enhances features of interest while attenuating background noise.

- Preset Imaging Profiles
 - 9800
 - General
 - Orthopedic
 - Spine

AutoTrak™

- Automatic Brightness Stabilization (ABS)
- Automatically seeks the subject anatomy anywhere within the imaging field and selects the optimum imaging technique
- Automatically adjusts to anatomical size and location
- Provides uniform image quality throughout entire image
- Simplifies operation

Image Quality

- Smart Window:
 - Dynamically senses the collimator position and automatically adjusts brightness and contrast to produce high image quality.
 - Smart Metal:
-

- Allow user to adjust automatic brightness and contrast sensitivity levels to metal
- Provides optimum image quality even when metal is introduced to the field
- Tungsten Collimator:
 - Denser collimator limits X-ray exposure area
 - Reduces scatter radiation
 - Improves image detail

Video Camera

- High resolution 1k x 1k CCD camera
- Full frame capture
- Motorized rotation
- On-screen orientation indicator (real-time feedback without fluoro)
- Left-right image reversal
- Top-bottom image invert

Video Display

- Dual display anti-glare, LCD flat panel monitors mounted on an articulating arm:

- Left hand Black & White monitor, Right hand Color monitor

- 22" horizontal travel
- 7° up/10° down
- Monitors viewable from all four sides of workstation
- Horizontal and vertical viewing angle 170°
- 1200 CD/M2 maximum brightness
- Touch screen system control
- 1280 x 1024 high resolution monitors
- OEC 9900 TechView Reference Monitor:
 - 9" LCD Display mounted at C-arm mainframe
 - Reference quality real-time video of left live-image C-arm
- 270° rotation, +30°/-5° tilt

PMCCare Platform

- 1k x 1k x 16 bit image processing
 - Preset Imaging Profiles:
 - 9800
 - General
 - Orthopedic
 - Spine
 - Noise filter with on-screen indicator
 - Minimal difference spatiotemporal noise filter (MDST)
 - Real-time dynamic range management (DRM)
 - Automatic digital brightness and contrast control
 - Manual digital brightness and contrast control
-

- Negate mode
- Save and auto-save feature
- Swap and auto-swap feature
- Patient information
 - Examination list
 - Customized patient information
- Customize functions
 - Workstation set-up
 - Mainframe set up
 - Patient information set up
 - Date/time set up
 - DICOM interface set-up
- Last image hold
- 1000 image storage
 - CD/DVD burner with DICOM viewer for displaying images on PC platforms 512 x 512 or 1k x 1k
 - Integrated DICOM interface (store, print, worklist, and query/retrieve)
- HIPAA SecureView
 - Password protection
 - Blank screen function
 - Delete all
- Zoom and roam function
- Image annotation
- Measurement software
- 8fps Dynamic digital disk
 - Recording /playback rate: 1,2,4,8fps
 - Recording time: 5 minutes @ 8fps
 - Automatic image playback
 - Frame-by-frame review
- Re-registration

User Interface

- Entire system is computer controlled and software upgradeable
- Touchscreen control simplifies operation
- Automated system operation requires minimum operator interface
- Multi-functional controls
 - Footswitch
 - Hand-held control
- Simplified keyboard with integrated touchpad
- Multi-purpose image directory
 - Retrieve and review images
 - Compose hardcopy films
 - Copy images
- X-ray dose summary

C-arm Mechanics

- Counterbalanced, manual adjustment of orbital
-

rotation, cranial-caudal rotation, wig-wag and horizontal motion

- Patented flip-flop C-arm reversal (SmartView)
- 31" free space, 28" depth in arc, 115° orbital rotation
- Dual, illuminated C-arm operator control panels

OEC Clinical Excellence Onsite Training

- Pre-training package with interactive CD-ROM
- Up to three days* of in-service by our ARRT certified Clinical Imaging Specialists (CIS) during the one-year warranty period.
- Post-training skills assessment & test
- Participants may be eligible for Continuing Education (CE) credits from the American Society of Radiologic Technologists**

Notes: WSP - Wireless Service Platform

- The OEC 9900 comes with a device called the WSP which facilitates these capabilities:
- USB 2.0 mass storage: The USB functionality is write only, and saves images in .jpg/.bmp/.avi file formats. USB storage devices must be unencrypted and unprotected.

Warranty

- One Year Warranty

Notes: OEC Clinical Excellence Onsite Training

* Onsite training provided from 8am to 5pm, Monday through Friday. Includes all CIS travel and living expenses. ** Training produces the best results when a dedicated core group of technologists complete the session. Those who complete the entire OEC Clinical Excellence curriculum should be competent to perform the tasks required for basic operation of the system. Competency will be measured through a skills assessment completed while the CIS is on-site.

1 **12" Twelve Month Extended Warranty, 9900**

1 **IDI, 100-4T And MDS D Package**

Includes the following items:
IDI Aspect 100-4T G2 Fluoroscopic Procedure Table
Package, PN 5339212

Table Specifications:

- Standard table top, 22"/24" X 80 contoured shape with Mini Rails
- Cantilevered, carbon fiber tabletop with low x-ray attenuation

- Manual 4 way float Table top
- Unobstructed imaging area: 62" (157.5 cm)
- Motorized tabletop movements with hand control:
 - Elevation 29" - 38.9"
 - Longitudinal Travel 32"
 - Trendelenburg Tilt $\pm 12^\circ$
 - Transverse travel 8"
- Locking swivel casters
- Patient weight capacity: 450 lbs. (204 kg)
- Table weight: 605 lbs. (147 kg)
- 120 VAC or 230 VAC operation (must specify on order)
- Battery back-up operation
- Warranty: 3 years parts, 1 year labor

Table Accessories Included:

- Tabletop Pad 2"
- Patient Restraint Straps
- Panning Hand Control
- Clamp-on accessory rail, qty 2, for 100-4T and Aspect ISR (ea), 5335432
 - Arm board, phenolic, rail mounted, qty 2, 5335433 (requires Accessory Rail 5335432),
 - VAB Arm board; carbon fiber, one-piece, extra wide armboard for vascular access procedures (body section slides under patient/table pad). Includes strap and pad, 5335436.
 - Catheter Tray Extension for Aspect ISR & 100-4T table with mini-rails, 22" wide, PN 5459779

WARRANTY:

- Table warranty terms are specified and service provided by the manufacturer during the warranty period as described above. During this period any warranty claims should be addressed directly with the manufacturer:

Image Diagnostics, Inc.
310 Authority Drive
Fitchburg, MA 01420
(978) 829-0009, Fax (978) 829-0027

IDI MDS D Mobile Display System, Complete, with High Definition Video Monitors, PN 5537868

The Aspect MDS stand provides a wide-range of vertical and horizontal positioning for convenient placement of video monitors at the desired location during surgical, interventional and diagnostic procedures.

The stand includes one equipment shelf for placement of ancillary equipment such as video endoscopy camera control, light source, etc.

IDI MDS D Mobile Display Specifications:

- Dual-Arm Mobile Display Stand;
- Video Converter and Switcher;
- Radiance 26" High-Brightness LCD Widescreen Multi-Modality Video Monitors (Qty of 2);
- Protective covers for 26" Radiance monitors (Qty of 2).
- Video Cable kit, including common cables/connectors needed for connection of C-arm and other equipment that will be connected to MDS Mobile Display System.
- Built in shelf (1) for placement of ancillary equipment.

AC INPUT POWER OPTIONS:

- North America Version, 15 amp. For connection to 110-120VAC, 60 Hz, 15 amp outlet. Includes built-in 1,800 Watt isolation transformer and 15 amp power cord and hospital grade plug.
- Maximum allowable combined load on MDS power strip = 12 amp.

Includes GE OEC C-arm Cable Kit, PN 5454320. Kit contains the following cables:

- Video connection kit including qty (2) 6 ft. internal VGA to BNC RGBS (SOG) connector cable
- Dual BNC connector panel, Qty (1)
- VGA/DVI adapter, Qty (1)
- External 20 ft. BNC coaxial, Qty (2) cable

WARRANTY:

- MDS warranty terms are specified and service provided by the manufacturer during the warranty period as described above. Video displays and router are not repairable at customer site.
 - Warranty repair is provided via exchange/loaner program in which replacement monitor or router is delivered to customer and defective monitor or router is returned to IDI in the same shipping box for factory repair.
 - See Official Warranty Document for details.
 - During this period any warranty claims should be addressed directly with the manufacturer:
Image Diagnostics, Inc.
310 Authority Drive
-

1 **IDI, MDS-D Install With GE CIS Support, Continental
US**
