



- FLOOR FRAMING NOTES
- DESIGN FLOOR LIVE LOADS: 150 PSF U.O.
 - TYP. FLOOR CONSTRUCTION: 10" CONCRETE SLAB OVER CONCRETE BEAMS.
 - TOP OF SLAB ELEVATION (T.O.S.) = 166'-1 1/8" U.O. SEE ARCHITECTURAL AND MECHANICAL DRAWINGS FOR MINOR SLOPES, C.I.P. CONCRETE CURBS, DRAINS, OPENINGS FOR PIPES AND DUCTS, ETC.
 - (CD) - 3 1/2" LIGHT WEIGHT CONCRETE FILL W/ #4 @ 11" O.C. EA. WAY OVER 2" COMPOSITE METAL DECK. OVERALL THICKNESS=5 1/2"
 - SEE SHEET 8SF601 FOR CONCRETE BEAM SCHEDULE.
 - SEE SHEETS 8SF610 & 8SF611 FOR COLUMN SCHEDULES.
 - SEE SHEET 8SB001 FOR STRUCTURAL NOTES AND LEGEND.
 - SEE SHEET 8SF201 FOR WALLS.
 - LAP ALL TOP AND BOTTOM SLAB REINFORCING FOR A FULL TENSION LAP. SEE SHEET 8SF001 FOR LENGTHS.
 - (PR)-PERIPHERAL TIE REINFORCING. SEE 13/8SF503. SEE 5/8SF504 FOR (PR) IN COMPOSITE METAL DECK SLABS.
 - SEE 4/8SB504 FOR CATWALK FRAMING AT MECHANICAL UNITS.
 - FIELD VERIFY ALL EXISTING DIMENSIONS AND ELEVATIONS.
 - SEE ELEVATIONS ON SHEETS 8SF203 & 8SF204 FOR (E) MASONRY WALL LINTELS, WINDOW PLATE FRAMES AND BACK UP TUBES.

CONSULTANTS:

DESMAN ASSOCIATES / PARKING
CODE CONSULTANTS, INC. / CODE CONSULTANT
THE SEXTANT GROUP / AV & ACOUSTICAL
HAMMER DESIGN ASSOCIATES / FOOD SERVICE
PYBURN & ODOM / ABATEMENT
TATA & HOWARD / TANK CONSULTANT
I.S.C. GROUP, INC. / IRRIGATION
DAN EUSER WATER ARCHITECTURE, INC. / WATER FEATURE



ARCHITECT/ENGINEERS:

studio **NOVA**
SCHRENK & PETERSON CONSULTING ENGINEERS / CIVIL
KORDA/NEMETH ENGINEERING / STRUCTURAL
BR+A CONSULTING ENGINEERS / MECH, ELECT, PLUMBING, LOW VOLTAGE
ARCHITECTURAL ENGINEERING / PLUMBING
SCALES ASSOCIATES / FIRE PROTECTION
COMMUNICATIONS DESIGN GROUP / LOW VOLTAGE

DRAWING TITLE
BLDG 8 LEVEL 5 FLOOR FRAMING PLAN

APPROVED: PROJECT DIRECTOR

Yadda Jandera

PROJECT TITLE
SLVHCS REPLACEMENT MEDICAL
CENTER PROJECT

LOCATION
NEW ORLEANS, LOUISIANA

DATE
July 16, 2012

CHECKED
TMD

DRAWN
RJC

PROJECT NUMBER
629-HS2-401

DOCUMENT SET PACKAGE
WP_09B

DRAWING NUMBER

8SF105

OFFICE OF
CONSTRUCTION
AND FACILITIES
MAINTENANCE

