

ONE INCH = FORTY FEET (1" = 40')

ONE INCHES = ONE FOOT

ONE AND ONE HALF INCHES = ONE FOOT

THREE QUARTERS INCH = ONE FOOT

ONE HALF INCH = ONE FOOT

ONE QUARTER INCH = ONE FOOT

ONE EIGHT INCH = ONE FOOT

ONE SIXTEENTH INCH = ONE FOOT

FINISH CODE	FINISH TYPE	MANUFACTURER	MODEL NUMBER	COLOR	COMMENTS
CARPET TILE	SPEC SECTION 09 68 00				
CPT-1	CARPET TILE SPEC SECTION 09 68 00				
CPT-2	CARPET TILE SPEC SECTION 09 68 00				
CPT-4	CARPET TILE SPEC SECTION 09 68 00				
CERAMIC TILE / PORCELAIN TILE FLOOR	SPEC SECTION 09 30 13				
CTF-1	CERAMIC TILE / PORCELAIN TILE FLOOR SPEC SECTION 09 30 13	STONEPEAK CERAMICS	MATERIA 3D COLLECTION UNGLAZED 12" X 24" X 3/8" NOMINAL TILE - PORCELAIN	HEATHER GREY HONED USH1224080	TO BE USED WITH GT-1 GROUT
CTF-2	CERAMIC TILE / PORCELAIN TILE FLOOR SPEC SECTION 09 30 13	STONEPEAK CERAMICS	MATERIA 3D COLLECTION UNGLAZED 12" X 24" X 3/8" NOMINAL TILE - PORCELAIN	PLATINUM HONED USH1224083	TO BE USED WITH GT-1 GROUT
CTF-5	CERAMIC TILE / PORCELAIN TILE FLOOR SPEC SECTION 09 30 13	GRANITI FIANDRE	GEOLOGICA COLLECTION NEW STONE 12" X 24" X 1" FLOOR TILE - PORCELAIN	AS4236 PIETRA SERENA HONED FINISH	TO BE USED WITH GT-4 GROUT. USED IN RESEARCH BUILDING ONLY
FLOOR ACCESSORY	SPEC SECTION 09 30 13				
FA-3	FLOOR ACCESSORY SPEC SECTION 09 30 13	TM MARBLE SUPPLY	1/8" ZINC DIVIDER STRIP		TO BE USED WITH CERAMIC TILE FLOORING
FLOOR ACCESSORY	SPEC SECTION 09 68 00				
FA-1	FLOOR ACCESSORY SPEC SECTION 09 68 00	JOHNSONITE	TRANSITION STRIP	20 CHARCOAL	TO BE USED IF CARPET IS COOL IN COLOR
FA-2	FLOOR ACCESSORY SPEC SECTION 09 68 00	JOHNSONITE	TRANSITION STRIP	167 FUDGE	TO BE USED IF CARPET IS WARM IN COLOR
RESINOUS FLOORING	SPEC SECTION 09 67 25				
RES-1	RESINOUS FLOORING SPEC SECTION 09 67 25	STONHARD	STONTEC ERF 1/16" FLAKE	CUSTOM COLOR V-TEC-92C	LIGHT WARM GRAY
RES-2	RESINOUS FLOORING SPEC SECTION 09 67 25	STONHARD	STONTEC ERF 1/16" FLAKE	CUSTOM COLOR V-TEC-92E	DARK WARM GRAY
SEALED CONCRETE	SPEC SECTION 09 91 00 - PAINT				
SCONC	SEALED CONCRETE SPEC SECTION 09 91 00 - PAINT				
SHEET VINYL	SPEC SECTION 09 65 16				
SV-1	SHEET VINYL SPEC SECTION 09 65 16	MANNINGTON	BIOSPEC MD 2.03MM HEAT-WELDED	15246 BRIGHT WHITE	USE WR-1
SV-2	SHEET VINYL SPEC SECTION 09 65 16	MANNINGTON	BIOSPEC MD 2.03MM HEAT-WELDED	15162 ECRU	USE WR-2
SHEET VINYL WELDING ROD	SPEC SECTION 09 65 16				
WR-1	SHEET VINYL WELDING ROD SPEC SECTION 09 65 16	MANNINGTON	BIOSPEC MD	15246 BRIGHT WHITE	CAMO# 415146
WR-2	SHEET VINYL WELDING ROD SPEC SECTION 09 65 16	MANNINGTON	BIOSPEC MD	15362 ECRU	CAMO# 415162
TERRAZZO TILE	SPEC SECTION 09 66 16				
TT-1	TERRAZZO TILE SPEC SECTION 09 66 16	MATS INC	FLOORAZZO MARBLE 2" X 2" TILE WITH FUSION SEAM	1990 GLACIER	USED IN ELEVATOR CABS
TRAFFIC COATING	SPEC SECTION 07 18 15				
TC-1	TRAFFIC COATING SPEC SECTION 07 18 15	TRAFFIC COATING			
VINYL COMPOSITION TILE	SPEC SECTION 09 65 19				
VCT-1	VINYL COMPOSITION TILE SPEC SECTION 09 65 19	MANNINGTON	SOLID POINT PREMIUM TILE 12" X 12" VCT	317 COOL BEIGE	
VCT-2	VINYL COMPOSITION TILE SPEC SECTION 09 65 19	MANNINGTON	SOLID POINT PREMIUM TILE 12" X 12" VCT	313 PRAIRIE	
VCT-3	VINYL COMPOSITION TILE SPEC SECTION 09 65 19	MANNINGTON	SOLID POINT PREMIUM TILE 12" X 12" VCT	319 SUEDE	
WALK OFF GRID	SPEC SECTION 12 48 16				
FG-1	WALK OFF GRID SPEC SECTION 12 48 16	C/S GROUP	PEDISYSTEMS PEDIGRID-SA G8	ALUMINUM CLEAR FINISH	

FINISH CODE	FINISH TYPE	MANUFACTURER	MODEL NUMBER	COLOR	COMMENTS
CERAMIC TILE / PORCELAIN TILE BASE	SPEC SECTION 09 30 13				
CTB-1	CERAMIC TILE / PORCELAIN TILE BASE SPEC SECTION 09 30 13	STONEPEAK CERAMICS	MATERIA 3D COLLECTION UNGLAZED - 4" X 24" X 3/8" NOMINAL PORCELAIN TILE; FACTORY CUT TO 4" W/ FINISHED BULLNOSE EDGE	COLOR: HEATHER GRAY HONED FINISH USH0624080	TO BE USED WITH GROUT GT-1
CTB-2	CERAMIC TILE / PORCELAIN TILE BASE SPEC SECTION 09 30 13	STONEPEAK CERAMICS	MATERIA 3D COLLECTION UNGLAZED - 4" X 24" X 3/8" NOMINAL PORCELAIN TILE; FACTORY CUT TO 4" W/ FINISHED BULLNOSE EDGE	COLOR: PLATINUM HONED FINISH USH0624083	TO BE USED WITH GROUT GT-1
CTB-4	CERAMIC TILE / PORCELAIN TILE BASE SPEC SECTION 09 30 13	STONEPEAK CERAMICS	SKY COLLECTION UNGLAZED - 4" X24" X 3/8" NOMINAL PORCELAIN TILE	COLOR: GREENSKY HONED USG0624107	TO BE USED WITH GROUT GT-4
INTEGRAL BASE	SPEC SECTION 09 65 16				
ICB-4	INTEGRAL BASE SPEC SECTION 09 65 16	INTEGRAL COVED BASE	4"		
ICB-6	INTEGRAL BASE SPEC SECTION 09 65 16	INTEGRAL COVED BASE	6"		
INTEGRAL BASE RESINOUS	SPEC SECTION 09 67 25				
RESB-4	INTEGRAL BASE RESINOUS SPEC SECTION 09 67 25	INTEGRAL COVED BASE	4"		
RESB-6	INTEGRAL BASE RESINOUS SPEC SECTION 09 67 25	INTEGRAL COVED BASE	6"		
RUBBER BASE	SPEC SECTION 09 65 13				
RB-1	RUBBER BASE SPEC SECTION 09 65 13	JOHNSONITE	4" COVE BASE	#179 STEEL	TO BE USED AT SHEET AND VCT FLOORING
RB-2	RUBBER BASE SPEC SECTION 09 65 13	JOHNSONITE	4" STRAIGHT BASE	#179 STEEL	TO BE USED AT CARPET FLOORING
STAINLESS STEEL BASE	SPEC SECTION 05 70 50				
SSB-1	STAINLESS STEEL BASE SPEC SECTION 05 70 50	16 GAUGE #304 STAINLESS STEEL	4"		REFERENCE DETAIL C2/C3/D2/D3 SHEET 0A1515
SSB-2	STAINLESS STEEL BASE SPEC SECTION 05 70 50	16 GAUGE #304 STAINLESS STEEL	6"		REFERENCE DETAIL C2/C3/D2/D3 SHEET 0A1515

RFI 7852 confirmed that at locations where there is 6" tall base and base cabinets with a 4" toe kick, it is acceptable that the 6" base be used in the room and the 6" base be turned down to 4" base at the casework's toe kick.

REVISIONS:	DATE	CONSULTANTS:
		DESMAN ASSOCIATES / PARKING
		CODE CONSULTANTS, INC. / CODE CONSULTANT
		THE SEXTANT GROUP / AV & ACOUSTICAL
		HAMMER DESIGN ASSOCIATES / FOOD SERVICE
		PYBURN & ODOM / ABATEMENT
		TATA & HOWARD / TANK CONSULTANT
		I.S.C. GROUP, INC. / IRRIGATION
		DAN EUSER WATER ARCHITECTURE, INC. / WATER FEATURE



ARCHITECT/ENGINEERS:

studio **NOVA**

SCHRENK & PETERSON CONSULTING ENGINEERS / CIVIL  
KORDA/NEMETH ENGINEERING / STRUCTURAL  
BR+A CONSULTING ENGINEERS / MECH. ELECT, PLUMBING, LOW VOLTAGE  
ARCHITECTURAL ENGINEERING / PLUMBING  
SCALES ASSOCIATES / FIRE PROTECTION

DRAWING TITLE	FINISH LEGEND - PART A	PROJECT TITLE	SLVHCS REPLACEMENT MEDICAL CENTER PROJECT	PROJECT NUMBER	100342.00	BUILDING NUMBER	08	OFFICE OF CONSTRUCTION AND FACILITIES MANAGEMENT
APPROVED: PROJECT DIRECTOR	<i>Yadda Sanders</i>	LOCATION	NEW ORLEANS, LOUISIANA	DOCUMENT SET PACKAGE	WP_09B	DRAWING NUMBER	8AF602	
		DATE	July 16, 2012	CHECKED	JR	DRAWN	AN	
								Department of Veterans Affairs

FINISH CODE	CEILING TYPE	MANUFACTURER	MODEL NUMBER	COLOR	COMMENTS
ACOUSTICAL CEILING TILE	SPEC SECTION 09 51 00				
AT-1	ACOUSTICAL CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	#3257 OPTIMA OPEN PLAN SQUARE TEGULAR 2' X 4' X 1" W/ 9/16" GRID	WHITE	
AT-3	ACOUSTICAL CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	#1776 DUNE BEVELED TEGULAR 2' X 4' X 5/8" W/ 15/16"	WHITE	
AT-4	ACOUSTICAL CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	#1773 DUNE SQUARE LAY-IN 2' X 4' X 5/8" W/ 15/16" GRID	WHITE	
AT-7	ACOUSTICAL CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	# 3265 OPTIMA PLANK SQUARE TEGULAR 24" X 60" X1"	WHITE	
ACOUSTICAL CEILING TILE SPECIAL	SPEC SECTION 09 51 00				
ATSP-1	ACOUSTICAL CEILING TILE SPECIAL SPEC SECTION 09 51 00	ARMSTRONG	#1716 CLEAN ROOM MYLAR 24" X 48" X 3/4" SQUARE LAY-IN FIELD TILE WITH #1721 BORDER PANELS WITH 15/16" ALUMINUM CLEAN ROOM GRID SYSTEM	WHITE	
EXPOSED/EXPOSED PAINTED	SPEC SECTION 09 91 00				
EXPP	EXPOSED/EXPOSED PAINTED SPEC SECTION 09 91 00				EXPOSED PAINTED
EXP	EXPOSED/EXPOSED PAINTED SPEC SECTION 09 91 00				EXPOSED
GYPSUM WALLBOARD PAINTED	SPEC SECTION 09 91 00				
GWB	GYPSUM WALLBOARD PAINTED SPEC SECTION 09 91 00				EGGSHELL PAINT
GYPSUM WALLBOARD SPECIAL COATING	SPEC SECTION 09 91 00				
GWBC	GYPSUM WALLBOARD SPECIAL COATING SPEC SECTION 09 91 00				EPOXY PAINT
METAL CEILING	SPEC SECTION 09 54 23				
MC-1	METAL CEILING SPEC SECTION 09 54 23	ALPRO ACOUSTICAL SYSTEMS (GORDON)	ACOUSTICAL CEILING BAFFLES .032" SMOOTH SURFACE ACOUSTICAL CEILING FLAT BAFFLE PANEL W/ ACROGUARD FINISH WITH ACOUSTICAL BACKING	ASTI II - PDR-308 11	INSTALLED USING EYEBOLTS SUSPENDED PANEL INSTALLATION. PANEL DIMENSIONS AS INDICATED ON ROPS. LENGTH NOT TO EXCEED 120"