

ONE INCH = FORTY FEET (1" = 40')

ONE INCHES = ONE FOOT

ONE AND ONE HALF INCHES = ONE FOOT

THREE QUARTERS INCH = ONE FOOT

ONE HALF INCH = ONE FOOT

ONE QUARTER INCH = ONE FOOT

ONE EIGHT INCH = ONE FOOT

ONE SIXTEENTH INCH = ONE FOOT

FINISH CODE	FINISH TYPE	MANUFACTURER	MODEL NUMBER	COLOR	COMMENTS
CABINET PULL SPEC SECTION 06 40 00					
H-2	CABINET PULL SPEC SECTION 06 40 00	EPCO - ENGINEERED PRODUCT CO	MC402-3-SS SATIN STAINLESS BAR PULL	OVERALL LENGTH +/- 3'	MOUNTS HORIZONTAL AT CABINET DOORS, CASEWORK AT CLINICAL AREAS AND BACK OF HOUSE
H-2A	CABINET PULL SPEC SECTION 06 40 00	EPCO - ENGINEERED PRODUCT CO	MC402-8-SS SATIN STAINLESS BAR PULL	OVERALL LENGTH +/- 8'	MOUNTS HORIZONTAL AT CABINET DRAWERS, CASEWORK AT CLINICAL AREAS AND BACK OF HOUSE
EPOXY RESIN COUNTERTOPS SPEC SECTION 12 36 00					
EXR-1	EPOXY RESIN COUNTERTOPS SPEC SECTION 12 36 00	RFI 7151: KEWAUNEE	GREENSTONE	WHITE RFI 7151:BLACK	HISTOLOGY LAB BENCH; REPAIR SHOP
EXPANSION JOINT COVER ASSEMBLIES SPEC SECTION 07 95 13					
EJCA-1	EXPANSION JOINT COVER ASSEMBLIES SPEC SECTION 07 95 13				
GROUT SPEC SECTION 09 30 13					
GT-1	GROUT SPEC SECTION 09 30 13	LATICRETE	LATICRETE SPECTRALOCK PRO OR SIMILAR	#78 STERLING SILVER	TO BE USED WITH CTF-2, CTB-2
GT-3	GROUT SPEC SECTION 09 30 13	LATICRETE	LATICRETE SPECTRALOCK PRO OR SIMILAR	#18 SAUTERNE (WHITE)	TO BE USED WITH CT-1, CT-1A, CT-7, FTCT-1, FTCT-2, FTCT-3, FTCT-4, FTCT-5, FTCT-6, FTCT-7, FTCT-8, FTCT-9, FTCT-10, FTCT-11
GT-4	GROUT SPEC SECTION 09 30 13	LATICRETE	LATICRETE SPECTRALOCK PRO OR SIMILAR	#24 NATURAL GRAY (TAUPE)	TO BE USED WITH CTF-1, CTB-1, CT-5, CTB-4
GT-5	GROUT SPEC SECTION 09 30 13	LATICRETE	LATICRETE SPECTRALOCK PRO OR SIMILAR	#24 NATURAL GRAY (TAUPE)	TO BE USED WITH CTF-1, CTB-1, CT-5, CTB-4
LAMINATED GLASS SPEC SECTION 08 80 10					
LAM GL-1	LAMINATED GLASS SPEC SECTION 08 80 10	VIRACON	9/16" CLEAR LAMINATED GLASS	9/16" CLEAR LAMINATED HS/HS	1/4" (6MM) CLEAR HS -.060 (1.52MM) CLEAR PVB - 1/4" (6MM) CLEAR HS
LAM GL-2	LAMINATED GLASS SPEC SECTION 08 80 10	VIRACON	9/16" FROSTED LAMINATED GLASS	9/16" CLEAR SF-41 LAMINATED HS/HS	1/4" (6MM) CLEAR ACID ETCHED 41 #1 HS -.060 (1.52MM) CLEAR PVB - 1/4" (6MM) CLEAR HS
LAM GL-10	LAMINATED GLASS SPEC SECTION 08 80 10	FORMS & SURFACES	VIVICHROME SCRIBE	PEARLEX FINISH WITH MAGNETIC CONFIGURATION	3/8" THICKNESS
PLASTIC LAMINATE SPEC SECTION 06 40 00					
PLAM-1	PLASTIC LAMINATE SPEC SECTION 06 40 00	LAMINART PEARLESENCE	PEARLESENCE	2421T SNOWCAP	USE OYSTER SHIELD WHEN USED ON HORZ APPLICATION, USE CANPLAST EDGE BANDING CP1 1460 TL FROSTY WHITE
PLAM-2	PLASTIC LAMINATE SPEC SECTION 06 40 00	LAMINART PEARLESENCE	PEARLESENCE	2430T NATURAL SILK	USE OYSTER SHIELD WHEN USED ON HORZ APPLICATION, USE DOELLEN-WOODTAPE EDGE BANDING 7400 SANDCASTLE
PLAM-4	PLASTIC LAMINATE SPEC SECTION 06 40 00	LAMINART	VENEER - ART	975 AMBER BAMBOO	
PLAM-6	PLASTIC LAMINATE SPEC SECTION 06 40 00	WILSONART	MARKERBOARD LAMINATE	1573-09 FROSTY WHITE	
PLAM-7	PLASTIC LAMINATE SPEC SECTION 06 40 00	LAMINART PEARLESENCE	PEARLESENCE	2451T SHADOW	USE OYSTER SHIELD WHEN USED ON HORZ APPLICATION, USE CANPLAST EDGE BANDING CP1 1460 TL FROSTY WHITE
SHOWER CURTAIN SPEC SECTION 10 28 00					
SC-1	SHOWER CURTAIN SPEC SECTION 10 28 00	STANDARD TEXTILE	POLYESTER FABRIC SHOWER CURTAIN: SUPREME WAFFLE WA4030SU	WHITE	STAINLESS GROMMETS, STAINLESS HOOKS AND CLEAR LINER
SOLID SURFACE SPEC SECTION 06 61 16					
S-1	SOLID SURFACE SPEC SECTION 06 61 16	DUPONT CORIAN	CORIAN 1/2" THICK SOLID SURFACE	GLACIER WHITE	TYPICAL SOLID SURFACE COUNTERTOP
S-3	SOLID SURFACE SPEC SECTION 06 61 16	DUPONT CORIAN	CORIAN 1/2" THICK SOLID SURFACE	MEDEA	CONCOURSE BENCHES
STONE SPEC SECTION 06 61 16					
ST-1	STONE SPEC SECTION 06 61 16	DIFINITI QUARTZ	ENLIGHTEN COLLECTION 1 1/8" THICK SOLID SURFACE	PEARL	
WINDOW SHADE TREATMENT SPEC SECTION 12 24 13					
WTS-1	WINDOW SHADE TREATMENT SPEC SECTION 12 24 13	MECHO SHADE	EUROTWILL 3% OPENESS MANUAL	6018 STONE	OWNER PROVIDED
WTS-3	WINDOW SHADE TREATMENT SPEC SECTION 12 24 13	MECHO SHADE	EUROTWILL 3% OPENESS WITH BLACKOUT SHADE MANUAL	6018 STONE	OWNER PROVIDED
X - DOOR FINISHES DOOR GLAZING SPECIFICATION 08 80 10					
D LAM GL-1	X - DOOR FINISHES DOOR GLAZING SPECIFICATION 08 80 10	VIRACON	1/4" CLEAR LAMINATED GLASS (FOR DOORS & RELITES)	1/4" CLEAR LAMINATED HS/HS	1/8" (3MM) CLEAR HS -.060 (1.52MM) CLEAR PVB - 1/8" (3MM) CLEAR HS
D LAM GL-2	X - DOOR FINISHES DOOR GLAZING SPECIFICATION 08 80 10	VIRACON	1/4" FROSTED LAMINATED GLASS (FOR DOORS & RELITES)	1/4" CLEAR SF-41 LAMINATED HS/HS	1/8" (3MM) CLEAR ACID-ETCHED 41 #1 HS -.060 (1.52MM) CLEAR PVB - 1/8" (3MM) CLEAR HS
X - DOOR FINISHES SPEC SECTION 08 14 00					
D WD-1	X - DOOR FINISHES SPEC SECTION 08 14 00	BROOKSIDE VENEERS	BROOKLINE RIFT WHITE OAK 112-00/Y-17	POLYURETHANE CLEAR FINISH, STAINED TO MATCH ARCHITECTS CONTROL SAMPLE	TYP WOOD VENEER FOR DOORS UNO; GRAIN TO BE ORIENTED VERTICALLY; STAINED WITH 'GOLDEN OAK' SHERWIN-WILLIAMS MINWAX WOOD FINISH
X - DOOR FINISHES SPEC SECTION 09 91 00					
D HM-1	X - DOOR FINISHES SPEC SECTION 09 91 00		HOLLOW METAL DOORS & FRAMES PAINTED TO MATCH ADJACENT WALL	PAINT DOOR & FRAME TO MATCH ADJACENT WALL	HOLLOW METAL DOORS
X - OPERABLE PARTITION FINISHES SPEC SECTION 10 23 26					
OP-1	X - OPERABLE PARTITION FINISHES SPEC SECTION 10 23 26	DESIGN TEX FOR MODERNFOLD	KENTUCKY DERBY II OPERABLE PARTITION POLYOLEFIN FABRIC	SHETLAND 111873-506	

FINISH CODE	FINISH TYPE	MANUFACTURER	MODEL NUMBER	COLOR	COMMENTS	
DOC-FIN-KEY-ALT						
Replaces Base Bid Item	Alternate	Alt Finish Type	Alt Finish Manufacturer	Alt Model Number	Alt Finish Color	Alt Finish Comments
8.11	ADD ALTERNATE FOR FLOOR ACCESSORY SPEC SECTION 09 65 16, 09 68 06, 09 66 23					
A FA-4	8.11 ADD ALTERNATE FOR FLOOR ACCESSORY SPEC SECTION 09 65 16, 09 68 06, 09 66 23	TM MARBLE SUPPLY	1/4" ZINC DIVIDER STRIP			TO BE USED WITH TERRAZZO FLOORING
A FA-5	8.11 ADD ALTERNATE FOR FLOOR ACCESSORY SPEC SECTION 09 65 16, 09 68 06, 09 66 23	TM MARBLE SUPPLY	1/2" ZINC DIVIDER STRIP			TO BE USED WITH TERRAZZO FLOORING
8.12 ADD ALTERNATE FOR CEILING TILE SPEC SECTION 09 51 00						
AT-2	8.12 ADD ALTERNATE FOR CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	1915HRC ULTIMA BEVELED TEGULAR 2' X 4' X 3/4" WITH 9/16" GRID	WHITE		
AT-3	8.12 ADD ALTERNATE FOR CEILING TILE SPEC SECTION 09 51 00	ARMSTRONG	1914HRC ULTIMA BEVELED TEGULAR 2' X 4' X 3/4" WITH 15/16" GRID	WHITE		
9.04 ADD ALTERNATE FOR TERRAZZO TILE BASE IN LIEU OF CERAMIC TILE BASE SPEC SECTION 09 30 13						
CTB-1	9.04 ADD ALTERNATE FOR TERRAZZO TILE BASE IN LIEU OF CERAMIC TILE BASE SPEC SECTION 09 30 13	MATS INC	4" H X 24" WIDE TERRAZZO TILE BASE			TO MATCH A TT-1
CTB-2	9.04 ADD ALTERNATE FOR TERRAZZO TILE BASE IN LIEU OF CERAMIC TILE BASE SPEC SECTION 09 30 13	MATS INC	4" H X 24" WIDE TERRAZZO TILE BASE			TO MATCH A TT-2
9.04 ADD ALTERNATE FOR TERRAZZO TILE IN LIEU OF CERAMIC TILE FLOORING SPEC SECTION 09 66 16						
CTF-1	9.04 ADD ALTERNATE FOR TERRAZZO TILE IN LIEU OF CERAMIC TILE FLOORING SPEC SECTION 09 66 16	MATS INC	FLOORAZZO TILE 24" X 48" TILE PANEL	RESIN PIGMENT: BONE WHITE 210		CONTROL SAMPLE - 20% MOCHA #1, 25% MOCHA #2, 10% GEORGIA WHITE #1, 25% AMBER #0, 20% AMBER #1 - FIELD SEALED WITH HILLYARD TERRAZINE AND FIELD-FINISHED WITH HILLYARD NORTH STAR
CTF-2, CTF-2A	9.04 ADD ALTERNATE FOR TERRAZZO TILE IN LIEU OF CERAMIC TILE FLOORING SPEC SECTION 09 66 16	MATS INC	FLOORAZZO TILE 24" X 48" TILE PANEL	RESIN PIGMENT: BONE WHITE 210		CONTROL SAMPLE - 15% AMER #0, 30% AMBER #1, 25% MOCHA #1, 20% MOCHA #2, 10% GEORGIA WHITE #1 - FIELD SEALED WITH HILLYARD TERRAZINE AND FIELD-FINISHED WITH HILLYARD NORTH STAR
ACCEPTABLE EQUALS FOR CARPET TILE SPEC SECTION 09 68 00						
A1 CPT-1	ACCEPTABLE EQUALS FOR CARPET TILE SPEC SECTION 09 68 00	SHAW	CATALYST TILE 59579	TORTOISE SHELL		ALTERNATE 1 FOR CPT-1
A2 CPT-1	ACCEPTABLE EQUALS FOR CARPET TILE SPEC SECTION 09 68 00	LEES	ANALOGUE TILE 959	50111-F7983 MATE		ALTERNATE 2 FOR CPT-1

ADD ALTERNATES 8 10 (RUBBER FLOOR ILO SHEET VINYL) AND 8 XX (VET ILO VCT) WERE DELETED FROM THIS SCHEDULE IN ADDENDUM 3 - POST-BID.

REVISIONS:	DATE
3 Addendum #3 - Post-Bid	7/3/2013

CONSULTANTS:
 DESMAN ASSOCIATES / PARKING
 CODE CONSULTANTS, INC. / CODE CONSULTANT
 THE SEXTANT GROUP / AV & ACOUSTICAL
 HAMMER DESIGN ASSOCIATES / FOOD SERVICE
 PYBURN & ODOM / ABATEMENT
 TATA & HOWARD / TANK CONSULTANT
 I.S.C. GROUP, INC. / IRRIGATION
 DAN EUSER WATER ARCHITECTURE, INC. / WATER FEATURE



ARCHITECT/ENGINEERS:
 studio NOVA
 SCHRENK & PETERSON CONSULTING ENGINEERS / CIVIL
 KORDA/NEMETH ENGINEERING / STRUCTURAL
 BR+A CONSULTING ENGINEERS / MECH, ELECT, PLUMBING, LOW VOLTAGE
 ARCHITECTURAL ENGINEERING / PLUMBING
 SCALES ASSOCIATES / FIRE PROTECTION

DRAWING TITLE FINISH LEGEND - PART C	PROJECT TITLE SLV/HCS REPLACEMENT MEDICAL CENTER PROJECT	PROJECT NUMBER 100342.00	BUILDING NUMBER 08	OFFICE OF CONSTRUCTION AND FACILITIES MANAGEMENT Department of Veterans Affairs
APPROVED: PROJECT DIRECTOR	LOCATION NEW ORLEANS, LOUISIANA	DOCUMENT SET PACKAGE WP_09B	DRAWING NUMBER 8AF604	
	DATE July 16, 2012	CHECKED JR	DRAWN AN	