

DATE: June 7, 2012

FROM: The Schemmer Associates  
1044 North 115th Street  
Omaha, Nebraska 68154-4436  
Phone: (402) 493-4800  
Telefax: (402) 493-7951

TO: Prospective Bidders and Plan Holders

RE: Addendum No. 4 to the Bidding Documents for:  
Women's Clinic Within Existing Hospital  
VA Project No. 636A6-11-308  
Schemmer Project No. 06054.002

This addendum is issued by the Architect to the Contractor. This Addendum shall be made a part of the Contract Documents. Acknowledge receipt of this Addendum shall be provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

Prior approval of manufacturers is a general approval only for bidding purposes. Final approval of the products is contingent upon the submittal of product data and/or shop drawings which will have to meet the specific design requirements and the specifications.

This addendum consists of five (5) pages of written addendum items.

THE SCHEMMER ASSOCIATES INC.  
ARCHITECTS | ENGINEERS | PLANNERS

# **PROJECT MANUAL**

## **ARCHITECTURAL**

### **Item No. SA-1:**

#### **Question:**

What are the finish selections?

#### **Answer:**

Please replace existing Section 09 06 00 Schedule for Finishes with the updated Section for clarification of finish selection.

## **DRAWINGS**

### **ELECTRICAL**

#### **Item No. DE-1, Sheet :**

#### **Question:**

The prints call out for all cabling to originate in room 114. It should state that the cabling should originate in the telecom room located in the Red Gold area.

The drawings do not state that all computer cable rough-in must be piped complete to the cable tray, with grounding bushing and the conduit must be ground bonded to the cable tray.

All sleeves should have grounding bushings and they should be grounded to the cable tray

What is meant by "Provide Bushed Conduit Sleeve through Wall Going To Structure", The term "STRUCTURE" is the key work?

#### **Answer:**

Delete all references to conduit sleeves for the telecom cabling and termination of cables in room 114. The cabling shall originate in the Telecom Room 1411 in the Blue/White area. All the rough-ins from each of the telecom outlets shall be piped complete to the main corridor cable tray. Provide a grounding bushing and bond each rough-in to the tray. The VA will provide additional patch panel as necessary.