

AMENDMENT NO. A00005

Solicitation VA261-17-B-0393

**Project 654-16-621
Building 7 Renovation**

General

The following changes, additions or deletions shall be made to the following Contract Documents.
All other conditions shall remain the same.

1. SPECIFICATIONS
 - a. N/A
2. DRAWINGS
 - a. N/A
3. BIDDER QUESTIONS AND CLARIFICATIONS
 - a. Question: *Excuse the late question on Building 7. I have had a question asked and also a clarification presented as an add alternate, both for the same subject. That has generated my question. Drawing 7-MD-1.1 the note for the piping in the trench is to remove all piping and a permit is required for confined space to complete the removal. Drawing 7-AD-1.1 note 29 further defines demolition items, and Drawing -AE-1.2 states the trench is to be filled with concrete. Are there design details showing the length and cross sectional area of the trench? Demolition subcontractor and the mechanical subcontractor have questioned me.*
 - b. Response: The tunnel between Building 7 and the Boiler plant is NOT to be filled in with concrete. After the demolition work is complete, the end of the tunnel will be closed off with a new CMU wall at the opening to the vertical shaft within the Building 7. The vertical shaft will be back-filled and a 6" thick concrete slab will be constructed such that it is flush with the existing floor slab. Please refer to sheets 7-AE-1.3, 7-AE-3.1, 7-SF2.1, detail 1/ 7-SS3.1, detail 14/7-SS0.3. Please refer to the remainder of the architectural, structural, and mechanical drawings.

I'm not sure which note you are referring to on sheet 7-AE-1.2, but I'm guessing that you are looking at some notes that are in reference to filling in an old utility trench in Room N 219, and an existing recess in the floor for an old floor scale, (scale pit), located in Room N 218. These rooms are actually found on sheet 7-AE-1.3.

-END OF AMENDMENT NO. A00005-