



FIRE PROTECTION MATERIAL LIST

THE SYMBOLS AND THE MATERIAL LIST ARE FOR THE CONVENIENCE OF THE CONTRACTOR. CONTRACTOR SHALL VERIFY QUANTITIES AND FURNISH ALL MATERIALS REQUIRED FOR FULLY OPERATIVE SYSTEMS, WHETHER SPRINKLER OR NOT.

CATALOG NUMBERS SHALL NOT BE CONSIDERED COMPLETE, BUT ARE GIVEN AS AN AID TO THE CONTRACTOR AND TO INDICATE THE QUALITY REQUIRED. CONTRACTOR IS RESPONSIBLE FOR COMPLETE DESCRIPTION OF MATERIAL ON THESE DRAWINGS AND IN THE SPECIFICATIONS BEFORE ORDERING. THE DESCRIPTION OF THE MATERIAL TAKES PRECEDENCE OVER THE CATALOG NUMBER. THE FIRST LISTED MANUFACTURER IS THE BASIS OF DESIGN.

ADW-1

DESCRIPTION: AUTOMATIC DRIP VALVE, 175 PSI, BRASS BAR, STAINLESS STEEL SPRING AND RETAINING RING, CLOSING PRESSURE 13.5 PSI WITH INCREASING PRESSURE, OPENING PRESSURE 12.5 PSI WITH DECREASING PRESSURE, 1/2" NPT INLET AND 1/4" NPT DRAIN OUTLET.

MANUFACTURER & CATALOG NO.: VIKING B-1, TYCO AD-1, RELIABLE C.

OK-1

DESCRIPTION: 1/2"-1/2" TO 1/2" SIZE CHECK VALVE, 175 PSI, FLANGED OR GROoved, IRON BODY, BRONZE MOUNTED, BRONZE SEAT RING AND RUBBER CALPAC FACING, SWEET TYPE, UL/FM.

MANUFACTURER & CATALOG NO.: VIKING D-1/J-1, TYCO CV-2, RELIABLE D OR K, KENNEDY 125A OR 425.

FDC-1

DESCRIPTION: EXPOSED FIRE DEPT. INLET CONNECTION, POLISHED CHROME PLATED TWO-WAY INLET BODY WITH DRY CLOSERS, PIN LUG SWIVELS, KNOX STAINLESS STEEL LOCKING FDC CAPS WITH MATCHING THRODS AND CHROME FINISH, POLISHED CHROME PLATED WALL PLATE LABELED "AUTO. SPR." 4" x 2-1/2" x 2-1/2". UL THREADS TO MATCH LOCAL FIRE DEPARTMENT.

CONTRACTOR TO COORDINATE PURCHASE OF KNOX LOCKING CAP WITH LOCAL FIRE DEPARTMENT.

MANUFACTURER & CATALOG NO.: POTTER-ROEMER 5750 SERIES, CROKER 6430 SERIES, GUARDIAN 6124, ELKHART 156.

FDC-2

DESCRIPTION: EXPOSED FIRE STANDING FIRE DEPT. INLET CONNECTION, POLISHED CHROME PLATED TWO-WAY INLET BODY WITH DRY CLOSERS, PIN LUG SWIVELS, KNOX STAINLESS STEEL LOCKING FDC CAPS WITH MATCHING THRODS AND CHROME FINISH, POLISHED CHROME PLATED WALL PLATE LABELED "AUTO. SPR." 4" x 2-1/2" x 2-1/2". UL THREADS TO MATCH LOCAL FIRE DEPT. CONNECTION.

CONTRACTOR TO COORDINATE PURCHASE OF KNOX LOCKING CAP WITH LOCAL FIRE DEPARTMENT.

MANUFACTURER & CATALOG NO.: POTTER-ROEMER 5750 SERIES, CROKER 6510 SERIES, GUARDIAN 6224, ELKHART 15.

HY-1

DESCRIPTION: 1/2"-1/2" HOSE VALVE, ANGLE TYPE, CAST BRASS BODY AND TRIM, RISING STEM, TWO HAND OPERATED HAND WHEEL, KNOX STAINLESS STEEL LOCKING CAPS WITH MATCHING THRODS AND CHROME FINISH. HOSE THREADS TO MATCH LOCAL FIRE DEPARTMENT.

CONTRACTOR TO COORDINATE PURCHASE OF KNOX LOCKING CAP WITH LOCAL FIRE DEPARTMENT.

MANUFACTURER & CATALOG NO.: POTTER-ROEMER 4060, CROKER 9305, ELKHART U-25, KENNEDY 936.

Office of
Construction
and Facilities
Management

 Department of
Veterans Affairs