



LEGEND

EXISTING	PROPOSED
EXISTING DATA IS CALLED OUT USING SLANTED TEXT	PROPOSED DATA IS CALLED OUT USING UPRIGHT TEXT
PROPERTY LINE	PROPERTY LINE
ADJOINING PROPERTY LINE	ADJOINING PROPERTY LINE
RIGHT OF WAY LINE	RIGHT OF WAY LINE
EASEMENT	EASEMENT
SETBACK LINE	SETBACK LINE
SOIL TYPE BOUNDARY	SOIL TYPE BOUNDARY
MINOR CONTOUR	MINOR CONTOUR
MAJOR CONTOUR	MAJOR CONTOUR
CENTERLINE	CENTERLINE
EDGE OF PAVEMENT	EDGE OF PAVEMENT
CURBING	CURBING
FENCE LINE	FENCE LINE
TREE LINE	TREE LINE
GUIDE RAIL	GUIDE RAIL
SANITARY SEWER LINE	SANITARY SEWER LINE
STORM SEWER LINE	STORM SEWER LINE
GAS LINE	GAS LINE
UNDERGROUND TELEPHONE	UNDERGROUND TELEPHONE
UNDERGROUND ELECTRIC	UNDERGROUND ELECTRIC
UNDERGROUND CABLE	UNDERGROUND CABLE
UNDERGROUND LINES	UNDERGROUND LINES
OVERHEAD TELEPHONE	OVERHEAD TELEPHONE
OVERHEAD ELECTRIC	OVERHEAD ELECTRIC
OVERHEAD CABLE	OVERHEAD CABLE
OVERHEAD LINES	OVERHEAD LINES
FIRE SUPPRESSION LINE	FIRE SUPPRESSION LINE
WATER LINE	WATER LINE
MAN DOOR	MAN DOOR
INDUSTRIAL DOOR	INDUSTRIAL DOOR
SIGN	SIGN
IRON PIN	IRON PIN
CONCRETE MONUMENT	CONCRETE MONUMENT
UTILITY POLE	UTILITY POLE
SPOT ELEVATION	SPOT ELEVATION
GAS VALVE	GAS VALVE
WATER VALVE	WATER VALVE
FIRE HYDRANT	FIRE HYDRANT
WATER WELL	WATER WELL
SANITARY CLEANOUT	SANITARY CLEANOUT
SANITARY MANHOLE	SANITARY MANHOLE
STORM MANHOLE	STORM MANHOLE
STORM INLET	STORM INLET
STORM INLET #	STORM INLET #
TREE	TREE
CEDAR	CEDAR
RED OAK	RED OAK

- STEEP SLOPES (15% - 25%)
- VERY STEEP SLOPES (>25%)
- EXISTING FEATURES TO BE DEMO'D

DEMOLITION NOTES

- ALL EXISTING FEATURES IN THE CROSSHATCHED AREA, SHOWN IN BOLD, OR CLOUDED ITEMS SHOWN ON THIS PLAN ARE TO BE DEMOLISHED UNLESS NOTED OTHERWISE.
- THE CONTRACTOR IS RESPONSIBLE FOR THE DEMOLITION, REMOVAL, AND DISPOSAL OF ALL STRUCTURES, (SIDEWALKS, CONCRETE PADS, WALLS, PAVEMENT, UTILITIES, ETC) SO THAT THE PROPOSED SITE IMPROVEMENTS CAN BE CONSTRUCTED. FACILITIES TO BE REMOVED SHALL BE UNDERCUT TO SUITABLE MATERIAL AND BROUGHT TO GRADE WITH SUITABLE COMPACTED FILL MATERIAL PER THE SPECIFICATIONS.
- CONTRACTOR IS RESPONSIBLE FOR THE PROPER DISPOSAL OF ALL CONSTRUCTION WASTE MATERIALS. CONTRACTOR IS RESPONSIBLE FOR OBTAINING ANY AND ALL PERMITS REQUIRED FOR WASTE DISPOSAL AND DEMOLITION.
- CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING THE EXACT LOCATIONS OF UTILITY LINES PRIOR TO THE START OF CONSTRUCTION. THE CONTRACTOR SHALL NOTIFY PA ONE CALL AND THE AFFECTED UTILITY COMPANIES FOR ON-SITE LOCATION OF EXISTING UTILITIES.
- UTILITY LINES NOT IDENTIFIED TO BE RELOCATED AND THAT REQUIRE RELOCATION SHALL BE COORDINATED WITH THE RESPECTIVE UTILITY COMPANY, OWNER AND ARCHITECT.
- CONTRACTOR SHALL SAWCUT ALL PAVEMENT, SIDEWALKS, CONCRETE AND CURBS MARKED TO BE REMOVED AND/OR AS REQUIRED FOR INSTALLATION OF UTILITIES. SAWCUTS SHALL BE STRAIGHT AND NEAT WITHOUT IRREGULARITIES. DAMAGE TO ANY PAVEMENT OR CURB NOT MARKED TO BE REMOVED SHALL BE REPAIRED AT NO COST TO THE OWNER.
- CONTRACTOR IS RESPONSIBLE FOR FOLLOWING ALL APPLICABLE LOCAL, STATE AND FEDERAL REGULATIONS PERTAINING TO THE CONSTRUCTION ACTIVITIES.
- ALL DEMOLITION ACTIVITIES ARE TO BE PERFORMED IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS. DEMOLITION SHALL COMPLY WITH ALL LOCAL, STATE, AND FEDERAL REGULATIONS IN DISPOSING OF DEMOLISHED MATERIALS REMOVED FROM THE SITE.
- CONTRACTOR SHALL ENSURE THAT ALL EROSION AND SEDIMENTATION CONTROL MEASURES ARE IN PLACE PRIOR TO SITE DISTURBANCE.
- CONTRACTOR SHALL PROTECT FROM DAMAGE ALL ITEMS THAT ARE TO REMAIN. DAMAGED ITEMS SHALL BE RESTORED TO EQUAL TO, OR BETTER THAN, EXISTING CONDITIONS AT NO COST TO THE OWNER. SHOULD REMOVAL AND/OR RELOCATION ACTIVITIES DAMAGE FENCING, LIGHTING, STORM INLET STRUCTURES, ETC, THEN THE CONTRACTOR SHALL PROVIDE NEW MATERIALS / STRUCTURES IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. EXCEPT FOR MATERIALS DESIGNATED TO BE RELOCATED ON THIS PLAN, ALL OTHER CONSTRUCTION MATERIALS SHALL BE NEW.
- THE CONTRACTOR SHALL MAINTAIN ALL UTILITY SERVICES TO THE EXISTING BUILDING(S) AT ALL TIMES. UTILITY SERVICES SHALL NOT BE INTERRUPTED WITHOUT APPROVAL AND COORDINATION THROUGH THE OWNER. CONTRACTOR SHALL COORDINATE WITH UTILITY COMPANIES TO RELOCATE UTILITIES (IF REQUIRED) WITH MINIMAL IMPACTS TO THE OWNER.
- THE CONTRACTOR SHALL COORDINATE WITH RESPECTIVE UTILITY COMPANIES PRIOR TO THE REMOVAL AND/OR RELOCATION OF UTILITIES. THE CONTRACTOR SHALL COORDINATE WITH THE UTILITY COMPANY CONCERNING PORTIONS OF WORK WHICH MAY BE PERFORMED BY THE UTILITY COMPANY'S FORCES AND ANY FEES WHICH ARE TO BE PAID TO THE UTILITY COMPANY FOR THEIR SERVICES. THE CONTRACTOR IS RESPONSIBLE FOR PAYING ALL FEES AND CHARGES.
- THE LOCATIONS OF ALL EXISTING UTILITIES SHOWN ON THE PLAN HAVE BEEN DETERMINED FROM THE BEST INFORMATION AVAILABLE AND ARE GIVEN FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THEIR ACCURACY. PRIOR TO THE START OF ANY DEMOLITION ACTIVITY, THE CONTRACTOR SHALL NOTIFY PA ONE CALL AND THE UTILITY COMPANIES FOR ON-SITE LOCATIONS OF EXISTING UTILITIES.
- ALL EXISTING UTILITIES SHOWN ARE NOT TO BE INTERPRETED AS EXACT LOCATIONS OR AS THE ONLY UTILITIES/OBSTACLES THAT MAY BE PRESENT WITHIN THE PROJECT AREA. CONTRACTOR SHALL VERIFY EXISTING CONDITIONS AND PROCEED WITH CAUTION AROUND ANY ANTICIPATED FEATURES. CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES REGARDING DESTRUCTION AND/OR REMOVAL OF ALL SERVICE LINES. CAP ALL LINES BEFORE PROCEEDING WITH THE WORK.
- CONTRACTOR MUST PROTECT THE PUBLIC AT ALL TIMES WITH FENCING, BARRICADES, ENCLOSURES, ETC. CONTRACTOR IS RESPONSIBLE TO SAFEGUARD THE SITE AS NECESSARY TO PERFORM THE WORK AND TO PREVENT UNAUTHORIZED ENTRY WITHIN THE PROJECT AREA.
- CONTRACTOR SHALL PROVIDE TRAFFIC CONTROL AND GENERALLY ACCEPTED SAFE PRACTICES IN CONFORMANCE WITH THE "MANUAL ON UNIFORM TRAFFIC CONTROL", IN ADDITION TO COMPLYING WITH LOCAL, STATE AND FEDERAL REGULATIONS, IF APPLICABLE.
- DEMOLITION EQUIPMENT AND ACTIVITIES SHALL NOT USE AREAS OUTSIDE OF THE PROJECT AREA WITHOUT WRITTEN PERMISSION FROM THE PROPERTY OWNER AND/OR GOVERNMENTAL APPROVAL(S).
- REFER TO EROSION AND SEDIMENT CONTROL PLANS FOR SEQUENCE OF CONSTRUCTION AND APPROXIMATE TIMING.
- CONTRACTOR TO REMOVE OR RELOCATE, WHEN APPLICABLE, ALL EXISTING BUILDINGS, FOUNDATIONS, EASEMENTS, CONNECTING IMPROVEMENTS, DRAIN PIPES, SANITARY SEWER PIPES, POWER POLES AND GUY WIRES, WATER METERS AND WATER LINES, WELLS, SIDEWALKS, SIGN POLES, UNDERGROUND GAS, AND ASPHALT, SHOWN AND NOT SHOWN, WITHIN CONSTRUCTION LIMITS AND WHERE NEEDED, TO ALLOW FOR NEW CONSTRUCTION AS SHOWN.



Know what's below
Call before you dig.

NOTES:
1. THIS DRAWING DOES NOT RELIEVE ANYONE'S RESPONSIBILITY FOR CONSTRUCTION SAFETY. ALL CONSTRUCTION MUST BE DONE IN ACCORDANCE WITH THE CODES AND ALL STATE AND FEDERAL REGULATIONS PERTAINING TO THE PROJECT.

W. JEFFERY NAGORNY, P.E. PA P.E. LICENSE # 39220E	1. 100% CONSTRUCTION DRAWINGS REVISIONS	03/10/17 DATE
--	--	------------------



EXISTING CONDITIONS & DEMOLITION PLAN	PROJECT TITLE WILKES-BARRE V.A. MEDICAL CENTER PARKING GARAGE	DATE: 03/10/2017
FACILITY PROJECT NAME WILKES-BARRE V.A. MEDICAL CENTER	BUILDING NUMBER PARKING GARAGE	CHECKED WIN
	DRAWN JAR	DRAWING TITLE S-2
LOCATION 1111 EAST END BLVD, WILKES-BARRE, PA 18702	DWG. 3 OF 15	

veterans
Affairs