

**Conditioner Numbers  
Referenced on Flow  
Diagrams**

**List of Equipment**

Building 1 - Provide 6" flanged, water conditioner to main line as it enters building prior to pumps and any branching.	1
Building 1 pump room - Provide 1 - 6" flanged water conditioner after main pump manifold to condition main cold water header to all 9 floors of Building 1 and water supply to CLC/Hospice Buildings	3
Building 1 pump room - Provide 1 - 4" flanged water conditioner to condition water supply to CLC/Hospice building and Building 1 kitchen and laundry areas	4
CLC Building - Provide 1 - 1" water conditioner for hot water return from Hospice Building	26
CLC Building - Provide 1 - 1-1/4" water conditioner for hot water return from CLC Building	27
CLC Building on roof cold water supply to Hospice - Provide 1 - 2" flanged water conditioner	28
Fisher House - Provide 1 - 1-1/2" flanged water conditioner on Fisher House's water supply into building	25
Fisher House - Provide 1 - two-stage, 5 micron + 0.2 micron filter in place of existing 0.45 micron filter unit	
Building 1 cold water supply off header to floors 2, 5, and 6 - Provide 1 - 3" flanged water conditioners for floor 2 and 2 - 2" flanged water conditioners for floors 5 and 6	8, 11, 12
Building 1 hot water return from floors 2, 5, and 6 to main hot water return line - Provide 3 - 1-1/2" flanged water conditioners for floors 2, 5, and 6	17, 20, 21
Building 1 hot water area - Provide 1 - 6" flanged water conditioner for makeup water line on 160 deg F hot water system	5
Building 1 hot water area - Provide 1 - 4" flanged water conditioner for makeup water line on 120 deg F hot water system	6
Building 16 cold water supply off header - Provide 1 -2" flanged water conditioner	29
Building 16 Hot water supply off header and return - Provide 2 -2" flanged water conditioner	30,31

Building 1 pump room - Provide 1 - 6" flanged water conditioner after secondary pump manifold to condition main cold water header to all 9 floors	2
Building 1 cold water supply off header to floors 1, 3, 4, 7, 8, 9 - Provide 3 - 3" flanged water conditioners for floors 1, 3, 4 and 3 - 2" flanged water conditioners for floors 7, 8, 9	7, 9, 10, 13, 14, 15
Building 1 hot water return from off each floor to main hot water return line - Provide 6 - 1-1/2" flanged water conditioners for floors 1, 3, 4, 7, 8, 9	16, 18, 19, 22, 23, 24

Note: Line sizes and flow rates to be verified. No diagram provided for water equipment in Building 16.