



1. EXIT SIGN, SPRINKLER HEADS, AND OTHER CEILING ACCESSORIES SHOWN ARE AT CRITICAL LOCATIONS ONLY. REFER TO MECHANICAL AND ELECTRICAL DRAWINGS FOR AREAS WHERE THE ABOVE ITEMS ARE NOT SHOWN. PROVIDE SPRINKLER HEADS AT LOCATIONS PER CODE REQUIREMENTS AND APPROVED SHOP DRAWINGS.
2. PROVIDE ACCESS DOORS AS REQUIRED FOR ACCESS TO UTILITIES, AND AS REQUIRED BY CODES. ACCESS DOOR LOCATIONS ARE NOT ALL SHOWN ON REFLECTED CEILING PLAN.
3. A.F.F. REFERS TO BLDG. 20 F.F. LEVEL

1. DO NOT PROCEED WITH DEMOLITION WORK PRIOR TO THE INSTALLATION OF CONSTRUCTION BARRICADE.
2. PROVIDE CONSTRUCTION BARRICADE IN EXISTING UNOCCUPIED AREAS AS REQUIRED AND AS DIRECTED BY COTR AT NO ADDITIONAL COST TO THE GOVERNMENT.
3. VERIFY EXTENT OF DEMOLITION PRIOR TO BEGINNING WORK.
4. CONTRACTOR SHALL PROTECT ALL EXISTING COMPONENTS OF EXTERIOR GLAZING SYSTEM, OTHER EXISTING CONSTRUCTION AND EXISTING LIFE-SAFETY EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIRING ANY DAMAGE TO EXISTING GLAZING SYSTEM, OTHER EXISTING CONSTRUCTION OR EXISTING LIFE-SAFETY EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR AND RESTORATION OF EXISTING CONSTRUCTION TO ORIGINAL CONDITION AT NO ADDITIONAL COST TO THE GOVERNMENT.
5. PATCH TO MATCH EXISTING FLOORS, CEILINGS, WALL, PARTITIONS, AND OTHER ITEMS THAT ARE DAMAGED OR REMOVED FROM DEMOLITION WORK AND NEW CONSTRUCTION WORK.
6. PROVIDE SUPPORTS AND BRACINGS AS REQUIRED FOR EXISTING STRUCTURE, UTILITIES, PIPES, DUCTS, CHIMNEYS, ETC. DURING DEMOLITION. NEW CONSTRUCTION WORK WHERE EXISTING SUPPORTS ARE REMOVED DUE TO WORK UNDER THIS CONTRACT, NEW SUPPORTS SHALL MEET CURRENT CODE REQUIREMENTS.
7. FOR DEMOLITION OF UTILITY SYSTEMS, REFER TO MECHANICAL, PLUMBING, AND FIRE PROTECTION AND ELECTRICAL DRAWINGS.

Department of
Veterans Affairs