

1. ADD LIGHTNING AIR TERMINAL.
2. NEW LIGHTNING CONDUCTOR.
3. CONNECT NEW CONDUCTOR TO EXISTING LIGHTNING PROTECTION WIRE.
4. REMOVE LIGHTNING PROTECTION WIRING ON EXISTING INTERCONNECTING CORRIDOR AND  
EXISTING 307.
5. EXISTING LIGHTNING AIR TERMINAL TO REMAIN. TYPICAL UNLESS OTHERWISE NOTED.
6. EXISTING DOWN CONDUCTOR TO REMAIN. TYPICAL UNLESS OTHERWISE NOTED.
7. EXISTING LIGHTNING CONDUCTOR TO REMAIN. TYPICAL UNLESS OTHERWISE NOTED.
8. PROVIDE DOWN CONDUCTOR, ROOF FITTING, LIGHTNING ROD.

**ITEM 1 (BASE BID):** All work specified or shown in the bid documents. Work includes all site work, demolition, removal, disposal, hauling, and replacement of existing work and new work and protection, necessary removal of existing construction and certain other items and construction of new work shown. Contractor shall have 90 days from Notice to Proceed to complete Work associated with BID ITEM 1, (BASE BID).

**a. BID ITEM 1 (BASE BID) except:**

- 1. Deduct all work associated with installation new ceiling and floor finish materials and lighting in rooms 2-2-2, 2-2-3, 2-2-4, 2-2-5, 2-2-6, 2-2-7, 2-2-8, 2-2-9, 2-2-10, 2-2-11, 2-2-12, 2-2-13, 2-2-14, 2-2-15, 2-2-16, 2-2-17, 2-2-18, 2-2-19, 2-2-20 and 2-2-21 in Building 315.
- 2. Deduct all work associated with Restrooms 200 and 208 in Building 315.
- 3. Deduct all work associated with internal duct sealant in Building 315.
- 4. Deduct all work associated with Rebuilding of existing roof structure, gutters, downspouts, breakers and tube panels A, B, C, AA, 1A, 1B, 1C, 1S, 1M, 1E1 and 1E2 in Building 315.

As indicated in the contract documents, Contractor shall have 90 days from Notice to Proceed to complete Work associated with BID ITEM 3, (DEDUCT ALTERNATE NO. 3).

**b. BID ITEM 3 (DEDUCT ALTERNATE NO. 2):** Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2 and

- 1. Deduct all work associated with North floor of Building 330,

as indicated in the contract documents. Contractor shall have 90 days from Notice to Proceed to complete Work associated with BID ITEM 3, (DEDUCT ALTERNATE NO. 2).

**c. BID ITEM 4 (DEDUCT ALTERNATE NO. 3):** Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3 and:

- 1. Deduct all work associated with the demolition of Building 307 and 308 and Reentry Suite at the second floor of Building 330.
- 2. Deduct all work associated with internal duct sealant in Building 330,


as indicated in the contract documents. Contractor shall have 90 days from Notice to Proceed to complete Work associated with BID ITEM 4, (DEDUCT ALTERNATE NO. 3).

**d. BID ITEM 5 (DEDUCT ALTERNATE NO. 4):** Contractor shall perform all work as described in BID ITEM 1 (BASE BID) except deduct all work associated with BID ITEM 2, BID ITEM 3, BID ITEM 4 and

- 1. Deduct all work associated with the demolition of Building 307 and associated exterior wall repair, site work connecting corner and utility modifications, as indicated in the contract documents. Contractor shall have 90 days from Notice to Proceed to complete Work associated with BID ITEM 5, (DEDUCT ALTERNATE NO. 4).

**BUILDING 340**[illegible]

**Heapy Engineering**  
MEP Design Technology Planning Commissioning Energy  
**Nationally Recognized Leader in Sustainability**  
1400 W Dorothy Lane, Dayton, OH 45409-1310  
Ph 937-224-0861 Fax 937-224-5777 [www.heapy.com](http://www.heapy.com)  
Heapy Project No.: 2014-04034 Firm License No.: 0152



JOHN POE ARCHITECTS

3131 NEWMARK DRIVE,  
SUITE 200  
MIAMISBURG, OHIO 45342  
937 461 3290 PHONE  
jpa@johnpoe.com

## ROOF PLAN - LIGHTNING PROTECTION

Approved: Project Director

Location	Dayton, Ohio
----------	--------------

Date

Checked
---------

Drawn

Drawing Number  
0035D104

307EP

Office of  
Construction  
and Facilities  
Management

