



- GENERAL SHEET NOTES:

1. REFER TO DWG E-001 FOR NOTES, SYMBOLS, AND ABBREVIATIONS
2. COMMISSIONING/START UP SHALL OCCUR ONLY DURING OFF PEAK HOURS.
3. REFER TO DWG EP-601 SINGLE LINE FOR DETAILS
4. ELECTRICAL EQUIPMENT DIMENSIONS ARE REPRESENTATIVE FOR DRAWING PURPOSES ONLY. ELECTRICAL CONTRACTOR SHALL VERIFY DIMENSIONS WITH ELECTRICAL EQUIPMENT MANUFACTURER AND COORDINATE WITH OTHER TRADES BEFORE FINAL INSTALLATION

**SHEET KEYNOTES**

1. PER VA SPECIFICATION 26-05-41, CONDUITS ENCLOSED IN CONCRETE SHALL BE BURIED AT A  
a.) 24" UNDER FINISHED GRADE  
b.) 36" UNDER ROADS AND SIDEWALKS  
c.) 48" UNDER SLOES
2. PLASTIC IDENTIFICATION TAP SHALL BE BURIED AT A MINIMUM OF 1 FOOT ABOVE THE TOP OF THE CABLE
3. PROVIDE 12 PFER, MALLORCE PERMAN RATED 50/125 CONDUCTORS, 12 PFER, MALLORCE PERMAN RATED 50/125 CONDUCTORS, COMPATIBLE WITH SHD AND OWNERS EQUIPMENT

# CONSTRUCTION DOCUMENTS

[illegible]