



- GENERAL SHEET NOTES:**
- SEE DWG. E1-201 FOR GENERAL NOTES, LEGEND, AND ABREVIATIONS
 - CONTRACTOR SHALL PROVIDE AND INSTALL LOCKABLE POSI-LOK CABLE CONNECTION ENCLOSURE AND POSI-LOK CABLES IN ADDITION TO POSI-LOK PANEL E-400
 - SEE SINGLE LINE DWG EP-601 FOR CABLE DETAILS CONNECTING TO FUSED DISCONNECT SWITCH
 - COMMISSIONING/START UP SHALL ONLY OCCUR DURING NON PEAK HOURS
 - ELECTRICAL EQUIPMENT DIMENSIONS ARE ONLY FOR INFORMATION. CONTRACTOR SHALL VERIFY DIMENSIONS WITH ELECTRICAL EQUIPMENT MANUFACTURE AND INSTALLATION WITH OTHER TRADES BEFORE FINAL
 - COMMISSIONING/START UP SHALL ONLY OCCUR DURING NON PEAK HOURS

SHEET KEYNOTES:

- MALE PLUGGED POSI-LOK CABLE TO BE STORED IN LOCKABLE ENCLOSURE
- CONTRACTOR SHALL PROVIDE NEMA 13 ENCLOSURE W/ (2) NEW POSI-LOK PANELS 400-A TO ACCEPT POSI-LOK CABLES FROM 200KVA GENERATOR ENCLOSURE SHALL BE LARGES ENOUGH TO STORE (2) 20' CABLES.
- CABLE DIRECT BURIAL " IN CONDUIT AND CONCRETE, TABLE 310.15(B) 75 deg.C (2) SETS OF 5/C 500 KCMIL
- CONTRACTOR SHALL PROVIDE AND INSTALL FUSED DISCONNECT SWITCH 800A FRAME 700A FUSE AND/OR ON UNI-STRUT W/ 500 KCMIL PER PHASE
- COMMISSIONING/START UP SHALL ONLY OCCUR DURING NON PEAK HOURS

CONSULTANTS:

ARCHITECT/ENGINEERS:

ADDENDUM #1	06-11-12
Revisions	Date

THOMAS L. SHUBANK, P.E.
PROFESSIONAL ENGINEER
PENNSYLVANIA LICENSE NO. 16034038

Miller-Ramick LLC
A Division of Ramick Group, Inc.
2010 KINGS HIGHWAY SOUTH
CHERRY HILL, NEW JERSEY 08034
PHONE: (609) 459-4000
FAX: (609) 459-5502

Drawing Title
POWER PANEL 1 AND POSI-LOK DETAILS

Project Title
THERMAL STORAGE FOR CHILLER PLANT

Project Number
595-11-131

Office of Construction and Facilities Management

Approved Project Director
SCALE: VARIOUS

Location
VA MED CENTER, LEBANON, PA

Drawing Number
EP-501

Department of Veterans Affairs