



SCHEDULE OF CONNECTIONS - STEEL TO CONCRETE					
STEEL BEAM SECTION	EMBEDDED PLATE SIZE	WEB ANGLE	WELD A	WELD B	
W14	18"x10"x3/8"	2L3"x3"x5/16"x0'-8"	3/16"	1/4"	
W16	18"x10"x3/8"	2L3"x3"x5/16"x0'-8"	3/16"	1/4"	
W18	21"x10"x3/8"	2L4"x3"x5/16"x1'-0"	3/16"	1/4"	
W24	24"x10"x3/8"	2L4"x3"x5/16"x1'-0"	3/16"	1/4"	

TYPICAL CANTILEVER CONNECTION DETAIL

SCALE 3/4" = 1'-0"

1/27/21 AS BUILT JUL 27 1981

NO. DATE DESCRIPTION REVISIONS

SHEET TITLE SECTIONS

BLDG NO. PROJECT TITLE

102 200 Bed Domiciliary Building

DRAWN BY G. DELCAMPO CHECKED BY [Signature] DATE JUN 19 1978

SHS Associates Inc. Architects, Engineers, Planners 2600 - 9th Street North St. Petersburg, Florida 33704

102-SII DWG. 65 OF 147 PROJECT NUMBER 516-053F

VETERANS ADMINISTRATION

V.A.C. Bay Pines, Florida