

TOMAH, WI

CONSOLIDATE LIBRARIES AND CONSTRUCT CONFERENCE ROOM

VA PROJECT NO. 676-12-102

SCHEDULE - DOORS													
Door Number	Room #	Room Name	Door					Frame Material	Frame Type	Frame Finish	Hardware Group	Assembly Rating	Notes
			Size	Type	Material	Finish	Glass						
FIRST FLOOR													
1100.1	1100	GENERAL LIBRARY	2 @ 3'-0"W x 7'-0"H	C	WD	STN-1		STL	C	PA	10A		2, 5
1100.2	1100	GENERAL LIBRARY	3'-8"W x 7'-0"H	G	STL	PA		STL	B	PA	E4		1
1110.1	1110	MEDICAL LIBRARY	3'-0"W x 7'-0"H	E	WD	STN-1		STL	A	PA	4A		2, 5
1110.2	1110	MEDICAL LIBRARY	3'-0"W x 7'-0"H	B	WD	STN-1		STL	A	PA	3B		5
1112.0	1112	PERC	3'-6"W x 7'-0"H	B	WD	STN-1		STL	A	PA	4H		3, 4, 5
1113.0	1113	CIRCULATION DESK	3'-0"W x 7'-0"H	B	WD	STN-1		STL	A	PA	3		5
1113A.0	1113A	WORK AREA	3'-0"W x 7'-0"H	F	WD	STN-1		STL	A	PA	3E		5
1116.0	1116	WOMEN'S TOILET	3'-6"W x 7'-0"H	F	WD	STN-1		STL	A	PA	2A		2
1118.0	1118	CRASH CART	3'-0"W x 7'-0"H	F	WD	STN-1		STL	A	PA	5D		
1119.0	1119	FAMILY ROOM	3'-0"W x 7'-0"H	A	WD	STN-1		STL	A	PA	2F		
1120.0	1120	CONFERENCE RM	2 @ 3'-0"W x 7'-0"H	D	WD	STN-1		STL	A	PA	10A		2, 5
1120A.0	1120A	STORAGE ROOM	2 @ 2'-6"W x 7'-0"H	A	WD	STN-1		STL	A	PA	11		

**DOOR SCHEDULE NOTES:**

- 1 NEW DOOR IN EXISTING WINDOW OPENING. VERIFY R.O. IN FIELD.
- 2 AUTOMATIC SWING DOOR OPERATOR BY OTHER SECTION
- 3 180 DEGREE HINGES.
- 4 WALL MOUNTED MAGNETIC HOLD- OPEN

5 SEE DOOR TYPE ELEVATIONS FOR GLASS