

<b>AHERA Asbestos Reassessment</b> <b>Durham VA Medical Center</b> <b>Durham, North Carolina</b>	<b>Building #16</b>
--	---------------------

Sample Number	Sample Location (Room Number or Area)	Material Description	Material Locations	Sample Analysis	Material Type (Surfacing, Miscellaneous, Thermal System Insulation)	Amount of Material	Friable or Non-Friable	Material Condition (Intact, Minor Damage, Damaged, Significant Damage) * include % damaged	Potential For Disturbance (H/M/L)
16-12FT01-10-01, 12FT01-18-02	16-10, 18	12x12 Floor Tile Gray with Gray and White Streaks and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile: 2% Chrysotile Mastic: 5% Chrysotile	Miscellaneous	6,964 SF	Non-Friable	Intact	Moderate
16-12FT02-31-01, 12FT02-SW22-02	16-31, Stairwell 22	12x12 Floor Tile White with Gray and Black Streaks and Tan and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile: NAD Tan Mastic: NAD Black Mastic:5% Chrysotile	Miscellaneous		Non-Friable	Intact	Moderate
16-12FT03-5-01, 12FT03-5-02	16-5	12x12 Floor Tile Beige with Brown Streaks and Tan and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile: 2% Chrysotile Tan Mastic: NAD Black Mastic: 2% Chrysotile	Miscellaneous		Non-Friable	Intact	Moderate
16-12FT04-ELEV.-01, 16-12FT04-37-02	Elevator, 37	12x12 Floor Tile White with Gray Streaks and Tan and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile: NAD Tan Mastic:NAD Black Mastic 2-5% Chrysotile:	Miscellaneous		Non-Friable	Intact	Moderate
16-12FT05-21-01, 12FT05-22-02	16-21, 22	12x12 Floor Tile White with Black Streaks and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile:5% Chrysotile Mastic: 5% Chrysotile	Miscellaneous		Non-Friable	Intact	Moderate
16-12FT06-19-01, 12FT06-8-02	16-19, 8	12x12 Floor Tile Beige with Gray Streaks and Tan and Black Mastic	Throughout The Buidling (See Attached Drawing)	Tile: 2% Chrysotile Tan Mastic: NAD Black Mastic: 5% Chrysotile	Miscellaneous	6,964 (cont.)	Non-Friable	Intact	Moderate
16-9FT01-SW22-01, 9FT01-SW8-02	16 Stairwell 22, Stairwell 8	9x9 Floor Tile Beige with Brown Streaks and Tan Mastic	Throughout The Buidling (See Attached Drawing)	Tile: 8% Chrysotile Tan Mastic: NAD	Miscellaneous		Non-Friable	Intact	Moderate
		2x4 Suspended Ceiling Panel with Pinholes	Rooms 2,6,7,19, Stairwells and Landings	3% Chrysotile	Miscellaneous	Removed			
16-LC01-8-01, LC01-22-01	16-8, 22	Black Laboratory Countertops	Laboratories 8/10,17,18 and 21	10% Chrysotile	Miscellaneous	560 SF	Non-Friable	Intact	Moderate
		Exhaust Hood Panelboard	Laboratories 12/14 and 18	15% Chrysotile	Miscellaneous	Removed			
16-TB04-18A-01, TB04-18A-02	16-18A	Black Glass Drying Rack	Laboratory 18 A	25% Chrysotile	Miscellaneous	Removed			
RS16-FL01-65-01	Room 65	Yellow Floor Covering	Room 65	NAD					

\*SAMPLE NUMBERS BEGINNING WITH "RS11" INDICATE THOSE TAKEN DURING THE 2011 REASSESSMENT SURVEY

\*\*SAMPLE NUMBERS BEGINNING WITH "RS" INDICATE THOSE TAKEN DURING THE REASSESSMENT SURVEY

\*\*\*NAD - No Asbestos Detected

