

- ① (E) INTERGY/DEMCO SERVICE POLE.
- ② (E) DEMCO PRIMARY PULLBOX.
- ③ (E) 4" DEMCO RISER.
- ④ (E) 2-3" DEMCO 25KV PRIMARY CONDUITS.
- ⑤ (N) SINGLE PHASE TRANSFORMER PAD PER DEMCO REQUIREMENTS.
- ⑥ (E) CONDUITS (2-4")
- ⑦ TELECOMMUNICATIONS ENTRY PROJECTOR PANEL SEE 3/E-2.
- ⑧ (E) IRRIGATION CONTROLLER.
- ⑨ (E) BOOSTER PUMP, 208V, 3ø, 1.5HP.
- ⑩ (E) 1-4" DEMCO SECONDARY SERVICE CONDUIT.
- ⑪ (E) AT&T CONCRETE PULL BOX.
- ⑫ (N) SERVICE PANEL 'A', 200A, 120/240V, 1ø.
- ⑬ (E) SERVICE PEDESTAL 'B', 400A, 120/208V 3ø, 4WL.
- ⑭ MAINTENANCE BLDG SERVICE PANEL 'B1', 200A, 120/208V 3ø, 4WL.
- ⑮ (E) 3" CONDUIT FOR PANEL 'B1' SEE 2/E-3 FOR FEEDER INFORMATION.
- ⑯ SEPTIC TANK, PUMP AND CONTROLLER, 120V.
- ⑰ (E) UNDERGROUND UTILITY SERVICES FOR ADMIN. BLDG. AND MAINTENANCE BLDG. (E) 1-2"C FOR DATA (FIBER), (E) 1-2"C FOR TELEPHONE, (E) 1-2"C FOR FIRE AND SECURITY & (E) 1-2"C SPARE CONDUITS. SEE 3/E-2.
- ⑱ (E) CONCRETE PULLBOX.
- ⑲ (E) 2" CONDUIT FOR PEDESTAL SERVICE, SEE 2/E-3 FOR FEEDER INFORMATION.
- ⑳ (N) 1" CONDUIT FOR TELECOM CONDUCTORS. SEE 3/E-2.
- ㉑ (E) FUEL TRANSFER PUMP. 1/3 HP, 115V.
- ㉒ (N) 11"x18" CONCRETE PULL BOX.
- ㉓ 25-PAIR PROTECTOR PANEL. SEE 3/E-2.



1. CONDUIT ROUTING SHOWN IS IN APPROXIMATE LOCATIONS ONLY. DO NOT LOCATE CONDUIT OR BOXES INTENDED FOR FUTURE GRAVESITES. COORDINATE EXACT ROUTING ON THE JOB. IN GENERAL, ROUTE CONDUITS IMMEDIATELY ADJACENT TO ROADWAYS WITHIN 10'-0" OF THE CURB OR PAVEMENT EDGE UNLESS OTHERWISE NOTED ON PLANS. COORDINATE EXACT ROUTING WITH LANDSCAPE, IRRIGATION AND SANITARY DRAWINGS.
2. OWNER/CONTRACTOR SHALL CONTACT DEMCO WITH 4-5 WEEKS ADVANCE NOTICE PRIOR (E) SERVICE DEACTIVATION & TO PULLING OF NEW CABLE.



A ————— B ————— C ————— D ————— E ————— F

Dwg. 56 of 137

[illegible]

ECOM ENGINEERING INC.
1796 TRIBUTE ROAD, SUITE 100
SACRAMENTO, CA. 95815
916.641.5600
916.641.1640 FAX
WWW.ECOMENG.COM

JOB NO. **10E286.00** PW. **MARK**
DESIGNERS **CHERYL**

CarterBurgess
A Wholly Owned Subsidiary of Jacobs

Consultants in Architecture, Engineering,
Planning, and the Environment

Sacramento Office
180 Promenade Circle, Suite 300
Sacramento, California 95834
(916) 929-3323 Fax (916) 929-1772

Subconsultant List	
DREYFUSS & BLACKFORD	3540 FOLSOM BOULEVARD, SACRAMENTO, CA 95816 (916) 453-1234
CAPITAL ENGINEERING CONSULTANTS	11020 SUN CENTER DRIVE, RANCHO CORDOVA, CA 95670 (916) 851-3500
ECOM ENGINEERING INC.	1796 TRIBUTE ROAD, SUITE 100 SACRAMENTO, CA (916) 641-5600
BUELHER & BUEHLER STRUCTURAL ENGINEERS, INC.	600 Q STREET, STE. 200, SACRAMENTO, CA. 95811 (916) 443-0303
W.L. BURLE ENGINEERS, PA	111 S. WALNUT STREET, GREENVILLE, MS 38702 (662) 332-2619
AQUA ENGINEERING, INC.	4803 INNOVATION DRIVE, FORT COLLINS, CO 80525 (970) 229-9668
THE SIERRA WEST GROUP, LLC	2730 GATEWAY OAKS DRIVE, STE. 110 SACRAMENTO, CA. 95833 (916) 925-4000



NATIONAL
CEMETERY
ADMINISTRATION

Drawing Title

SITE LAYOUT ENLARGEMENT
PLANS – ELECTRICAL

Approved: Director, Office of Construction Management

Approved: Director, Project Management Service

Building Number

Checked

rawn

Location	LOUISIANA NATIONAL CEMETERY ZACHARY, LOUISIANA
----------	---