



U.S. ABILITYONE COMMISSION

February 9, 2016

703-603-7740
FAX 703-603-0655

1401 S. Clark Street, Suite 715
Arlington, Virginia 22202-4149

VIA EMAIL

PROCUREMENT LIST NOTICE OF ADDITION

TO: Defense Logistics Agency Troop Support
ATTN: Abin Mathai, abin.mathai@dla.mil

National Industries for the Blind

In accordance with 41 CFR 51-2.2, the U.S. AbilityOne Commission (Commission) has determined that the following product(s) are suitable for provision by nonprofit agency(ies) employing people who are blind or significantly disabled. Accordingly, the Commission approved the following product(s) for addition to the Procurement List at the Fair Market Price (FMP) indicated.

Product NSN: 5340-00-NIB-0141
Product Name: Lockset, Mortise, Privacy Function, Escutcheon Trim, Philadelphia-style Lever
Product Description: Mortise lockset for a privacy with an escutcheon trim and Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either sides. Thumb-turn inside locks/unlocks outside lever. Rotating inside lever unlocks outside lever. Lockset is certified ANSI F22 function compatible. UOI is EA.
FOB-Origin FMP: \$251.34

Product NSN: 5340-00-NIB-0142
Product Name: Electronic Push Button Lockset, Philadelphia-style Lever, Small Format Interchangeable Core
Product Description: Electronic push button lockset with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. This is a battery-operated stand-alone lockset utilizing a keypad. UOI is EA.
FOB-Origin FMP: \$345.90

Product NSN: 5340-00-NIB-0143
Product Name: Electronic Push Button Lockset, Philadelphia-style Lever, Large Format Interchangeable Core
Product Description: Electronic push button lockset with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. This is a battery-operated stand-alone lockset utilizing a keypad. UOI is EA.
FOB-Origin FMP: \$345.90

PL Number: 20150054

Transaction ID: 26146



COMMITTEE FOR PURCHASE FROM PEOPLE WHO ARE BLIND OR SEVERELY DISABLED
An Independent Federal Agency



Product NSN: 5340-00-NIB-0144
Product Name: Exit Device, Rim, Panic Listed, 3' Door
Product Description: Exit device 3' rim application with hex key dogging, Grade 1 lockset, "Panic Bar" closure device. UOI is EA.
FOB-Origin FMP: \$409.10

Product NSN: 5340-00-NIB-0145
Product Name: Exit Device, Rim, Fire Listed, 3' Door
Product Description: Exit device 3' rim application that is fire listed. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$465.37

Product NSN: 5340-00-NIB-0146
Product Name: Exit Device, Surface Vertical Rod, Panic Listed, 3' Door
Product Description: Exit device, surface vertical rod devices feature top and bottom pull-man latch bolts that are dead locking where applicable. Grade 1 lockset, "Panic Bar" exit device. Hex key dogging for 3' door. UOI is EA.
FOB-Origin FMP: \$580.30

Product NSN: 5340-00-NIB-0147
Product Name: Exit Device, Surface Vertical Rod, Fire Listed, 3' Door
Product Description: Exit device, surface vertical rod devices feature top and bottom pull-man latch bolts that are dead locking where applicable. Grade 1 lockset. Fire listed for a 3' door. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$618.08

Product NSN: 5340-00-NIB-0148
Product Name: Exit Device, Rim, Panic Listed, 4' Door
Product Description: Exit device 4' rim application with hex key dogging, Grade 1 lockset, "Panic Bar" closure device. UOI is EA.
FOB-Origin FMP: \$435.40

Product NSN: 5340-00-NIB-0149
Product Name: Exit Device, Rim, Fire Listed, 4' Door
Product Description: Exit device 4' rim application that is fire listed. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$491.19

Product NSN: 5340-00-NIB-0150
Product Name: Exit Device, Surface Vertical Rod, Panic Listed, 4' Door
Product Description: Exit device that is panic listed. Has a vertical rod for a 4' door. UOI is EA.
FOB-Origin FMP: \$609.85



Product NSN: 5340-00-NIB-0151
Product Name: Exit Device, Surface Vertical Rod, Fire Listed, 4' Door
Product Description: Exit device that is fire listed. Has a vertical rod for a 4' door. UOI is EA.
FOB-Origin FMP: \$646.83

Product NSN: 5340-00-NIB-0152
Product Name: Door Closer, Architectural Commercial Grade
Product Description: Architectural commercial grade door closer featuring full rack and pinion construction, heavy duty cast aluminum closer body, standard tri-pack arm assembly, non-handed. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$112.45

Product NSN: 5340-00-NIB-0153
Product Name: Door Closer, Heavy Duty Institutional Grade
Product Description: Heavy duty institutional door closer featuring full rack and pinion construction, heavy duty cast iron closer body, forged steel main arm and full architectural cover, hydraulic controlled, back-check positioning valve provides consistent back-check range. Standard tri-pack arm assembly, non-handed. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$193.36

Product NSN: 5340-00-NIB-0154
Product Name: Door Closer, Architectural Commercial Grade with Hold Open Function
Product Description: Architectural commercial grade door closer with hold open arm and tri-pack for regular, top jamb and parallel arm function. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$159.81

Product NSN: 5340-00-NIB-0155
Product Name: Door Closer, Heavy Duty Institutional Grade with Hold Open Function
Product Description: Heavy duty institutional door closer with hold open arm function, standard tri-pack assembly, non-handed. Full rack and pinion construction, heavy duty cast iron closer body, forged steel main arm and full architectural cover, hydraulic controlled, back-check positioning valve provides consistent back-check range. Grade 1 lockset. UOI is EA.
FOB-Origin FMP: \$254.12

Product NSN: 5340-00-NIB-0236
Product Name: Lockset, Cylindrical, Storeroom Function, Philadelphia-style Lever, Small Interchangeable Core
Product Description: Cylindrical lockset for a storeroom with a Philadelphia-style lever and a small format interchangeable core. Latch-bolt operated by



inside lever from either side. Both levers lock/unlock by key from either side. Lockset is certified ANSI F91 function compatible. UOI is EA.

FOB-Origin FMP:

\$186.93

Product NSN:

5340-00-NIB-0135

Product Name:

Lockset, Cylindrical, Vestibule/Classroom, Philadelphia-style Lever, Small Interchangeable Core

Product Description:

Cylindrical lockset for a vestibule/classroom with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times and is certified ANSI F110 function compatible. UOI is EA.

FOB-Origin FMP:

\$186.94

Product NSN:

5340-00-NIB-0237

Product Name:

Lockset, Cylindrical, Storeroom Function, Boston-style Lever, Small Format Interchangeable Core

Product Description:

Cylindrical lockset for a storeroom with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by inside lever from either side. Both levers lock/unlock by key from either side. Lockset is certified ANSI F91 function compatible. UOI is EA.

FOB-Origin FMP:

\$186.94

Product NSN:

5340-00-NIB-0241

Product Name:

Lockset, Cylindrical, Institutional Function, Philadelphia-style Lever, Small Interchangeable Core

Product Description:

Cylindrical lockset for an institution with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Both levers rigid. Latch bolt retracted by key on both sides, can only gain entry by key. Lockset is certified ANSI F87 function compatible. UOI is EA.

FOB-Origin FMP:

\$186.94

Product NSN:

5340-00-NIB-0242

Product Name:

Lockset, Cylindrical, Institutional Function, Boston-style Lever, Small Format Interchangeable Core

Product Description:

Cylindrical lockset for an institution with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt retracted by key on both sides, can only gain entry by key. Lockset is certified ANSI F87 function compatible. UOI is EA.

FOB-Origin FMP:

\$186.94

Product NSN:

5340-00-NIB-0244

Product Name:

Lockset, Cylindrical, Communication Function, Philadelphia-style Lever, Small Interchangeable Core



Product Description: Cylindrical lockset for communication with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Key in either side locks or unlocks its own lever independently and is certified ANSI F80 function compatible. UOI is EA.

FOB-Origin FMP: **\$186.94**

Product NSN: **5340-00-NIB-0245**

Product Name: Lockset, Cylindrical, Communication Function, Boston-style Lever, Small Format Interchangeable Core

Product Description: Cylindrical lockset for communication with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Key in either side locks or unlocks its own lever independently and is certified ANSI F80 function compatible. UOI is EA.

FOB-Origin FMP: **\$186.94**

Product NSN: **5340-00-NIB-0259**

Product Name: Lockset, Cylindrical, Vestibule/Classroom/Security, Philadelphia-style, Small Interchangeable Core

Product Description: Cylindrical lockset for vestibule or classroom security with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side. Key in either lever locks or unlocks outside lever. Inside lever always free. Lockset is certified ANSI F110 function compatible. UOI is EA.

FOB-Origin FMP: **\$186.94**

Product NSN: **5340-00-NIB-0134**

Product Name: Lockset, Cylindrical, Passage/Closet Function, Philadelphia-style Lever

Product Description: Cylindrical lockset for a passage or closet with a Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either side at all times and is certified ANSI F75 function compatible. UOI is EA.

FOB-Origin FMP: **\$119.33**

Product NSN: **5340-00-NIB-0239**

Product Name: Lockset, Cylindrical, Exit Function, Philadelphia-style Lever

Product Description: Cylindrical lockset used for an exit with a Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by inside lever at all times, outside lever always fixed and is certified ANSI F89 function compatible. UOI is EA.

FOB-Origin FMP: **\$119.33**

Product NSN: **5340-00-NIB-0240**

Product Name: Lockset, Cylindrical, Exit Function, Boston-style Lever

Product Description: Cylindrical lockset used for an exit with a Boston-style lever. Grade 1 lockset. Latch bolt operated by inside lever at all times,



outside lever always fixed and is certified ANSI F89 function compatible. UOI is EA.

FOB-Origin FMP:

\$119.33

Product NSN:

5340-00-NIB-0254

Product Name:

Lockset, Cylindrical, Passage/Closet Function, Boston-style Lever

Product Description:

Cylindrical lockset for a passage with a Boston-style lever. Grade 1 lockset. Latch bolt operated by lever from either side at all times and is certified ANSI F75 function compatible. UOI is EA.

FOB-Origin FMP:

\$119.33

Product NSN:

5340-00-NIB-0238

Product Name:

Lockset, Cylindrical, Storeroom Function, Philadelphia-style Lever, Large Interchangeable Core

Product Description:

Cylindrical lockset for a storeroom with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times. Lockset is certified ANSI F91 function compatible. UOI is EA.

FOB-Origin FMP:

\$188.54

Product NSN:

5340-00-NIB-0243

Product Name:

Lockset, Cylindrical, Institutional Function, Philadelphia-style Lever, Large Interchangeable Core

Product Description:

Cylindrical lockset for an institution with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Both levers rigid. Latch bolt retracted by key on both sides, can only gain entry by key. Lockset is certified ANSI F87 function compatible. UOI is EA.

FOB-Origin FMP:

\$188.54

Product NSN:

5340-00-NIB-0246

Product Name:

Lockset, Cylindrical, Communication Function, Philadelphia style lever, Large Interchangeable Core

Product Description:

Cylindrical lockset for communication with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Key in either side locks or unlocks its own lever independently and is certified ANSI F80 function compatible. UOI is EA.

FOB-Origin FMP:

\$188.54

Product NSN:

5340-00-NIB-0260

Product Name:

Lockset, Cylindrical, Vestibule/Classroom/Security, Boston-style Lever, Large Interchangeable Core

Product Description:

Cylindrical lockset for vestibule or classroom security with a Boston-style lever and a large format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side. Key in either lever locks or unlocks outside lever. Inside lever always free. Lockset is certified ANSI F110 function compatible. UOI is EA.

PL Number: 20150054

- 6 -

Transaction ID: 26146



FOB-Origin FMP: \$188.54

Product NSN: 5340-00-NIB-0247

Product Name: Lockset, Cylindrical, Dormitory/Corridor, Philadelphia-style Lever, Small Interchangeable Core

Product Description: Cylindrical lockset for a dormitory/corridor with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever unlocked by key in outside lever, closing door, or rotating inside lever; inside lever always free. Lockset is certified ANSI F90 function compatible. UOI is EA.

FOB-Origin FMP: \$177.97

Product NSN: 5340-00-NIB-0248

Product Name: Lockset, Cylindrical, Dormitory/Corridor Function, Boston-style Lever, Small Interchangeable Core

Product Description: Cylindrical lockset for a dormitory/corridor with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever unlocked by key in outside lever, closing door, or rotating inside lever; inside lever always free. Lockset is certified ANSI F90 function compatible. UOI is EA.

FOB-Origin FMP: \$177.97

Product NSN: 5340-00-NIB-0249

Product Name: Lockset, Cylindrical, Dormitory/Corridor, Philadelphia-style Lever, Large Interchangeable Core

Product Description: Cylindrical lockset for a dormitory/corridor with a Philadelphia-style lever and a large format interchangeable core. Latch bolt operated by lever from either side or key in outside lever. Outside lever unlocked by key in outside lever, closing door, or rotating inside lever; inside lever always free. Lockset is certified ANSI F90 function compatible. UOI is EA.

FOB-Origin FMP: \$179.57

Product NSN: 5340-00-NIB-0132

Product Name: Lockset, Cylindrical, Storeroom Function, Philadelphia-style Lever, Small Interchangeable Core

Product Description: Cylindrical lockset for a storeroom with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times and is certified ANSI F86 function compatible. UOI is EA.

FOB-Origin FMP: \$160.34

Product NSN: 5340-00-NIB-0133

Product Name: Lockset, Cylindrical, Office/Entrance Function, Philadelphia-style Lever, Small Interchangeable Core

PL Number: 20150054

- 7 -

Transaction ID: 26146



Product Description: Cylindrical lockset for an office/entrance with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times and is certified ANSI F109 function compatible. UOI is EA.

FOB-Origin FMP: **\$160.34**

Product NSN: **5340-00-NIB-0250**

Product Name: Lockset, Cylindrical, Entrance Function, Boston-style Lever, Small Format Interchangeable Core

Product Description: Cylindrical lockset for an entrance with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever locked by pushing and turning the button on the inside. Lockset is certified ANSI F109 function compatible. UOI is EA.

FOB-Origin FMP: **\$160.34**

Product NSN: **5340-00-NIB-0252**

Product Name: Lockset, Cylindrical, Storeroom Function, Boston-style Lever, Small Format Interchangeable Core

Product Description: Cylindrical lockset for a storeroom with a Boston-style lever and a small format interchangeable core. Grade 1 lockset Latch bolt operated by inside lever of key in outside lever. Outside lever always fixed. Lockset is certified ANSI F86 function compatible. UOI is EA.

FOB-Origin FMP: **\$160.34**

Product NSN: **5340-00-NIB-0256**

Product Name: Lockset, Cylindrical, Entry Function, Philadelphia-style Lever, Small Format Interchangeable Core

Product Description: Cylindrical lockset for an entrance with a Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever locked by push button on inside. Lockset is certified ANSI F82 function compatible. UOI is EA.

FOB-Origin FMP: **\$160.34**

Product NSN: **5340-00-NIB-0257**

Product Name: Lockset, Cylindrical, Entry Function, Boston-style Lever, Small Format Interchangeable Core

Product Description: Cylindrical lockset for an entrance with a Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever locked by push button on inside. Lockset is certified ANSI F82 function compatible. UOI is EA.

FOB-Origin FMP: **\$160.34**



Product NSN: 5340-00-NIB-0251
Product Name: Lockset, Cylindrical, Entrance Function, Philadelphia-style Lever, Large Format Interchangeable Core
Product Description: Cylindrical lockset for an entrance with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side or key in outside lever. Outside lever locked by pushing and turning the button on the inside. Lockset is certified ANSI F109 function compatible. UOI is EA.
FOB-Origin FMP: \$161.95

Product NSN: 5340-00-NIB-0253
Product Name: Lockset, Cylindrical, Storeroom Function, Philadelphia-style Lever, Large Format Interchangeable Core
Product Description: Cylindrical lockset for a storeroom with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Latch bolt operated by inside lever of key in outside lever. Outside lever always fixed. Lockset is certified ANSI F86 function compatible. UOI is EA.
FOB-Origin FMP: \$161.95

Product NSN: 5340-00-NIB-0258
Product Name: Lockset, Cylindrical, Entrance Function, Philadelphia-style Lever, Large Format Interchangeable Core
Product Description: Cylindrical lockset for an entrance with a Philadelphia-style lever and a large format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times side or key in outside lever. Outside lever locked by push button on inside. Philadelphia style lever. Lockset is certified ANSI F82 function compatible. UOI is EA.
FOB-Origin FMP: \$161.95

Product NSN: 5340-00-NIB-0136
Product Name: Lockset, Cylindrical, Privacy Function, Philadelphia-style Lever
Product Description: Cylindrical lockset for privacy, such as a bedroom or bathroom with a Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either side or emergency release in outside lever. Outside lever locked by push button on inside and is certified ANSI F76 function compatible. UOI is EA.
FOB-Origin FMP: \$136.31

Product NSN: 5340-00-NIB-0255
Product Name: Lockset, Cylindrical, Privacy Function, Boston-style Lever
Product Description: Cylindrical lockset for privacy with a Boston-style lever. Grade 1 lockset. Latch bolt operated by lever from either side or emergency release in outside lever. Outside lever locked by push



button on inside. Lockset is certified ANSI F75 function compatible. UOI is EA.

FOB-Origin FMP:

\$136.31

Product NSN:

5340-00-NIB-0261

Product Name:

Lockset, Cylindrical, Classroom Security LED, Philadelphia-style Lever, Small Interchangeable Core

Product Description:

Cylindrical lockset for classroom security with an LED function, Philadelphia-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side. Key in either lever locks/unlocks lever. The inside lever is always free and the red LED inside indicates the outside locking status with a lock directional arrow. Lockset is certified ANSI F110 function compatible. UOI is EA.

FOB-Origin FMP:

\$252.30

Product NSN:

5340-00-NIB-0262

Product Name:

Lockset, Cylindrical, Classroom Security LED, Boston-style Lever, Small Interchangeable Core

Product Description:

Cylindrical lockset for classroom security with an LED function, Boston-style lever and a small format interchangeable core. Grade 1 lockset. Latch bolt operated by lever from either side at all times. Latch bolt operated by lever from either side. Key in either lever locks/unlocks lever. The inside lever is always free and the red LED inside indicates the outside locking status with a lock directional arrow. Lockset is certified ANSI F110 function compatible. UOI is EA.

FOB-Origin FMP:

\$252.30

Product NSN:

5340-00-NIB-0137

Product Name:

Lockset, Mortise, Storeroom Function, Escutcheon Trim, Philadelphia-style Lever

Product Description:

Mortise lockset for a storeroom with an escutcheon trim and Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from outside. Key outside retracts latch bolt. Auxiliary latch deadlocks latch bolt and is certified ANSI F07 function compatible. UOI is EA.

FOB-Origin FMP:

\$273.05

Product NSN:

5340-00-NIB-0138

Product Name:

Lockset, Mortise, Office Function, Escutcheon Trim, Philadelphia-style Lever

Product Description:

Mortise lockset for office function with escutcheon trim and a Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either side and is certified ANSI F04 function compatible. UOI is EA.



FOB-Origin FMP: \$273.05

Product NSN: 5340-00-NIB-0263

Product Name: Lockset, Mortise, Classroom Holdback Function, Wide Escutcheon Trim, Philadelphia-style Lever

Product Description: Mortise lockset for a classroom holdback function with a wide escutcheon trim and Philadelphia-style lever. Latch bolt operated by lever from inside. Key outside retracts latch bolt, rigid outside lever, auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F06 function compatible. UOI is EA.

FOB-Origin FMP: \$273.05

Product NSN: 5340-00-NIB-0264

Product Name: Lockset, Mortise, Holdback Function, Wide Escutcheon Trim, Ball Knob

Product Description: Mortise lockset for a holdback function with a wide escutcheon trim and ball knob. Latch bolt operated by lever from inside. Key outside retracts latch bolt, rigid outside lever, auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F06 function compatible. UOI is EA.

FOB-Origin FMP: \$273.05

Product NSN: 5340-00-NIB-0265

Product Name: Lockset, Mortise, Classroom Holdback Function, Escutcheon Trim, Dallas-style Lever

Product Description: Mortise lockset for a classroom holdback function with an escutcheon trim and Dallas-style lever. Latch bolt operated by lever from inside. Key outside retracts latch bolt, rigid outside lever, auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F06 function compatible. UOI is EA.

FOB-Origin FMP: \$273.05

Product NSN: 5340-00-NIB-0278

Product Name: Lockset, Mortise, Storeroom Function, Wide Escutcheon Trim, Ball Knob

Product Description: Mortise lockset for a storeroom with a wide escutcheon trim and ball knob. Latch bolt operated by lever from outside. Key outside retracts latch-bolt. Auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F07 function compatible. UOI is EA.

FOB-Origin FMP: \$273.05

Product NSN: 5340-00-NIB-0279

Product Name: Lockset, Mortise, Storeroom Function, Wide Escutcheon Trim, Dallas-style Lever

Product Description: Mortise lockset for a storeroom with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from outside. Key



FOB-Origin FMP: outside retracts latch-bolt. Auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F07 function compatible. UOI is EA. **\$273.05**

Product NSN: 5340-00-NIB-0280
Product Name: Lockset, Mortise, Office Function, Ball Knob
Product Description: Mortise lockset for an office with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side at all times and is certified ANSI F07 function compatible. UOI is EA.

FOB-Origin FMP: **\$273.05**

Product NSN: 5340-00-NIB-0281
Product Name: Lockset, Mortise, Office Function, Wide Escutcheon Trim, Dallas-style Lever
Product Description: Mortise lockset for an office with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from either side at all times and is certified ANSI F07 function compatible. UOI is EA.

FOB-Origin FMP: **\$273.05**

Product NSN: 5340-00-NIB-0140
Product Name: Lockset, Mortise, Corridor Function, Escutcheon Trim, Philadelphia-style Lever
Product Description: Mortise lockset for a corridor with an escutcheon trim and Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either sides. Key outside extend/retracts deadbolt. Thumb-turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Lockset is certified ANSI F13 function compatible. UOI is EA.

FOB-Origin FMP: **\$285.19**

Product NSN: 5340-00-NIB-0266
Product Name: Lockset, Mortise, Front Door/Corridor Function, Escutcheon Trim, Philadelphia-style Lever
Product Description: Mortise lockset for a front door or corridor function with an escutcheon trim and Philadelphia-style lever. Toggle locks/unlocks outside lever. Key outside retracts latch bolt. Key outside extends/retracts deadbolt; thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F08 function compatible. UOI is EA.

FOB-Origin FMP: **\$285.19**

Product NSN: 5340-00-NIB-0267
Product Name: Lockset, Mortise, Front Door/Corridor Function, Wide Escutcheon Trim, Ball Knob
Product Description: Mortise lockset for a front door or corridor function with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key outside



retracts latch bolt. Key outside extends/retracts deadbolt; thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F08 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0268

Product Name:

Lockset, Mortise, Front Door/Corridor Function, Escutcheon trim, Dallas-style Lever

Product Description:

Mortise lockset for a front door or corridor function with an escutcheon trim and Dallas-style lever. Toggle locks/unlocks outside lever. Key outside retracts latch bolt. Key outside extends/retracts deadbolt; thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F08 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0269

Product Name:

Lockset, Mortise, Store Door Function, Wide Escutcheon Trim, Philadelphia-style Lever

Product Description:

Mortise lockset for a store door function with a wide escutcheon trim and Philadelphia-style lever. Latch bolt operated by lever from either side. Key inside or outside extends/retracts deadbolt. Key locks/unlocks outside lever. Lockset is certified ANSI F14 function compatible. UOI is EA.

FOB-Origin FMP:

\$300.27

Product NSN:

5340-00-NIB-0270

Product Name:

Lockset, Mortise, Store Door Function, Wide Escutcheon Trim, Ball Knob

Product Description:

Mortise lockset for a store door with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side. Key inside or outside extends/retracts deadbolt. Key locks/unlocks outside lever. Lockset is certified ANSI F14 function compatible. UOI is EA.

FOB-Origin FMP:

\$300.27

Product NSN:

5340-00-NIB-0271

Product Name:

Lockset, Mortise, Store Door Function, Wide Escutcheon Trim, Dallas-style Lever

Product Description:

Mortise lockset for a store door function with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from either side. Key inside or outside extends/retracts deadbolt. Key locks/unlocks outside lever. Lockset is certified ANSI F14 function compatible. UOI is EA.

FOB-Origin FMP:

\$300.27



Product NSN: 5340-00-NIB-0272
Product Name: Lockset, Mortise, Dormitory Function, Wide Escutcheon Trim, Philadelphia-style Lever
Product Description: Mortise lockset for a dormitory with a wide escutcheon trim and Philadelphia-style lever. Latch bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key inside or outside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt; auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F11 function compatible. UOI is EA.
FOB-Origin FMP: \$304.32

Product NSN: 5340-00-NIB-0273
Product Name: Lockset, Mortise, Dormitory Function, Wide Escutcheon Trim, Ball Knob
Product Description: Mortise lockset for a dormitory with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key inside or outside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt; auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F11 function compatible. UOI is EA.
FOB-Origin FMP: \$304.32

Product NSN: 5340-00-NIB-0274
Product Name: Lockset, Mortise, Dormitory Function, Wide Escutcheon Trim, Dallas-style Lever
Product Description: Mortise lockset for a dormitory with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key inside or outside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt; auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F11 function compatible. UOI is EA.
FOB-Origin FMP: \$304.32

Product NSN: 5340-00-NIB-0139
Product Name: Lockset, Mortise, Passage Function, Escutcheon Trim, Philadelphia-style Lever
Product Description: Mortise lockset for a passage with an escutcheon trim and Philadelphia-style lever. Grade 1 lockset. Latch bolt operated by lever from either side and is certified ANSI F01 function compatible. UOI is EA.
FOB-Origin FMP: \$226.69

Product NSN: 5340-00-NIB-0282
Product Name: Lockset, Mortise, Passage Function, Escutcheon Trim, Ball Knob
Product Description: Mortise lockset for a passage with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side at all times and is certified ANSI F01 function compatible. UOI is EA.



FOB-Origin FMP: \$226.69

Product NSN: 5340-00-NIB-0283
Product Name: Lockset, Mortise, Passage Function, Wide Escutcheon Trim, Dallas-style Lever
Product Description: Mortise lockset for a passage with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from either side at all times and is certified ANSI F01 function compatible. UOI is EA.

FOB-Origin FMP: \$226.69

Product NSN: 5340-00-NIB-0275
Product Name: Lockset, Mortise, Entrance/Storeroom Function, Wide Escutcheon trim, Philadelphia-style Lever
Product Description: Mortise lockset for an entrance or storeroom with a wide escutcheon trim and Philadelphia-style lever. Latch bolt operated by lever from either side. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F21 function compatible. UOI is EA.

FOB-Origin FMP: \$285.19

Product NSN: 5340-00-NIB-0276
Product Name: Lockset, Mortise, Entrance/Storeroom Function, Wide Escutcheon Trim, Ball Knob
Product Description: Mortise lockset for an entrance or storeroom with a wide escutcheon trim and ball knob. Latch bolt operated by lever from either side. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F21 function compatible. UOI is EA.

FOB-Origin FMP: \$285.19

Product NSN: 5340-00-NIB-0277
Product Name: Lockset, Mortise, Entrance/Storeroom Function, Wide Escutcheon Trim, Dallas-style Lever
Product Description: Mortise lockset for an entrance or storeroom with a wide escutcheon trim and Dallas-style lever. Latch bolt operated by lever from either side. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Lockset is certified ANSI F21 function compatible. UOI is EA.

FOB-Origin FMP: \$285.19

Product NSN: 5340-00-NIB-0284
Product Name: Lockset, Mortise, Corridor Function, Wide Escutcheon Trim, Ball Knob, Dallas-style Lever
Product Description: Mortise lockset for a corridor with a wide escutcheon trim, ball knob and a Dallas-style lever. Grade 1 lockset. Latch-bolt operated by lever from either side. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Inside



lever simultaneously retracts latch bolt and deadbolt, auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F13 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0285

Product Name:

Lockset, Mortise, Corridor Function, Wide Escutcheon Trim

Product Description:

Mortise lockset for a corridor with a wide escutcheon trim. Latch bolt operated by lever from either side. Grade 1 lockset. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt, auxiliary latch deadlocks latch bolt. Lockset is certified ANSI F13 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0286

Product Name:

Lockset, Mortise, Entrance function, Wide Escutcheon Trim, Philadelphia-style Lever

Product Description:

Mortise lockset for an entrance with a wide escutcheon trim and Philadelphia-style lever. Grade 1 lockset. Latch-bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key outside retracts latch bolt, extends deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Projecting then retracting the deadbolt releases the toggle. Lockset is certified ANSI F10 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0287

Product Name:

Lockset, Mortise, Entrance function, Wide Escutcheon Trim, Ball Knob

Product Description:

Mortise lockset for an entrance with a wide escutcheon trim and ball knob. Grade 1 lockset. Latch-bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key outside retracts latch bolt, extends deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Projecting then retracting the deadbolt releases the toggle. Lockset is certified ANSI F10 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0288

Product Name:

Lockset, Mortise, Entrance Function, Wide Escutcheon Trim, Dallas-style Lever

Product Description:

Mortise lockset for an entrance with a wide escutcheon trim and Dallas-style lever. Grade 1 lockset. Latch bolt operated by lever



from either side. Toggle locks/unlocks outside lever. Key outside retracts latch bolt, extends deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Projecting then retracting the deadbolt releases the toggle. Lockset is certified ANSI F10 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0289

Product Name:

Lockset, Mortise, Dormitory/Exit Function, Wide Escutcheon Trim, Ball Knob

Product Description:

Mortise lockset for a dormitory or exit with a wide escutcheon trim and ball knob. Grade 1 lockset. Latch-bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key outside retracts latch bolt. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Lockset is certified ANSI F20 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0290

Product Name:

Lockset, Mortise, Dormitory/Exit Function, Wide Escutcheon Trim, Dallas-style Lever

Product Description:

Mortise lockset for a dormitory or exit with a wide escutcheon trim and Dallas-style lever. Grade 1 lockset. Latch-bolt operated by lever from either side. Toggle locks/unlocks outside lever. Key outside retracts latch bolt. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Lockset is certified ANSI F20 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0301

Product Name:

Lockset, Mortise, Dormitory/Exit Function, Wide Escutcheon Trim, Philadelphia-style Lever

Product Description:

Mortise lockset for a dormitory or exit with a wide escutcheon trim and Philadelphia-style lever. Toggle locks/unlocks outside lever. Key outside retracts latch bolt. Key outside extends/retracts deadbolt. Thumb turn inside extends/retracts deadbolt. Inside lever simultaneously retracts latch bolt and deadbolt. Lockset is certified ANSI F20 function compatible. UOI is EA.

FOB-Origin FMP:

\$285.19

Product NSN:

5340-00-NIB-0291

Product Name:

Lockset, Mortise, Privacy Function, Wide Escutcheon Trim, Ball Knob



Product Description: Mortise lockset for privacy with a wide escutcheon trim and ball knob. Grade 1 lockset. Latch-bolt operated by lever from either sides. Thumb-turn inside locks/unlocks outside lever. Rotating inside lever unlocks outside lever. Lockset is certified ANSI F22 function compatible. UOI is EA.

FOB-Origin FMP: \$251.34

Product NSN: 5340-00-NIB-0292

Product Name: Lockset, Mortise, Privacy Function, Wide Escutcheon Trim, Dallas-style Lever

Product Description: Mortise lockset for privacy with a wide escutcheon trim and Dallas-style lever. Grade 1 lockset. Latch-bolt operated by lever from either sides. Thumb-turn inside locks/unlocks outside lever. Rotating inside lever unlocks outside lever. Lockset is certified ANSI F22 function compatible. UOI is EA.

FOB-Origin FMP: \$251.34

Product NSN: 5340-00-NIB-0293

Product Name: Door Closer, Architectural Commercial Grade with Door Saver Arm, Aluminum

Product Description: Architectural commercial door closer with a door saver/extra duty arm assembly. Grade 1 lockset. Full rack and pinion design, heavy duty cast aluminum closer body. UOI is EA.

FOB-Origin FMP: \$172.80

Product NSN: 5340-00-NIB-0294

Product Name: Door Closer, Architectural Commercial Grade with Door Saver Arm, Cast Iron

Product Description: Architectural commercial door closer featuring a door saver/hold open arm. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.

FOB-Origin FMP: \$172.80

Product NSN: 5340-00-NIB-0295

Product Name: Door Closer, Architectural Commercial Grade with Spring Cushion Stop

Product Description: Architectural commercial door closer featuring a spring cushion stop. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.

FOB-Origin FMP: \$231.13

Product NSN: 5340-00-NIB-0296

Product Name: Door Closer, Heavy Duty Institutional Grade with Door Saver Arm
Product Description: Heavy Duty Institutional door closer featuring a door saver arm function. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.

FOB-Origin FMP: \$272.40



Product NSN: 5340-00-NIB-0297
Product Name: Door Closer, Heavy Duty Institutional Grade with Door Saver, Hold Open Arm
Product Description: Heavy duty institutional grade door closer featuring a door saver plus a hold open arm function. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.
FOB-Origin FMP: \$272.40

Product NSN: 5340-00-NIB-0298
Product Name: Door Closer, Heavy Duty Institutional Grade with Spring Cushion Stop
Product Description: Heavy duty institutional door closer with spring cushion stop. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.
FOB-Origin FMP: \$254.04

Product NSN: 5340-00-NIB-0299
Product Name: Door Closer, Heavy Duty Institutional Grade, Delayed Action
Product Description: Heavy Duty institutional door closer with a delayed closing mechanism. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.
FOB-Origin FMP: \$210.72

Product NSN: 5340-00-NIB-0300
Product Name: Door Closer, Heavy Duty Institutional Grade with Door Arm Saver, Delayed Action
Product Description: Heavy duty institutional door closer with a delayed closing mechanism and door arm saver. Grade 1 lockset. Heavy duty cast iron closer body, forged steel main arm and full architectural cover. UOI is EA.
FOB-Origin FMP: \$292.96

FMPs apply to any orders received by the nonprofit agency on or after the effective date. Future FMPs will be determined according to the price change mechanism indicated. In accordance with 41 CFR 51-2.7, subsequent changes to these FMPs, outside of the approved methodology above and provisions in U.S. AbilityOne Pricing Policy 51.610, *Pricing AbilityOne Products*, must be approved by the Commission before a contract is awarded or an existing contract is modified.

The following information is applicable to all products listed above.

FMP Change Mechanism: Negotiated
FMP Category: Normal
Unit of issue: EA
Distribution: B-List

PL Number: 20150054

- 19 -

Transaction ID: 26146



Contracting Activity: Defense Logistics Agency Troop Support

Mandatory Purchase for: Total Government Requirement

Designated Mandatory Source(s) of Supply: VisionCorps, Lancaster, PA, a nonprofit agency associated with National Industries for the Blind (NIB), is authorized to accept orders for the products listed above.

The change to the Procurement List is effective as of March 6, 2016. In accordance with 41 CFR 51-5.3, this change does not affect contracts for the products awarded prior to the effective date of the Procurement List addition or options exercised under those contracts.



Barry S. Lineback
Director, Business Operations

