



SYMBOL AND LINE LEGEND

•	Bench Mark	○	Round Inlet
●	Control Point	▣	Curb Cast Inlet
⊙	Soil Boring	○	Post
⊕	Manhole	⊕	Light Pole
△	Sign	⊕	Electric Manhole
◇	Finish Floor	⊕	Electric Panel
⊞	Mailbox	⊕	Tree
⊕	Water Manhole	⊕	Pine Tree
⊕	Fire Hydrant	⊕	Handicap
⊕	Water Valve	⊕	Telephone Manhole
⊕	Water Curb Stop		
⊕	Post Indicator Valve		
---	Underground Cable Television		
---	Underground Telephone		
---	Overhead Telephone		
---	Underground Electric		
---	Overhead Electric		
---	Water Line		
---	Fence		
---	Gas Line		
---	Major Contour		
---	Minor Contour		
---	Asphalt		
---	Concrete		
---	Stone		
---	Center Line Ditch		
---	Sanitary Line		
---	Storm Line		
---	Steam Line		

Structure Table

STR.#	Rim	Invert	Invert	Invert
101	762.76	756.41E	755.46W	
102	762.28	758.43NE	756.48E	756.43W
103	762.26	758.56SW		
104	768.24	STEAM		
105	773.86	760.76W	760.86SE	
107	772.10	768.30NE	768.20SW	
108	770.52	765.32NE	766.12W	762.12NW
109	770.26	766.31E	766.31W	763.76B
110	770.33	766.43E	766.53NW	763.33B
111	771.11	STEAM		
112	771.55	768.10E	764.95W	764.85S
113	772.44	362.99B		
114	772.20	368.75N	768.70S	
115	771.57	367.87W	767.82N	
116	770.08	367.68N	767.63E	767.63SE
117	769.95	367.28NE	767.22NW	
118	768.91	364.91SW	762.41B	

B= Bottom of Structure

Control Table

Point #	Northing	Easting	Elevation	Description
501	2129301.12	481117.05	762.88	5/8" Steel Rebar w/"Miller" id. Cap Set
502	2129341.92	481560.01	775.71	5/8" Steel Rebar w/"Miller" id. Cap Set
503	2129334.21	481347.01	768.90	Mag Nail Set
504	2129013.27	481684.78	772.81	5/8" Steel Rebar w/"Miller" id. Cap Set
7777	2129110.12	481175.81	766.39	Southeast Bonnet Bolt on Fire Hydrant
7778	2129305.17	481366.23	770.62	Southeast Bonnet Bolt on Fire Hydrant

FLOOD PLAIN CERTIFICATION
 This property is within Zone "X" (areas determined to be outside the 0.2% annual chance floodplain), City of Fort Wayne, Indiana Community No.180003, Panel No.0305, dated August 3, 2009.

NOTES
 Location and sizes of underground utilities are shown from best available record drawings and/or field markings. Utility lines shown hereon are approximate in location and intended for reference only. Call Indiana Underground Plant Protection Services (IUPPS) at 1-800-382-5544 for field marked location of utilities prior to any excavation.
 Indiana Underground Plant Protection Services (IUPPS) Locate Number For This Project: 1503120370
 Elevations are based upon a INCORS (Indiana Continuously Operating Reference Station Network) Indiana East. Datum = North American Vertical Datum (NAVD88).

CERTIFICATION
 I Brett R. Miller certify that I am a Land Surveyor licensed in compliance with the laws of the State of Indiana; that to the best of my knowledge, information and belief all information shown hereon is true and accurate:

Brett R. Miller
 Brett R. Miller, PLS. 20300059

100% CONSTRUCTION DOCUMENTS

<p>CONSULTANTS:</p> <p>Corporate Office 221 Tower Drive Monroe, IN 46772 Phone: (260) 692-6166 Fax: (260) 692-6242</p> <p>Fort Wayne Office 217 Airport North Office Park Fort Wayne, IN 46835 Phone: (260) 489-8571 Fax: (260) 489-8570</p>	<p>Miller Land Surveying, Inc.</p> <p>Brett R. Miller, PLS. No.LS20300059 Robert J. Marucci, PLS. No.LS20400028 Angela D. Wallace, PLS.No.LS21200016</p> <p>www.mlswebsite.us MLS <i>Precision and Professionalism is where we draw the line.</i></p>	<p>ARCHITECT/ENGINEERS:</p> <p>APOGEE Consulting Group, PA www.apogee.com Apogee Project # 2014-121</p> <p>Raleigh, NC Indianapolis, IN Philadelphia, PA Pittsburgh, PA Virginia Beach, VA Fort Collins, CO Fort Collins, CO (918) 858-7420</p> <p>Civil Engineer GUIDON DESIGN 805 N. Capitol Avenue, STE 100 Indianapolis, IN 46205 Tel: (317) 800-6388</p>	<p>Drawing Title TOPOGRAPHIC SURVEY</p>	<p>Project Title REPLACE MAIN ELECTRICAL TO OUT-BUILDINGS</p>	<p>Project Number 610A4-12-188</p> <p>Building Numbers 1,3,5,6,7,10,14,15,16</p>	<p>Office of Construction and Facilities Management</p> <p>Department of Veterans Affairs</p>
			<p>Approved/Project Director</p>	<p>Location FORT WAYNE, IN</p>	<p>Drawing Number VF101</p> <p>Dwg. 4 of 48</p>	
<p>Revisions:</p>	<p>Date</p>	<p>Date 9/18/2015</p>	<p>Checked BRM</p>	<p>Drawn ADW</p>		