

Questions and Answers Emergency Steel Awnings/Carports

Answers are in **RED**

Q1. The SOW mentions Building Utility Systems which are to be installed, but there is no information about the electrical connection points? What are the locations for the service connections?

A1. The VA will supply power to one corner of each shelter. The contractor will have to come from that point to location within the shelter.

Q2. What are the diameters of the footings? (The 3' depth is the only item listed.)

A1. 18 inch

Q3. What are the base landscaping elevations for each site?

A3. There has not been any elevations shot for these shelters. The area will need to be graded some but not level. Footings will need to be level but the material going on the ground should slope for drainage and can be at different heights.

Q4. From the site visit, it appears that retaining walls may be required for the site work? If retaining walls are required, please provide information concerning the location and dimensions.

A4. Retaining walls will not be required for this project.

Q5. Can the posts and purlin be red primed and painted steel instead of galvanized steel?

A5. Red primed and painted.