

SALIENT CHARACTERISTICS

- Door type washing machine for pots, pans and utensils
- Heavy-duty stainless steel construction
- 28" x 28" x 28" wash chamber
- Revolving upper and lower high pressure spray nozzles
- 2 balanced doors with safety switches
- Recessed, front-mounted controls
- 7.5 HP drip-proof water pump motor
- Front and side enclosure panels
- 6" vent connection
- Electric Heat machine load: 208 Volts/60 Hz/3-phase and 50 Amps or 240 Volts/60 Hz/3-phase and 45 Amps or 480 Volts/60 Hz/3-phase and 22 Amps
- Electric booster: 208 Volts/60 Hz/3-phase and 75 Amps or 240 Volts/60 Hz/3-phase and 65 Amps or 480 Volts/60 Hz/3-phase and 34 Amps
- Amps: 75
- No Booster Heater
- Dimensions (HxWxD) 73" x 35.75" x 36"
- Dishwasher Type Pot & Pan Washer
- Horsepower 7.5
- Incoming Water Temperature 140°F
- Interior Clearance 28"
- Rack Included Yes
- Racks per Hour 25
- Rinse Temperature High-Temp
- Wash Tank Capacity 24 gal
- Wash Tank Usage 10 kW
- Water Used 3.3 gal/rack