



i-Vu® Building Automation System i-Vu® 6.5 Standard, Plus, & Pro

Web User Interfaces







The i-Vu® Building Automation System provides everything you need to access, manage, and control your building, including the powerful i-Vu user interface, plug-and-play BACnet® controllers, and state-of-the-art Carrier equipment.



Manage your facility 24/7, 365 days a year with the powerful i-Vu web user interface. Available in 3 different versions, the i-Vu web user interface allows you to:

- Manage the HVAC equipment in your building from anywhere in the world using a standard web browser.
- View and control the equipment in your building with a variety of PCs, tablets, and mobile devices.
- Graphically configure and view schedules, setpoints, trends, alarms, and reports.
- Integrate, monitor, and control other building systems such as lighting and meters using standard protocols.

i-Vu Web User Interface Feature Comparison

				
		Standard	Plus	Pro
Part Number(s)		CIV-OPN	CIV-OPNPL	CIV-OPNPRUL CIV-OPNPR CIV-OPNPR16
Includes		Web Server & i-Vu Software	Web Server & i-Vu Software	i-Vu Software Only
Networks Supported		BACnet & CCN	BACnet & CCN	BACnet & CCN
Recommended Routing Devices		USB-CCN Adapter USB-MS/TP Adapter Open/CCN Routers	USB-CCN Adapter USB-MS/TP Adapter Open/CCN Routers Open/CCN Links	Open/CCN Routers Open/CCN Links
Total Controllers Supported¹		750	750	Unlimited, 750, or 16
Trend Storage		7 days	62 days	Unlimited ²
Alarm Storage		500	500	Unlimited ²
Audit Log Storage		30 days	30 days	Unlimited ²
Custom Equipment & Trend Reports			√	√
Tenant Billing Override Reports			√	√
Supports i-Vu Add-ons			√	√
Web Services (XML/SOAP) Data Access			√	√
BACnet/Modbus®/LonWorks® Integration			√	√
Location Dependent Access				√

¹A Router or Link is required for every 60 Open controllers or 140 CCN controllers.

²Trends, Alarms, and Audit Log storage capacity is dependent on the database management system that is being used.



i-Vu® Building Automation System

i-Vu® 6.5 Web User Interface



i-Vu® Client Requirements

- Dual core processor, 1.5 GB RAM, 10Mbps or higher LAN communications
- Supports desktop PCs running Windows®, Linux®, and Apple® Mac® PCs running Mac OS X®
- Supports Microsoft® Surface™, Apple® iPad®, and Google™ Nexus (v7 & 10) tablets
- Supports Apple® iPhone® 6 and iPhone® 6 Plus, Nexus 6, and Nokia Lumia™ 830 phones
- Supports Microsoft® Edge, IE® v11, Google™ Chrome™, Mozilla® Firefox®, and Safari® browsers



i-Vu Standard and Plus Server Specifications

- Operating Temperature:** 32°F to 122°F (0°C to 50°C). NOTE: For indoor use only.
- Storage Temperature:** -4°F to 158°F (-20°C to 70°C)
- Storage Humidity:** 5% to 90% RH
- Weight:** 2.4 lb. (1.09 kg)
- Dimensions:** 4.52 in (115 mm) deep x 4.37 in. (111 mm) wide x 1.9 in. (48.7 mm) high
- USB Ports:** (4) USB 3.0 ports for i-Vu network connection or for backing up/restoring system data
- Mini DisplayPorts:** (2) that support a monitor for troubleshooting purposes
- LAN Port:** Integrated Intel® 10/100/1000 Mbps port for Ethernet network connection
- Safety Compliance:** IEC 60950-1, UL 60950-1, EN 60950-1, CAN/CSA-C22.2 No. 60950-1
- Environmental Compliance:** RoHS 2011/65/EU, WEEE 2002/96/EC, China RoHS MII Order #39
- EMC Compliance:** CE, FCC CFR Title 47, Chapter I, Part 15, Subparts A, B



i-Vu Pro Server Requirements (server sold separately)

- Dual core processor, 2GB RAM, 30 GB hard drive, 10Mbps or higher LAN communications
- Operating Systems Supported (32-bit and 64-bit)**
 - Windows 10, 8.1, and 7 Professional, Windows 8.1 Enterprise, Windows 7 Ultimate
 - Windows Server 2012 R2, Windows Server 2008 R2
 - Windows Vista Business or Ultimate SP2
- Database Management Systems Supported (sold separately except for Apache Derby)**
 - Apache Derby (default database; included with i-Vu Pro software)
 - MySQL 5.6
 - MS SQL Server® 2012 Express R2 & 2008 Express R2
 - MS SQL Server 2014 SP1, 2012 R2, & 2008
 - PostgreSQL 8.4 and 9.4



CONTROLS EXPERT

Tested. Certified. Factory Authorized.

For more information, contact
your local Carrier Controls Expert.
Controls Expert Locator:
www.carrier.com/commercial/en/us/find-an-expert

© Carrier Corporation Cat. No. 11-808-422-01 Rev. 05/16
Manufacturer reserves the right to discontinue, or change
at any time, specifications or designs, without notice and
without incurring obligations. All trademarks used herein
are the property of their respective owners.