



FOOD SERVICE EQUIPMENT SCHEDULE

EQUIPMENT SPECIFICATIONS		PREFERRED ENERGY SOURCE				PLUMBING		ALTERNATE ENERGY SOURCE		VENTILATION		ADDITIONAL NOTES			
NO.	ITEM	MODEL	SIZE	SUPPLY	ELECTRICAL	POWER	STEAM	GAS	WATER	WASTE	ELEC.	STEAM	GAS	VENT.	ADDITIONAL NOTES
B1	BEVERAGE COUNTER	FABRICATED	86/6034	VC	12"	1201	6.2A								
B6E	BEVERAGE/ICE DISPENSER	EXISTING UNIT	30/3038	WV	12"	1201	2.5A								FLOOR DRAIN
B9A	ICE MACHINE	HOSHIZAKI KMD-68MMH	30/2422	VC	AF*	1201	15A								12" FLOOR DRAIN
B6E	GOLD PEAK ICE DISPENSER	EXISTING UNIT	91/834	WV	12"	1201	2.5A								1/4"
B10	COFFEE BREWER	ICB TWIN TALL	23/2534	VC	AF*	1202/8	25A								3/8" (3-Wire + Ground)
B11	AIR POT (2)	BLINN ICB 307	86/6113	WV		1201	2.8A								
B13	COFFEE CREAMER	INTERNATIONAL DELIGHT	13/2031	VC	AF*										
C1	CONDIMENT STAND W/ TRAY	FABRICATED	60/3045	VC											
B81	FREEZER WORK TABLE	FABRICATED W/4 COLD WELLS	82/6034	VC	FLOOR BOX	1201	12A								3/4"
B87	FREEZER WORK TABLE	TRIPLE TURBO-CHEF ENCORE	48/3038	VC	12"	1151	6.1A								3/4"
B89	ENCORE OVEN	STRUCT CONCEPTS	33/2223	VC	FLOOR BOX	2081	30A								FLOOR DRAIN
K15	REFRIGERATED HEATED SELF-SERVE MERCHANDISER	STRUCT CONCEPTS HATCO CORP. QP25S-240 WEST/ND	86/3038	VC	48"	2081	30A								FLOOR DRAIN
M1	OFF THE GRILL	FABRICATED W/3 HATCO HDV-18N	84/6034	VC	12"	2081	35A								FLOOR DRAIN
OG1	1-DRAWER WARMER	FRYMASTER PMH-1	20/2510	VC	1201		3.8A								3/8"
OG3	DUMP TABLE W/ HEAT LAMP	DIKE FWV3-42	21/1822	VC	AF*	1201	13.3A								
OG7	HOLDING BIN	APV W/VERT. FRYMASTER CORPORATION	15/1513	VC	18"	1201	15A								
OG10	TOLSTER	GAILAND ED-118	15/3046	VC	AF*	2081	30A								
OG11	FRYER - ELECTRIC	FTL114C	50/388	VC	18"	2081	13A								
OG12	GRID/DEGRADER	FTL114C	50/388	VC	18"	2081	13A								
R1	REGISTER STAND	FABRICATED	47/2849	VC	51/8	1201	15A								
T1	MOBILE TRAY STAND	FABRICATED	18/24	VC	UP										

VV = VCS PURCHASE AND INSTALL
 VC = VCS PURCHASE AND VVAC CONSTRUCTION CONTRACTOR INSTALL
 C* = VVAC CONSTRUCTION CONTRACTOR PURCHASE AND INSTALL

NOTE TO MEDICAL CENTER:

1. ALL CONSTRUCTION AND/OR DEMOLITION SHOWN ON PLANS IS THE RESPONSIBILITY OF THE MEDICAL CENTER, OR ITS DESIGNATED REPRESENTATIVE/CONTRACTOR, INCLUDING, BUT NOT LIMITED TO, EQUIPMENT REMOVAL, DISCONNECTING & INSTALLING NEW UTILITIES, WALL REMOVAL, CEILING REMOVAL, AND THE INSTALLATION OF NEW CEILING, LIGHTING AND DUMPSTER FOR CONSTRUCTION DEBRIS.
2. ALL VCS PROVIDED EQUIPMENT MUST BE PROPERLY RECEIVED AND SECURELY STORED BY THE MEDICAL CENTER AS IT ARRIVES. REQUESTED DELIVERY DATES SHOULD BE SCHEDULED WITH THE VCS GENERAL OFFICE AS SOON AS POSSIBLE TO ENSURE TIMELY DELIVERY FOR THE INSTALLATION OF ALL FOOD EQUIPMENT AND RELATED SUPPLY ASSETS AND SCHEDULE WITH THE NOTATION "CC" AND "VC".
3. SECURITY CAMERAS ARE TO BE INSTALLED AT TYPICAL LOCATION (E.G. CASH REGISTER, ENTRANCES, STOCKROOM, FOOD LINE, KITCHEN, ETC.). THE EXACT LOCATION WILL BE DETERMINED BY VCS VENDOR AND COORDINATED WITH LOCAL ENGINEERING SERVICE DURING SITE VISIT BY VCS SECURITY VENDOR.

LEGEND

- ===== EXISTING WALLS TO BE REMOVED
- ===== NEW FULL-HEIGHT WALL
- ===== NEW 8'-0" HIGH WALL (8'-0" + 12" EXPOSED G/ASS)
- ===== EXISTING WALL TO REMAIN

UTILITY LEGEND

- ⊕ 2" 120V OUTLET WITH EQUIPMENT NUMBER
- ⊕ 3" 208V OUTLET WITH EQUIPMENT NUMBER
- ⊕ 3" SPARE 120V OUTLET
- ⊕ 9" J-BOX WITH EQUIPMENT NUMBER
- ⊕ 9" STUB UP WITH EQUIPMENT NUMBER
- ⊕ C COLD WATER
- ⊕ H H HOT WATER
- ⊕ D DRAIN
- ⊕ G GAS
- LAN LAN (LOCAL AREA NETWORK)
- OUT TELEPHONE LINE OUTBOUND ONLY
- ☐ ☐ DOME SECURITY CAMERA

* NOTE: FABRICATE COUNTER PIECES NO LONGER THAN 8'-0" FOR EASE OF DELIVERY. IF SHOWN LARGER ABOVE, BREAK INTO MULTIPLE PARTS.