

SUMMARY OF CHANGES

17. In response to note 7 of Amendment 2, I did a word search of the spec for “pneumatic tube.” It could not be found. I also looked through the plans for note G from page AS200 and could not find where a new station would go. Please clarify.

In response to the second part of the question, the p/t station is located on the first floor in Corridor C1-18B, near the door to Blood Draw M1-220.

18. Am I to include ALL wall protection in the alternate deducts, the statement about Perimeter walls to remain the same is making me wonder if the wall protection stays.

With respect to wall protection, any walls shown as remaining (with the exercise of any of the deduct-alternates) are to be built as shown on the base plan(s), unless otherwise noted. If those remaining walls are indicated to have wall protection on the base plan(s), then they are to have wall protection when the deduct-alternate is exercised.

19. Please provide a soils report for the project.

See attached 110407 Soil Boring Log

20. Is Builder Board an equivalent/replacement to “Reinforced Kraft paper”? In the Job Conditions of finished work section of Page 7 of the 09 65 16 Resilient Sheet Flooring specification.

With respect to the question about ‘Builder Board’, this product is considered acceptable for the protection of existing / finished floor work.

21. Attached Addendum No 1 Electrical 08.18.2017 is provided for the electrical scope of work.

END SUMMARY OF CHANGES