

SALIENT CHARACTERISTICS

- Heavy-duty stainless steel construction
- Pass-thru design
- 2 counter-balanced lift doors
- Capacity: 12 pans
- Stainless steel V jets
- Load/unload tabling
- Simple digital controls and display
- Self-contained water heating
- 12 kW built-in electric booster heater
- Separate wash and rinse tanks
- 7.5 HP wash pump motor
- External pre-rinse and wash-down hose
- Moisture resistant gauges display wash temperature, wash pressure and rinse temperature
- Electrical specifications: 120 Volts/1-phase and 5 running Amps along with the electric powered booster that operates at either 208 Volt/3-phase and 69 Amps, 240 Volt/3-phase and 63 Amps or 480 Volt/3-phase and 32 Amps
- Ship Weight 1,100 LB
- Manufacturer Champion
- Model Number PP-12-PT
- Manufacturer Part # PP-12-PT
- Amps 69
- Booster Heater Included Yes
- Booster Tank Capacity 6 gal
- Dishwasher Type Pot & Pan Washer
- Horsepower 7.5
- Incoming Water Temperature 120°F
- Interior Clearance 28.5"
- Rack Included Yes
- Racks per Hour 10
- Rinse Temperature High-Temp
- Wash Tank Capacity 20 gal
- Wash Tank Usage 12 kW
- Water Used 2.8 gal/rack