



SUMMARY OF QUANTITIES			
ITEM #	DESCRIPTION	UNITS	ESTIMATED
1	MOBILIZATION/DEMOLITION	LS	1
2	AC REMOVAL	SF	400
3	OVEREXCAVATION/BACKFILL (CONTINGENT ITEM)	CY	100
4	TYPE 2 CLASS B AGGREGATE BASE (6" THICK)	SY	45
5	ASPHALTIC CONCRETE (6" THICK)	SF	320
6	ASPHALTIC CONCRETE (4" THICK)	SF	80
7	REMOVE AND REPLACE CONCRETE WALK	SF	240
8	REMOVE AND REPLACE CONCRETE DRIVEWAY	SF	120
9	PCC VALLEY GUTTER	LF	16
10	PCC MEDIAN CURB	LF	58
11	PCC CURB AND GUTTER	LF	10
12	8" DUCTILE IRON PIPE W/ 4" INSULATION	LF	1,140
13	PIPE SUPPORTS	EA	120
14	CONCRETE UTILITY CHANNEL W/ LID	LF	557
15	48" MANHOLE	EA	4
16	4-INCH WIDE SOLID WHITE STRIPING	LF	40
17	REMOVE AND RESTORE DISABLED PARKING SPACE LEGEND	EA	1
18	FLOOR DRAIN	EA	2

**TWO DAYS BEFORE YOU DIG
CALL USA TOLL FREE
1-800-227-2600**

UNDERGROUND UTILITY NOTE:
The types, location, sizes, and/or depths of existing underground utilities as shown on this survey were obtained in part from field and office compilation, the latter being a source of varying reliability. A reasonable effort has been made to locate and delineate all known utilities. However, the surveyor can assume no responsibility for the completeness or accuracy of the delineation of such underground utilities nor for the existence of other buried objects or utilities which may be encountered but which are not shown on this drawing.

**FOR REFERENCE ONLY
RECORD DRAWINGS FOR UTILITY CHASE**

Revisions	Date
ADD BUILDING FOOTING NOTE.	3/25/09
REVISE PLAN AND PROFILE.	7/14/09
RECORD DRAWING	7/10/14

CONSULTANTS:



Stantec Consulting Inc.
Suite 200, 6995 Sierra Center Parkway
Reno NV U.S.A.
89511
Tel. 775.850.0777
Fax. 775.850.0787
www.stantec.com

ARCHITECT/ENGINEERS:



DINTER ENGINEERING Co.
385 GENTRY WAY
RENO, NV 89502
(775) 826-4044
FAX 826-4190

CONSULTING ENGINEERS FOR:
MECHANICAL
ELECTRICAL
AIRFIELD ELECTRICAL SYSTEMS

Drawing Title
CIVIL PLAN AND PROFILE

Approved Project Director

Project Title
VAMC - BUILDING 1
MECHANICAL HVAC UPGRADE
RENO, NV.

Project Number
654-07-163ES

Building Number
n/a

Drawing Number
C 10

Dwg 328 of 329

Office of Facilities Management

Department of Veterans Affairs

Date
8-8-08

Checked
JB

Drawn
KL

