



MEMORANDUM

Date: August 15, 2017

To: Ms. Kimina Chisolm, Project Engineer/ FAC-COR II

From: Carla Billingslea, EBA

CC: Flora Taylor, VA, Contracting Officer; Arben Pejo, VA, Project Manager;
Ernest Bland, EBA

Re: VAMC DC Sterile Processing Service Expansion & Renovation
Bid Documents – Addendum No. 1

ADDENDUM NO. 1

Architectural

1. The following statement needs to be revised for New Work Note 1 on Sheet AP-102 and New Work Key Note 3 on Sheet AP-103 to read as follow:
 - a. Line of concrete slab infill at removed dumbwaiter locations between the Basement/ Sub-Basement and Basement/First Floor Levels. Concrete infill is to be provided between Basement/Sub-Basement Level only at E7C. Provide UL Design No. D985 – 2hr fire rating. Include spraying all steel and metal members and underside of metal decking. Provide 2 hr fire rated expansion filler joint at perimeter of all new slab infills.
2. Add the following note to Detail 3/AS-504
 - a. Provide UL Design No. D985 – 2hr fire rating at underside of depressed slab. Include spraying all steel and metal members and underside of metal decking. Provide 2 hr fire rated expansion filler joint at perimeter of new slab depression.

Electrical

3. The following sketch has been provided for Sheet EP-301.
 - a. SKE-1: Added receptacle for TV in Sterile Storage GE133. See attached.
4. The following Division is included as part of Addendum No. 1.
 - a. Division 28: See attached.

Structural

5. The following sketch has been revised for Sheet SS303.
 - a. SKS-1: See attached.