

Equip ID	Equipment Name	New Qty	Reuse Qty	Manufacturer	Model	Part	Provides	Installs	Specifies	Approves	Mounting	HVAC	Plumb	Volts	~	Hz	Phase	Amps	Watts	"w	"d	"h	Weight (lbs.)	Description	Henry Adams' Drawing No.	
STERP07	Peroxide Plasma Sterilizer- Pass-Through	2	0	Advanced Sterilization Prod.	Sterrad 100NX Double-Door	10104-002	Contractor	Contractor	Eq Plnr	Owner	FloorStd	Y		208 AC	60	Three	13		2363max	31	40	70.5	962	FDA approved double-door, pass-through, low temperature peroxide plasma sterilizer which uses a combination of hydrogen peroxide vapor and low-temperature gas plasma to rapidly sterilize a wide variety of medical instruments and materials. Network connectivity enables data tracking and record keeping. It will interface with instrument tracking programs or a flash drive may be used in the USB port. Chamber size is (WxDxH) 20.1 in x 28.9 in x 16.1 in (510mm x 735 mm x 410 mm). Trim kit is not manufacturer installed. Pricing includes sterilizer, trim kit, and installation of sterilizer.	EQ-076	
TABLW41	Stainless Steel Work Table 6" w/Casters	1	0	Eagle Group	T3672SEB, CA4-SB		Owner	Owner	Eq Plnr	Owner	FloorStd									72	36	39.1	104	Stainless steel top, stainless steel crossbracing and legs. Weight capacity of 275 lbs with 4" locking casters, zinc w/ poly tread (2 swivel, 2 locking).		
TABLW48	Process Table, 48"w x 30"d	1	0	Herman Miller Inc.	Co/Struc Process Table		Owner	Owner	Eq Plnr	Owner	FloorStd									48	30	29				
TABLW49	Process Table, 60"w x 30"d	1	0	Herman Miller Inc.	Co/Struc Process Table		Owner	Owner	Eq Plnr	Owner	FloorStd									60	30	29				
TABPP18	Prep & Pack Table with Riser	7	0	STERIS Corporation	ErgoStat Deluxe	CG11	Contractor	Contractor	Eq Plnr	Owner	FloorStd			120 AC	60	Single	2.2			73	44	79.5	437.5	Electric Height Adjustment, Lockable casters, 36 x 72" Stainless steel surface, Riser frame, Task light (two bulb), Electric plug strips, Vertical CPU holder, Task drawer, 36" Spool holder, 36" Dispensing rail, Seven Subcontainers, Multifunction shelf, 15 x 36" Tackboard, Flat screen arm (saddle mount). It is capable of handling evenly distributed loads of up to 500 lbs. (227 kg).	EQ-077	
TABPP18A	Vendor Assembly/Installation of Prep Tbl	7	0	STERIS Corporation	ErgoStat Installation	SE115062	Contractor	Vendor	Eq Plnr	Owner	FloorStd															EQ-078
TELEF02	Flat-Panel 70" LED Television	1	0	Sharp Electronics Corporation	70" Class LED Smart TV	LC-70CG400U	Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd			120 AC	60	Single				64	3.5	38.4	79.4	1080p edge lit LED	EQ-079	
TELEZ11	Wall Mount for 42" Tracking Board	0	0	Peerless Industries Inc.	SmartMount ST650		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd									31	2.6	18.5	7.9	Supports most 32" to 56" flat panel screens. Tilt range from 15° forward to 5° backward without the use of tools. Tilt angle can be locked in place if desired. Includes hardware for installation to wood studs, concrete, cinder block, or metal studs. Load capacity of 175 lbs. Security Hardware.	EQ-081	
TELEZ71	Flat Panel Wall Mount, 55" to 82"	1	0	Chief Manufacturing Inc.	XSMU	Fusion Series	Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd									48	2.2	16.5	28	Holds display 1.83" (46mm) from the wall. Horizontal display adjustment up to 12" (304mm) for centering display on wall. Safety latch ensures display is securely attached to wall plate. Fits displays with mounting hole patterns up to 111.1mm x 745 mm (43.75" w x 29.31" h). Wall plate knockouts provide wall access, improving cable management options. Supports M10 mounting bolts. Wood stud, concrete, cinder/breeze block; accessory required for metal studs.	EQ-082	
TELEZ71A	Metal Stud Anchor Kit for Wall Mount	1	0	Chief Manufacturing Inc.	PAC115		Contractor	Contractor	Eq Plnr	Owner	Accssry												1	Kit of four (4) anchors allows installation of large flat panel TVs to metal studs. The weight capacity is dependent on which mount is used. Kits include 1/4-20 screws, 1/4 washers and heavy-duty toggler anchors. Drywall must be at least 0.5" (13 mm) thick. Compatible with all FUSION and FIT wall mounts and Thinstall dual stud swing arm wall mounts.	EQ-083	
TERMA65	All-In-One Computer with 20" Touchscreen	26	0	Lenovo	M71z		Owner	Owner	Info Sys	Owner	Counter			120 AC	60	Single		150		20	4.2	16.2	19.6	20" all-in-one computer with WSXGA display. Intel H61 chipset. Integrated Intel GMA HD graphics card.	EQ-084	
TERMW01	Wall Mount for CPU, Monitor, & Keyboard	0	0	Ergotron Inc.	LX Wall Mount, 45-247-026	(Replaces LX 45-238-194)	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd												49	Wall mount system includes mount for Medium CPU, LCD monitor, and keyboard, while providing vertical and side-to-side motion. Monitor mounting standards: VESA FDMI MIS-D, 100/75, C (hole pattern: 100 x 100 mm & 75 x 75 mm). Silver. Articulating arms feature full tilt/pan capability and 13" (33 cm) height adjustment. Extends LCD up to 25" (64 cm); keyboard tray extends up to 35" (89 cm). Keyboard folds to within 3.5" (9 cm) of wall in storage position. LCD arm folds back to a depth of 5.3" (13 cm). CPU Size Range: 3-3/8" to 8" (9 to 20 cm) wide; CPUs down to 2" (5 cm) wide can be accommodated by installing the included CPU spacer within the holder.	EQ-085	
TERMW24	Wall Mount for Monitor, Keyboard, CPU	3	0	Bialek Environments	StyleView Sit Stand Combo Sys.	45-271-026	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd									27	40	29.3	38.4	For LCD Monitor 24" or less. Includes HD Combo Arm, 34" Wall Track with (2) black track covers, Medium Silver CPU Holder, CPU spacer, two 10" cable channels, CPU and Arm track mount bracket kits, Wall Track fasteners for concrete and wood, CPU direct wall mount kit, height-adjustable LCD mount, wrist rest, scanner and mouse holders, integrated keyboard tray, handle, VESA monitor mounting kit (100 x 100 mm and 75 x 75 mm), cable ties. Weight capacity: display = 6-18 lbs (2.7-8.2 kg) or up to 25 lbs (11.4 kg) with tilt and lift lock-out features engaged; keyboard, mouse and barcode scanner = 4 lbs (1.8 kg); CPU = 40 lbs (18 kg). Keyboard tray: 18.6" w x 9" d. CPU Size Range: 3-3/8" to 8" (9 to 20 cm) wide; CPUs down to 2" (5 cm) wide can be accommodated by installing the included CPU spacer within the holder. CPU Holder includes fasteners for locking the holder's width.		
TRUCP12	Hand Pallet Truck	1	0	W.W. Grainger Inc.	Dayton 4YX96	4YX96	Owner	Owner	Eq Plnr	Owner	FloorStd									27	62		170	Load capacity: 6000 lbs. 27"width across forks; 14.42" between forks. Each fork is 48" long x 6.25"w. Fork height: 2.88"h (lowered) - 7.75"h (raised). 7.25" diameter polyurethane wheels; 2.88" diameter polyurethane rollers. Cushion grip with three-position lever, and a flow valve for controlled lowering. Push rods are fixed with no adjustment needed. One-piece cast pump with leakproof double seal. Top-of-stroke bypass protects pump from overpressure. Red.	EQ-087	
WASHC87	Case Cart and Utensil Washer	1	0	STERIS Corporation	VISION 1327		Contractor	Contractor	Eq Plnr	Owner	Maj Inst		Y	480 AC	60	Three			124	130	113	7483	For washing, low-level disinfection and drying of case carts, containers, utensils, beds, and other miscellaneous reusable items. Effective chamber load capacity: 40" w x 106" d x 80" h. Tempered glass doors provide full-size viewing inside the chamber. Has eight factory-set adjustable cycles; eleven additional cycles are available for customized programming. Unit can be built to seismic design.	EQ-088		
WASHC87A	Instrument Wash Option on Cart Washer	0	0	STERIS Corporation	Instrument Cycle Package	(for 1327)	Contractor	Contractor	Eq Plnr	Owner	Accssry													Package allows the cleaning and intermediate level disinfection of soiled hard-surfaced rigid surgical instruments (e.g., forceps and clamps). Option comes with an Enzyme injection line, a coupling system for manifolded rack, a Vision instrument washing manifolded rack, detergent flow meters and an Instrument Cycle.		
WASHC87V	Vendor Installation of Cart Washer	1	0	STERIS Corporation			Contractor	Vendor	Eq Plnr	Owner	Maj Inst									42	31	80	1187		EQ-089	
WASHD75	Pass Thru-Washer/Disinfector, Steam	3	0	STERIS Corporation	5052		Contractor	Contractor	Eq Plnr	Owner	Maj Inst		Y							30	29	40.3	44	Single chamber steam-heated washer/disinfector. Electric heated unit.	EQ-090	
WASHD75A	Transfer Cart , Unassembled	3	0	STERIS Corporation	Universal Transfer Cart	FD21800	Contractor	Contractor	Eq Plnr	Owner	Maj Inst															EQ-091
WASHD75B	Three-Level Manifold Rack	3	0	STERIS Corporation	Manifold Rack	FD74900	Contractor	Contractor	Eq Plnr	Owner	Maj Inst															EQ-092
WASHD75Z	Vendor Installation of WasherDisinfector	3	0	STERIS Corporation			Contractor	Vendor	Eq Plnr	Owner	Maj Inst															EQ-093
WASHD80	Built-In Domestic Dishwasher, 24"	1	0	Frigidaire (div of Electrolux)	FDB2410HC (stainless)		Contractor	Contractor	Eq Plnr	Owner	FloorStd		Y	120 AC	60	Single	10.0		24	23	34.9	65	ADA Compliant. Features: Built-in installation, Tall-tub design, Stainless Steel interior, Delay start, High temperature wash, Removable Stainless Steel filter, No heat dry option, 5 Wash levels, China/Crystal Cycle, 4 Leveling legs. Depth (with Door 90° Open): 46".			
WASHD80A	Dishwasher Installation Kit	1	0	Home Depot	Dishwasher Installation Kit		Contractor	Contractor	Eq Plnr	Owner	Accssry															
WASHD80Z	Dishwasher Installation	1	0	Home Depot	Dishwasher Installation		Contractor	Contractor	Eq Plnr	Owner																
WASTE01	Fire-Resistant Waste Receptacle, 28 Qt	9	0	Rubbermaid Commercial Products	2543 (priced per 1; sold per 6	Grainger # 5M74x	Owner	Owner	Eq Plnr	Owner	FloorStd									15	11	15.3	4	Fire-resistant fiberglass construction. UL classified. Nominal volume: 28 US quarts (26.5 Liters). Priced per each receptacle, sold in packages of six. Available in Beige, Black, or Grey.	EQ-094	
WASTE03	Waste Receptacle, 23 Gallon	21	0	Rubbermaid Commercial Products	3540 Slim Jim		Owner	Owner	Eq Plnr	Owner	FloorStd									20	11	30	8	Budgeted for one, sold in cases of four. 23 gallon capacity. Does NOT have venting channels.	EQ-095	
WASTE04	Waste Receptacle, 44 Gallon	3	0	Rubbermaid Commercial Products	2643 Brute	(priced per 1; sold per 4)	Owner	Owner	Eq Plnr	Owner	FloorStd									24	24	31.5	12.4			EQ-096
WASTE04A	Dolly for Waste Receptacle	3	0	Rubbermaid Commercial Products	2640 Brute Dolly	(priced per 1; sold per 2)	Owner	Owner	Eq Plnr	Owner	Accssry									19	19	6.6	13.1	Black. Twist on/off. Priced per each; sold in packages of two.	EQ-097	
WASTE21	Fire-Resistant Waste Receptacle, 40 Qt	9	0	Rubbermaid Commercial Products	2544 Fire Resistant	(Priced per one; sold 4/pkg)	Owner	Owner	Eq Plnr	Owner	FloorStd									15	11	20		Fire-resistant fiberglass construction. UL classified. Nominal volume: 40 U.S. quarts (37.9 Liters). Priced per receptacle, but usually sold 4 to a package. Beige.	EQ-098	
WATER41	Reverse Osmosis System with Deionizer	1	0	AmeriWater	RO4 Model 00HCS-2057		Contractor	Contractor	Eq Plnr	Owner	Maj Inst		Y	220 AC	60	Single				105	36	94	2458	Reverse osmosis system, a deionizer polisher, and a storage tank with demand pump package. 185 gallon tank; system provides up to 5600 gallons per day. Provides low conductivity water for washers, disinfectors, glassware washers, steam boilers and final rinses. Tap water enters the system through the filters, after which the anti-scalant chemical is pumped into the flow to the reverse osmosis pump and membranes. DI product water flows to the 185 gallon storage tank, reject concentrated waste water flows to the drain (product and reject are 50% each). The demand pump runs when flow is needed.	EQ-099	
WATER41X	Vendor Installation of RO Water System	1	0	AmeriWater			Contractor	Vendor	Eq Plnr	Owner	Maj Inst															
ZPAPR45	Battery-Operated Paper Towel Dispenser	14	0	Georgia-Pacific Corporation	enMotion Impulse 10	59487 (Blue) or 59488 (Smoke)	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd									15	9.8	13.3	6.3	Automated, touchless dispenser operates on 3 D-Cell alkaline batteries (included with order). Adjustable settings for sheet length, time delay, and dispense mode. Uses same towel as enMotion Classic Towel Dispensers. Only available via a one-time, lifetime lease agreement through Georgia-Pacific or authorized distributor. Color is Splash Blue.	EQ-102	
ZSKIN01	Sanitizing Foam Dispenser	17	0	STERIS Corporation	Alcare Dispenser Bracket	T603Q7 (Replaces T525)	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd									2.5	2.8	11.4	1	Bracket typically provided at no cost with the purchase of skin care product. Bracket must be ordered from Steris to avoid GPO handling charges.	EQ-103	
ZSOAP21	Foam Soap Dispenser	14	0	Ecolab Professional Products	Huntington Foam Dispenser	92723188	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd									4	6.8	9.3	2	Dispenser for foaming skin care products. ADA compliant. Various dispenser mounting adapters are available for wall protection; see cutsheet.	EQ-104	

The specifications shown above represent the Basis of Design. Equipment manufacturers and models presented should be considered non-proprietary.

Revision No.3 - Trailer Removal	06/26/17
Addendum No. 2	08-17-17
Revisions:	Date

CONSULTANTS:

**ROBERT L. SEYMOUR & ASSOCIATES, INC.**  
TRANSPORTATION  
ROBERT L. SEYMOUR & ASSOCIATES  
180 Thomas Johnson Drive  
SUITE 200  
FREDERICK, MARYLAND 21702

**STRUCTURAL, CIVIL, COST ESTIMATING**  
ALPHA CORPORATION  
1800 WASHINGTON BOULEVARD  
SUITE 405  
BALTIMORE, MD 21203

**HENRY ADAMS**  
Consulting Engineers  
MECHANICAL ELECTRICAL & PLUMBING ENGINEERS  
**MEP ENGINEERS**  
HENRY ADAMS  
600 BALTIMORE AVENUE  
BALTIMORE, MD 21204

**KORBEL ASSOCIATES**  
Fire Protection Engineers  
MEDICAL EQUIPMENT PLANNING  
**KORBEL ASSOCIATES INC.**  
8700 WEST 27TH STREET, SUITE 278  
MINNEAPOLIS, MN 55408

**INDUSTRIAL HYGIENISTS**  
AGRICOLA MONITORING & ANALYSIS, INC.  
1331 ASHTON ROAD, P.O. BOX 646  
HANOVER, MARYLAND 21076

ARCHITECTS / ENGINEERS:

**ERNEST BLAND ASSOCIATES, P.C.**  
TECHNICAL FACILITIES DESIGN  
802 SLIGO AVENUE, SILVER SPRING, MARYLAND 20910  
TELEPHONE (301) 589-4811 FAX (301) 589-3810

Drawing Title

EQUIPMENT SCHEDULE

Approved: Project Director

Project Title

SPS RENOVATION

Location

WASHINGTON DC VA MEDICAL CENTER

Date

06-26-2017

Checked

Checker

Drawn

Author

Project Number

688-14-003

Building Number

BUILDING NO. 1

Drawing Number

EQ106

Office of Construction and Facilities Management

Department of Veterans Affairs

Project Status