

Equip ID	Equipment Name	New Qty	Reuse Qty	Manufacturer	Model	Part	Provides	Installs	Specifies	Approves	Mounting	HVAC	Plumb	Volts	~	Hz	Phase	Amps	Watts	"w	"d	"h	Weight (lbs.)	Description	Henry Adams' Drawing No.			
ALLOW98	Allowance- Instrument Tracking System	1	0	Getinge USA Inc.	T-DOC Tracking System		Owner	Owner	Eq Plnr	Owner																EQ-001		
BENCH11	Locker Room Bench, Non-Fixed	4	0	Global Industrial	Bench & Legs (sold separately)	T9AB491183/T9AB490841	Owner	Owner	Int Des	Owner	FloorStd										48	12	17.3	60	Solid plastic locker bench top made of high density polyethylene for sanitary environments has stainless steel trapezoid legs. Legs and top are sold separately. Has 15 year warranty.			
BOARD03	Allowance- Tackboard, 48" w x 36" h	6	0	(Manufacturer Unknown)	(Interior Designer to Specify)	(based on Claridge 751F)	Owner	Contractor	Int Des	Owner	Wall-Mtd										48	1	36	24	Based on wood frame, fabric covered cork.	EQ-002		
BUCKM03	Stainless Steel Mop Bucket, 8 Gallon	2	0	Geerpres Inc.	2223	Stainless Steel Round Bucket	Owner	Owner	Eq Plnr	Owner	FloorStd										17	17	17	16	Floorstanding stainless steel bucket.	EQ-003		
CABEN18	Endoscope Storage Cabinet	4	0	Stanley InnerSpace	3800DA		Owner	Owner	Eq Plnr	Owner	FloorStd										36	18	92	200	Holds 16 large diameter endoscopes. Locking counterbalanced tambour door.	EQ-004		
CARHK18	Housekeeping Cart	2	0	Rubbermaid Commercial Products	9T75 Housekeeping Cart		Owner	Owner	Eq Plnr	Owner	FloorStd										22	48	53.5	70	7.25 cubic feet of locking cabinet area. JCAHO compliant: Locking cabinet doors on both sides of cart, locking security hood, and waste cover. Lock 'N Go bucket attachment available. Designed for use with all Rubbermaid Commercial Products Microfiber products. Rubber tool grips hold handles upright. 4" casters and 8" wheels. Includes two removable 10-quart disinfecting caddies. Non-rusting aluminum and structural web plastic construction. Comfort grip cart handle. Lobby dust pan/vacuum holder. Hooks hold up to four safety signs. Locking mechanism added for attaching accessories.	EQ-005		
CARSY18	Top-Track Shelving System, 17'	2	0	InterMetro Industries Corp.	Top Track		Contractor	Contractor	Eq Plnr	Owner	FloorStd										205	64	87		Shelving system consists of 4 moveable carts and 2 stationary end units. Both stationary and all movable units are 60" w x 24" d. Track length is 13' and overall (nominal) length of system is 17'.	EQ-006		
CARSY59	Top-Track Shelving System, 12' Long	2	0	InterMetro Industries Corp.			Contractor	Contractor	Eq Plnr	Owner	FloorStd										145	64	86	949	Includes 3 mobile (24" w x 60" d x 86" h) units between two stationary end units (18" w x 60" d x 86" h). Top track rail length is 9'. One 32" w aisle. Each unit has 5 wire shelves. The recommended maximum load for each mobile unit is 900 lbs.			
CARTM60	Process Table	1	0	Herman Miller for Healthcare	Co/Struc Process Table	C4215.2448	Owner	Owner	Eq Plnr	Owner	FloorStd										48	24	29		Freestanding, height-adjustable work surface with locking casters. Includes two pair of drawer bearers and supports C frames (4 max.). Laminate top. Complete cart by adding accessory components.			
CARTS03	Surgical Case Cart, Upright	7	3	Pedigo	CDS-233-C	End "C" adds shelves auto	Owner	Owner	Eq Plnr	Owner	FloorStd										29	29	56	155	Enclosed case cart transports sterile packs from central supply to surgery. All welded stainless steel construction; 5" (12.7cm) casters, wrap-around bumper; two stainless steel wire shelves.	EQ-010		
CARTS26	Enclosed Surgical Case Cart	7	3	Pedigo	CDS-242		Owner	Owner	Eq Plnr	Owner	FloorStd										46	29	39		For transporting sterile packs from central supply to surgical suite. All welded stainless steel construction. Four plate-mounted 6" swivel casters. Pull handles on both ends; wrap-around bumper on all sides mounted away from cart. Interior dimensions: 40" w x 23.5" d x 27.5" h. Adjustable shelves (wire or solid) specified separately.	EQ-011		
CARTS96	Endoscope Tray Cart	2	0	Medical Innovations [Medicart]	Cleanascope, 6 Tray		Owner	Owner	Eq Plnr	Owner	FloorStd										21	22	36.4		Cleanascope® is a unique transport and short term storage solution for endoscopes and other delicate equipment, which minimises direct handling and airborne contamination.	EQ-012		
CARTS96A	Endoscope Tray Liners for Tray Cart	2	0	Medical Innovations [Medicart]	Cleanascope Liners	103580 (Pack of 200)	Owner	Owner	Eq Plnr	Owner	FloorStd														Cleanascope® is a unique transport and short term storage solution for endoscopes and other delicate equipment, which minimises direct handling and airborne contamination.	EQ-013		
CARTU17	Three-Shelf Utility Cart	1	0	InterMetro Industries Corp.	BC2636-3D		Owner	Owner	Eq Plnr	Owner	FloorStd										39	27	41.5	46.5	3 shelf utility cart with 2.75" ledge on all shelves to contain spills. See last page of cut sheets for available accessories. This cart is also available with Microban product protection (same part number with MB suffix added) which inhibits the growth of bacteria, available only in Slate Blue color.	EQ-014		
CARTU35	Small Plastic Utility Cart	2	0	Rubbermaid Commercial Products	4500-88 (old style)		Owner	Owner	Eq Plnr	Owner	FloorStd										34	17	32.6	31	Four polyurethane swivel casters. Two shelves, 200 lbs/shelf capacity.	EQ-015		
CASES01	Stainless Steel Casework	1	0	Continental Metal Products Inc	BC-24		Contractor	Contractor	Eq Plnr	Owner	FloorStd										24	25	36					
CASES05	Stainless Steel Casework	1	0	Continental Metal Products Inc			Contractor	Contractor	Eq Plnr	Owner	FloorStd										96	25	36					
CASES41	Stainless Steel Casework	1	0	Continental Metal Products Inc	BC-33, & BC-18	with 52" w boxed edge counter	Contractor	Contractor	Eq Plnr	Owner	FloorStd										52	25	36					
CASES42	Stainless Steel Casework	1	0	Continental Metal Products Inc	BC-33 (3)	with 99" w boxed edge counter	Contractor	Contractor	Eq Plnr	Owner	FloorStd										99	25	36					
CASES55	Stainless Steel Upper Wall Cabinets	1	0	Continental Metal Products Inc	WHG-4830-12 (2)		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd										96	12	39					
CASES91	Stainless Steel Upper Wall Cabinets	1	0	Continental Metal Products Inc	WHG-3330-12; & WHG-1830-12		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd										52	12	39		Consists of one stainless steel wall cabinet with glass door (18" w x 12" d x 30" h), plus second stainless steel wall cabinet with glass doors (33" w x 12" d x 30" h).			
CASES92	Stainless Steel Upper Wall Cabinets	1	0	Continental Metal Products Inc	WHG-3330-12 (x3)		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd										99	12	39		Consists of three stainless steel wall cabinets with glass doors, each 33" w x 30" h x 12" d.			
CLEAE01	Endoscope Channel Disinfector/LeakTester	2	0	Olympus Med. Instruments Div	MU-1 (Maintenance Unit)	52541	Owner	Owner	Eq Plnr	Owner	Counter					120	AC	60	Single	2	3	5.8	5.5	6	Manually cleans, disinfects, and rinses the air/water channel of an endoscope. Includes leakage tester to detect hidden pinholes and loose joints to avoid damage from water leakage.	EQ-018		
CLEAE31	Automated Endoscope Reprocessor	5	0	Medivators Inc.	DSD EDGE	DSD-3001	Contractor	Contractor	Eq Plnr	Owner	FloorStd			Y		120	AC	60	Single		1440	36	21	46	400	Dual-basin, asynchronous automated endoscope reprocessor designed for use in busy hospitals and surgery centers. Reprocessing cycle as short as 22 minutes. It uses peracetic acid called Rapicide PA. This High Level Disinfectant works at a low 30 degrees Celsius temperature, eliminating cool down time and assuring scope compatibility.		
CLEAE37	Automated TEE Probe Disinfector	1	0	CS Medical LLC	TD 100	CS-TD100S	Contractor	Contractor	Eq Plnr	Owner	FloorStd			Y		120	AC	60	Single	8	24	8	44	90	Provides high-level disinfection of transesophageal echocardiogram (TEE) ultrasound probes using TD-5 disinfectant (single use container). Five individual rinse cycles following disinfection cycle. Disinfection and rinse process requires less than one minute of operator time; the whole process takes 17 minutes. Microprocessor controlled. Printed verification record for each cycle. Vapor management system adsorbs and neutralizes vapors. 12 month factory warranty (excludes consumables). Pre-installation kit includes: drain fitting, drain filter, quick disconnect ½" MNPT, and pre-installation instructions.			
CLEAE37N	Neutralization Station for Disinfectants	1	0	CS Medical LLC	AC-DS-03		Contractor	Contractor	Eq Plnr	Owner	FloorStd			Y		120	AC	60	Single	0.5	13	16	41.3	35	Neutralization component of the TD-100 for facilities that are required to neutralize their high level disinfectants. Check with relevant environmental regulations on a per facility basis for requirements.			
CLEAP22	High Level Disinfector- Ultrasound Probe	0	1	GE Healthcare	Trophon EPR; E8350NT	(formerly Nanosonics)	Owner	Owner	Eq Plnr	Owner						120	AC	60	Single	5	14	14	19.3	38	Disinfects ultrasound transducers within seven minutes using ultrafine hydrogen peroxide mist.. Meets FDA and CDC guidelines for high-level disinfection. For sale in the U.S. and Canada only. Select either mobile cart or wall mount accessory. Cycle verification via user screen, chemical indicator and electronic log. Probe compatibility can be validated per a transducer list at www.trophon.com. Package includes initial set of Trophon Sonex HL 80 mL bottles and chemical indicator.			
CLEAP22A	Mobile Cart for Trophon EPR	1	0	GE Healthcare	Trophon Mobile Cart; E8350NH	(formerly Nanosonics)	Owner	Owner	Eq Plnr	Owner	FloorStd										20	21	34.5	45				
CLEAP22B	Wall Mount for Trophon EPR	0	0	GE Healthcare	Trophon Wall Mount; E8350NG	(formerly Nanosonics)	Owner	Contractor	Eq Plnr	Owner	Wall-Mtd													3				
CLEAU16	Ultrasonic Cleaner	0	1	Getinge USA Inc.	2460UC	KS2460UCOO	Owner	Contractor	Eq Plnr	Owner	FloorStd	Y	Y			120	AC	60	Single	30	1000	27	34	41	514	Single tank unit cleans surgical instruments and other hardware using ultrasonic energy in a heated water/ detergent solution. 36" h working height, toe switch operation. Sonic cleaning chamber: 15" w x 16.5" d x 13" d (381mm x 673mm x 330mm), 16.25 gal. (62.5 L) liquid volume, 8.5" (216mm) effective liquid depth, 14" w x 23" d x 8" h (356mm x 584mm x 203mm) maximum tray size, 35 lbs. (15.9 KG) maximum load.	EQ-028	
CLEAU42	Two-Chamber Sonic Console	0	0	STERIS Corporation	CaviWave Sonic Console	CR220LR	Contractor	Contractor	Eq Plnr	Owner	Maj Inst			Y		208	AC	60	Three	37.1	70	37	58	950	It is a free standing instrument washer, rinser and dryer supplied in a compact stainless-steel cabinet. The sonic console contains all the needed components to clean (utilizing ultrasonic cavitation passing through a detergent balanced was solution) thoroughly rinse, lubricate and dry surgical instruments prior to disinfection and sterilization. Includes: Automated Load Lift Tray Elevator, Foot operated automatic sonic lid, Port flushing instrument tray and kit, Pure water inlet, Locking casters, and 132 kHz transducer. 20 gal (Left-Right Workflow).			
CLEAU48	Ultrasonic Cleaning System Console	1	0	STERIS Corporation	Caviwave Pro	CRP117	Contractor	Contractor	Eq Plnr	Owner	FloorStd			Y		208	AC	60	Three	26	36	35	42.3	841	Designed to remove tissue, blood, and other contaminants from laparoscopic devices, surgical instruments, and 5mm & 8mm da Vinci EndoWrist instruments and da Vinci accessories, prior to final disinfection and sterilization. Powered opening lid, load/unload tray elevator and touch screen control. Sonic generators deliver dual (58/132 kHz) frequencies and are mounted with individual slide out modules for ease of service. 200 Watts sonic power. Tray size: 24" w x 14" d x 3" h. Tank fluid capacity: 17 gallons (64 Liters).	EQ-029		
CLOCK50	Analog Display Clock	4	0	Spectracom Corporation	NWC-A1212-BAT		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd										13	2.2	12.7	2.5	12 hour display. Also requires Wireless Clock GPS Receiver.	EQ-030		
CLOCM06	Wireless GPS Analog Battery Wall Clock	2	0	Primex Wireless Inc.	14155	XR Series	Owner	Owner	Int Des	Owner	Wall-Mtd										13	2	12.5		The GPS receiver captures a time signal from the U.S. government's global positioning system (GPS) satellites and sends it to the transmitter. The transmitter then broadcasts the time to every system clock in the facility. 5-year, maintenance-free battery life.	EQ-031		
COFFE46A	Coffee Decanters	3	0	Bunn-O-Matic Corporation	Glass Coffee Decanter	06078.0001	Owner	Owner	Eq Plnr	Owner	Accssry														Glass Coffee Decanters 64 ounce (1.89 litre) capacity. Constructed of materials approved by NSF for potable water applications.	EQ-032		
COFFE84	Plumbed Coffeemaker with Hot Water Disp	1	0	Bunn-O-Matic Corporation	CWTF15-3 (3 Lower Warmers)	12950.0212	Contractor	Contractor	Eq Plnr	Owner	Counter			Y		120	AC	60	Single	13.9	1670	17	18	19.3	35	Twelve cup automatic coffee brewer with 3 lower warmers. Brews 3.8 gallons of coffee per hour. All stainless steel construction. Stainless filter basket. Back-up pour-over feature, hot water faucet, brew into decanters, SplashGard funnel deflects hot liquids away from the hand. Plastic funnel. Decanters must be purchased separately.	EQ-033	
DENTS15	Dental Handpiece Maintenance System	1	0	KaVo America Corporation	QUATTROcare PLUS 2124		Owner	Owner	Eq Plnr	Owner	Counter			Y		120	AC	60	Single		41	VA	14	9.1	15		Cleans and lubricates up to three handpieces at the same time in less than five minutes. Package includes: Maintenance System, Absorbent pads, Air tube with wall connector, Power connection, Midwest® Tradition/ Quiet-air® Quick Connect Maintenance Adapter, Midwest® Lowspeed Attachment Adapter, Midwest® Automate E-Type Maintenance Coupler, Midwest® Plus Aerosol Spray Can.	
DISPC30	Chemistry Delivery System, Three-Pump	5	0	STERIS Corporation	Prolystica AL-2000		Owner	Contractor	Eq Plnr	Owner	Wall-Mtd			Y		115	AC	60	Single	1.5	10	5.7	13.3	3.3				
DISPG59	Quadruple Glove Box Dispenser. White	1	0	Bowman Manufacturing Company	GB-059 Quad Dispenser		Contractor	Contractor	Eq Plnr	Owner	Wall-Mtd										22	3.8	10		Holds four boxes of gloves. Two-way keyholes for vertical or horizontal wall mounting. White powder coated steel.	EQ-036		
DISPO07	Waste Disposal System for Sink, 1.0 HP	1	0	InSinkErator (div of Emerson)	Evolution Excel 1.0 hp		Contractor	Contractor	Architect	Owner	Maj Inst			Y		120	AC	60	Single	10.2	9	9	13.5	25.5	1.0 HP single phase motor; 1725 RPM. Permanently lubricated upper and lower bearings. 40 oz. stainless steel grind chamber. MultiGrind technology delivers three stages of grind. Warranty: Seven-year parts and in-home service.			
DRYTU02	Tube Dryer with HEPA Filter	1	0	Olympic Medical (div of Natus)	Sterile-Drier Model 44	Catalog # 54344	Owner	Owner	Eq Plnr	Owner	FloorStd	Y				120	AC	60	Single	16	1700	47	21	86	247	Two doors. Furnished with 9 parts trays and tube-holder for 35 tubes.	EQ-038	
EQUIP00	Room Contains No Equipment	0	0	(Manufacturer Unknown)			Owner	Owner	Owner	Owner																EQ-039		
FILEL18	4-Drawer Lateral File Cabinet	2	0	(Manufacturer Unknown)			Owner	Owner	Int Des	Owner	FloorStd										42	18	53					
HAMPE25	18" Triangular Hamper with Lid	4	0	Pedigo	P-120-L		Owner	Owner	Eq Plnr	Owner	FloorStd										18	18	32	50	Accommodates 18" bags. Frame and bottom shelf constructed of chrome plated steel. Foot-operated stainless steel lid. Three 3" swivel casters.	EQ-041		

Revision No.3 - Trailer Removal	06/28/17
Addendum No. 2	08-17-17
Revisions:	Date

CONSULTANTS:

**ROBERT L. SEYMOUR & ASSOCIATES, INC.**  
TRANSPORTATION  
ROBERT L. SEYMOUR & ASSOCIATES  
180 Thomas Johnson Drive  
SUITE 200  
FREDERICK, MARYLAND 21702

**STRUCTURAL, CIVIL, COST ESTIMATING**  
ALPHA CORPORATION  
1800 WASHINGTON BOULEVARD  
SUITE 405  
BALTIMORE, MD 21203

**HENRY ADAMS**  
Consulting Engineers  
MECHANICAL ELECTRICAL & PLUMBING ENGINEERS  
HENRY ADAMS  
600 BALTIMORE AVENUE  
BALTIMORE, MD 21204

**KORBEL ASSOCIATES**  
Fire Protection ENGINEERS  
FIRE PROTECTION  
KORBEL ASSOCIATES, INC.  
8700 WEST 27TH STREET, SUITE 279  
MINNEAPOLIS, MN 55408

**INDUSTRIAL HYGIENISTS**  
AGRICOLA MONITORING & ANALYSIS, INC.  
1331 ASHTON ROAD, P.O. BOX 646  
HANOVER, MARYLAND 21076

ARCHITECTS / ENGINEERS:

**ERNEST BLAND ASSOCIATES, P.C.**  
TECHNICAL FACILITIES DESIGN  
802 SLIGO AVENUE, SILVER SPRING, MARYLAND 20910  
TELEPHONE (301) 589-4811 FAX (301) 589-3810

Project Status

Drawing No. **EQUIPMENT SCHEDULE**

Approved: Project Director

Project Title **SPS RENOVATION**

Location **WASHINGTON DC VA MEDICAL CENTER**

Date **06-26-2017**

Checked **Checker**

Drawn **Author**

Project Number **688-14-003**

Building Number **BUILDING NO. 1**

Drawing Number **EQ104**

Office of Construction and Facilities Management

Department of Veterans Affairs