



DUCT BANK NOTES:

1. CONCRETE SHALL BE 2500 P.S.I. @ 28 DAYS.
2. PROVIDE REINFORCING RODS ON TOP OF DUCTS WHEN CROSSING OR PLACED IN ROADWAYS.
3. NON-FERROUS TIE WIRES TO BE IMBEDDED IN DUCT BANK CONCRETE.



8/17/17

3

TYP. TRENCH/DUCT BANK DETAIL

SCALE: NONE

2	ASH#2	08/17/17	REFER TO SHEET E13 FOR ADDITIONAL WORK
NO.	DESCRIPTION	DATE	AND NOTES

PROJECT:

VA SOUTH TEXAS HEALTH CARE SYSTEM
UPGRADE EMERGENCY POWER - TASK ORDER NO. VA257-15-R-0634



**BAIRD, HAMPTON & BROWN
ENGINEERING & SURVEYING**

6300 Ridglea Place, Suite 700 Fort Worth, TX 76116 (817)338-1277 mail@bhbinco.com
BHB PROJECT # 2015.144.000 TBPE FIRM #44 TBPLS FIRM #10011300

SCALE:	NONE
DATE:	08/17/2017
DRAWN BY:	KER
CHECKED BY:	KER

SHEET
XE-1
of 1 XE