



GENERAL NOTES

1. Measurements/locations are approximate and shall be verified by the Contractor. VA will not be held responsible for any error or variation in any measurements or other data listed.
2. Appropriate PPE and safety procedures required.
3. ICRA (infection control risk assessment) required prior to starting any work. Follow all ICRA requirements including (but not limited to) providing negative air for work area and bagging debris prior to removal from work area.
4. Refer to SOW for additional details/specifications. Reference drawing sheets M-2 for equipment and device schedules. Sheet E-1 shows electrical work guidance.

SHEET NOTES

- ① DISCONNECT DUCTS, ELECTRICAL, CONTROLS AND FIRE ALARM AND MAKE SAFE FOR RTU REMOVAL. SECURE, LIFT (CRANE), AND REMOVE EXISTING 40 TON ROOFTOP HVAC UNIT (YORK). MAINTAIN INTEGRITY AND WARRANTY OF EXISTING ROOF. PROTECT OTHER EQUIPMENT IN AREA. COORDINATE AND SCHEDULE WITH COR.



A DEMOLITION: EXISTING HVAC RTU-1 (ROOF ABOVE MECH 124)
NTS

B EXISTING HVAC RTU-1
NTS

		Approved: Medical Center Facility Manager	Project Title REPLACE RTU-1 B-44		Drawing Title Demolition/Removal Existing RTU		Project Number 564-17-133		Engineering Service Department of Veterans Affairs	
							Building Number 44			
		Approved: Engineering Service Chief	Measures one inch or not to scale! 0 1"		Scale: NTS		Location VAMC - Fayetteville, AR			
Notes and/or Revisions:		Date			Checked ENG	Drawn ENG	Date 12 JAN 17	Drawing Number D-1		
							Sheet 1 of 4			