

## REQUEST FOR INFORMATION (RFI) FORM

RFI responses will be responded to as necessary in amendment format which will be posted on FBO.

### **Deadline for submission of RFIs for this solicitation is August 17, 2017 at 1:00PM PST.**

No questions will be answered after this date/time unless determined to be in the best interest of the Government as determined by the Contracting Officer. Telephone requests for information will not be accepted or returned.

SOLICITATION: VA261-17-B-0769, Project Number: 593-17-101 Finish 3rd Floor, Building 6, VASNHCS

**NOTE:** ALL PRE-BID INQUIRIES SHALL BE SUBMITTED VIA EMAIL TO [megan.barr@va.gov](mailto:megan.barr@va.gov) BY AN EDITABLE USE OF THIS FORM. Please identify, in numerical sequence, each set of inquiries that you send.

Question(s) is/are regarding the solicitation: **VA261-17-B-0769, Finish 3rd Floor, Building 6**  
Question(s) is/are regarding the drawings, specifications, technical data [   ]

---

---

---

---

Proposal Inquiry: (Type inquiry below)

RFI #1 - SOW 1.e.ii.1. states to provide three (3) six (6) inch diameter cores, however, the plans show two (2) core drills at Conference Table location in 3H313. Please clarify if two or three are to be provided.

**Please provide two (2), six (6) diameters cores as shown on Page 2 of 13 from the drawing packet. See revised Statement of Work (SOW).**

RFI #2 - Electrical and Data Plan for 3H313 (drawing 5 of 13) states to core drill and fill in with fire caulk; no new power or data receptacles are shown at this location. Overall Electrical/Data Plan (drawing 11 of 13) states to provide a table-top power and data module with duplex or quad power receptacles and four (4) Cat6 outlets. Please advise on what is required for the Conference Table.

**Please provide table with quad power receptacles. See revised SOW.**

- RFI #3 - What is located below core drill locations (3H313 and 3H319)? Are these areas accessible during regular business hours for core drilling operations?

Hall 2H210R is located below 3H313, I believe there is no core drilling requirements in Room 3H319. This work is required to be performed after business hours., either weekend or after hours.

- RFI #4 - Details C and D on drawing 10 of 13 state to extend new drywall to underside of roof. Is this also required at the window walls (West wall of 3H313 and East wall of 3H319)?

No, please only extend the drywall and provide a sound attenuation blanket as shown in drawing page 10 of 13 in details C and D, and as depicted on pages 2 and 6 of the drawing packet.

- RFI #5 - Please clarify what equipment or furniture will remain in rooms 3H313 and 3H319 during the performance of the work.

All equipment and furniture will be removed from Room 3H313 and 3H319.

- RFI #6 - SOW paragraph 1.e.i. states to provide a new electrical panel. Overall Electrical/Data Plan (drawing 11 of 13) also has a note that states, "New 100amp, 3PH 30 spaces" [panel]. However, plans also show new power to run from panels LA3BS, LRP3A and HA3A. Please advise if a new panel is to be provided or if new power is to be installed per the Electrical Panel Schedules (drawing 13 of 13).

Please provide new power and utilize the existing panel per the Electrical Panel Schedule on page 13 of 13 of the drawing set.

- RFI #7 - Please provide Manufacturer name for CP-3 carpet tiles (color/name: Happening, 2960 Flash Back) Specs for (E) ACT and CT?

Please refer to Specification Section 09 51 00 (P. 193 of 770) for ACT information. Please refer to Specification Section 09 65 19 (P. 195 of 770) for CP-3 information.

- RFI #8 - Please clarify where AF-1 Access Flooring is to be provided in 3H313.

AF-1 Access Flooring will not be required in Room 3H313.

RFI #9 - Specification section 09 06 00 Schedule For Finishes states to provide WS-3 in room 3H313. Please provide manufacturer/model/color information. Also, please clarify if WS-3 is also to be provided in 3H319.

Please refer to Specification Section 12 24 21 (P. 201 of 770) for manufacturer/model/color information on lightproof shades. Lightproof shades will also be required in Room 3H319.

RFI #10 - Please clarify if P-4 wall finishes in the Specification section 09 06 00 Schedule For Finishes is the same as PT-4.

Please refer to Specification Section 09 91 00 (P. 196 of 770). P-4 is a typo should read PT-4.

RFI #11 - Where is Acoustical Wall Paneling (SOW paragraph 1.c.i. and 2.c.i) to be installed? Please provide finish schedule information for this product.

Please refer to drawing set provided, pages 2, 6, and 10 of 13.

RFI #12 - Please provide a finish schedule and details for the new casework to be provided in 3H313.

Please provide shop drawing and finish schedule for approval.

RFI #13 - The plans (drawing 2 of 13) do not show the location of the demolition of existing south wall and placement of new door from 3H313 to 3H314M. Please clarify the location.

Door will not be required. See updated SOW and drawings.

RFI #14 - Project Specifications 00 01 15 List of Drawing Sheets includes drawing number 03 - 3H313 Furniture Plan, which is not included in the drawing set. Please provide this sheet or advise if this is not to be included in the drawing set.

Please disregard specification section 00 01 15. This is not to be included in the drawing set.

RFI #15 - Can existing cable tray be used to run new power and data required by the SOW? Data will be shielded cable to prevent interference from power.

Data Cables to be run in existing cable tray. Electrical wiring to be in conduits.

RFI #16 - Please provide As-Built Reference drawings referenced in notes on sheet 11 of 13 Overall Electrical/Data Plan.

Will provided as an attachment.

RFI #17 - Note 11 on sheet 11 of 13 Overall Electrical/Data Plan states to provide duplex receptacles, however, this plan sheet shows duplex receptacles in 3H313 and quad receptacles in 3H319. Electrical & Data Plans for 3H313 (drawing 5 of 13) and 3H319 (drawing 9 of 13) show quad receptacles. Please advise if new receptacles are to be duplex or quad.

Please provide quad receptacles for all “new” receptacle locations identified in the drawing plans.

RFI #18 - Note 12 on Overall Electrical/Data Plan (drawing 11 of 13) states to provide duplex receptacle in AV Wall (box at 4’AFF). This plan sheet shows a duplex receptacle, however Electrical & Data Plan for 3H319 (drawing 9 of 13) shows a new quad receptacle at this location. Please advise if new receptacle is to be duplex or quad.

Please provide quad receptacles for all “new” receptacle locations identified in the drawing plans.