

Enclosed are the Government responses in regards to Solicitation VA248-17-R-1257, as follows:

1. Please include the lead results for the existing thermoplastic paint at the parking lots.

Enclosed. Please refer to attached LBP report.

2. Does the lead study include details about the quantity of parking lines that resulted positive in lead? If not, we are suggesting that an allowance be established on the bid for this item to be in fair competition with other bidders.

Enclosed Please refer to attached LBP report.

3. During the site visit, we noticed the height of the multi-level parking may not accommodate a cold milling machine. If this is the case, Could the contractor use a digger to perform the milling?

The Contractors shall perform a partial depth removal by cold milling process except were physical or geometric restrains prevent the use of milling equipment.

4. Are wheels stops to be replaced with new ones or the existing ones are going to be reinstalled once paving is complete?

Contract don't include replacing wheel stops with new ones.

5. Please clarify hours of operation for this contract.

The Contractor shall be responsible, to develop a work plan and progress schedule detailing, at minimum, the procedures to be employed, the equipment and materials to be used on this construction project as per contract specifications. The Contractor shall provide the ILSM to be used during the work and activities durations. The Contractor shall coordinate the construction activities in advance with the delegated COR and CO seeking for approval; prior construction activities starts to minimize with the flow of Medical Center traffic and operations. All Contractors must refer to Specification 01 00 00 - General Requirements for further references.