

**Project 640-15-158**  
**Bldg 100/101 Emergency Power Upgrade**

**General**

The following changes, additions or deletions shall be made to the following Contract Documents. All other conditions shall remain the same.

<b><u>QUESTION</u></b>	There appears to be a conflict with the depth of the duct bank, storm drain line, and sewer piping on Civil Drawing CU-101. Can you verify the depths of the duct bank, storm drain and sewer piping?
<b><u>ANSWER</u></b>	Duct bank, storm drain line, and sewer piping are located on an active construction site and covered. Contractor is encouraged to include in the bid the cost of pot-holing to establish actual depths and make adjustments to piping depths as required.
<b><u>QUESTION</u></b>	Can the site generated spoils be stockpiled and used for backfill, or will we need to supply an approved structural fill material? Additional hauling and disposal fees will apply if we are not able to use the spoils for fill material.
<b><u>ANSWER</u></b>	Contractor shall comply with earth work specification. Use of site non-organic material is allowed as long as it meets compaction requirements.