

Brand Name Dinex Pod Tray System Line Item Specifications:

Pod tray assembly system will consist of multiple individual pieces of equipment each working together as part of the system to allow for tray assembly for up to 500 meal trays. Each Pod includes equipment to hold food a proper temperature and allow for tray assembly as well as delivery and retrieval carts.

Key Features: Each Pod tray assembly system will consist of the following

Quantity per Pod	Total Quantity needed	Item Description	Key Required Features
1 each	3 each	Dinex Model No. DX2011208CE Induction Charger, for heated bases	This equipment heats up a “pellet” that is then placed under the china plate to keep the food on the plate hot while being delivered. This unit heats up 1 pellet at a time. Induction Charger measuring 15-1/2"W x 18-1/8"D x 7"H, countertop, LCD display with audible alert, automatic stand by/shutoff feature, washable filter, multi-lingual (French, Spanish, English), internal surge, stainless steel housing, 208V/60/3-ph, 20 amps, 6700 watts, NEMA L15-20P, NSF, cETL, CE, FCC. *1 is needed for each Pod, but a back up unit is also required as this is a mission critical piece of equipment and if 1 ever went down, NFS would not be able to produce patient meals.
2 each	4 each	Dinex Model No. DXIBDRS270 Pellet STORAGE/ DRYING CART	This piece of equipment is a drying rack to put the pellets on after they come through the dishwashing machine. Drying & Storage Rack, stainless steel, for Smart-Therm™ bases, holds 270 induction pellets/bases, 1" square stainless steel tubing frame construction, welded tray slides, 5" casters (2 with brakes).
1 each	2 each	Dinex Model No. DXDHF6HIB-CUSTOM POD 6 well hot FOOD SERVING COUNTER	This is a piece of equipment that hold pans of multiple food items (6 wells) for meal assembly that comes with a two tier overshef with heat lamps to keep the plate hot while awaiting placement on the meal tray. Hot Food Counter measuring 91" L, with (6) 12" x 20" hot food wells, with thermostatic controls with indicator lights, stainless steel top, open cabinet base, stainless steel front & end panels, 4 swivel casters, (2 locking) (DHF/6). Includes 208v/60/1-ph, 5400 watt, 26 amps, 10' cord with NEMA 6-50P, std. Includes 4 Manifold Drains, for six well hot food unit (MD/6). Includes drop down work shelf for 6-well counter measuring 91" W x 8" D stainless steel on

			operator side. Includes overshef 99"L, two tier, heat lamps on top, stainless steel, for six pan size unit.
2 each	4 each	Dinex Model No. DXIDPC20120 Mobile Plate and Dish Dispenser	This is a dish dispenser that is able to pre-heat the china plates to aid in temperature retention of food items. Convection Heated Plate Dispenser, 2 removable silos, each plate silo holds (75) 9" plates, each silo accommodates 7-1/2" to 10-1/4" dia. With insulated top & sides, (2) latchless hinged lids, compartment temperature range: 140°-330°F, programmable temperature control, 304 stainless steel self leveling dispenser mechanisms with field adjustable springs, (4) 3-1/2" performance swivel casters (2 with brakes), non-marking cushion tread wheel, 0.063"H aluminum interior wall, 18 gauge 300 stainless steel exterior, 10' cord (20 amps), 3200 watts, 15.4 amps, 208v/60/1-ph, NEMA 6-20P, cETLus, ETL.
10 each	20 each	Dinex Model No. DXICT20-CUSTOM Tray Retrieval Cart – 20 tray capacity	These are 20 tray capacity carts used to pick up dirty trays from patient bedside areas. Tray Retrieval/Delivery Cart, single compartment, enclosed style, non pass thru, 20 tray capacity with 4.75" tray spacing, 14" x 18" or 15" x 20" trays, pull type door with drop latch, stainless steel construction, (4) 5" Quiet casters, 2 swivel with brakes, 2 fixed without brakes (ICT/20). Corner Bumpers (4). Push Handle (1).
8 each	17 each	Dinex Model No. DXTQ1T2D14-CUSTOM COMPACT QUIET CART – 14 tray capacity	These are 14 tray capacity carts used to serve meal trays to patient beside. Used for main hospital and other locations. Quiet Mobile Tray Delivery Cart with 2 Doors, capacity 14 trays, 1 tray per slide, vertical tray spacing 4.75", 44"x27"x52.8"H, adjustable tray slides, vertical push handles, vented side panels, gravity locking door with door stop, corner bumpers, stainless steel, 6" Colson Performa casters (2 rigid, 2 swivel with Tech lock brakes) with noise suppression bearing covers, NSF. Includes top Rail, 3 sided.
4 each	8 each	Dinex Model No. DXTQ1T2D20-CUSTOM CUSTOM COMACT QUIET CART – 20 tray capacity	These are 20 tray capacity carts used to serve meal trays to patient beside. Use for mental health and other locations. Quiet Mobile Tray Delivery Cart with 2 Doors, capacity 20 trays, 1 tray per slide, vertical tray spacing 4.75", 44"x27"x61"H, vertical push handles, vented side panels, gravity locking door with door stop, corner bumpers, stainless steel, 6" Colson Performa casters (2 rigid, 2 swivel with Tech lock brakes) with noise suppression bearing covers, NSF. Includes top Rail, 3 sided.
1 each	2 each	Dinex Model No. DXDST3-CUSTOM	This is a solid table top used in the pod to place induction heater and other needed equipment.

		POD WORK CENTER TABLE FOR INDUCTION	Solid Top Counters, 49" L, 16 ga. stainless steel top, 18 ga. sides and end panels, swivel casters (2 locking) (DST/3)
4 each	8 each	Dinex Model No. DXIRAC15HDEF AIR CURTAIN REFRIGERATOR	These are refrigerators used for each pod to keep food items at proper temperatures during the tray assembly period. 3/4 HP Air Curtain Refrigerator for operating POD systems up to 3 hours at a time, one-section, bottom mount self-contained refrigeration, accommodates: (15) 18" x 26" or (30) 14" x 18" trays, 18 gauge stainless steel tray slides, digital LDG controller, auto/manual defrost mode, 270° swing right hinged glass door, rear mounted tubular push handle with donut bumper, one piece self adjusting magnetic gasket, removable stainless steel tray side panel, no tip tray slides, non-marking perimeter markers, (4) 6" Performa swivel casters (2 with brakes), 430 grade 20 gauge polished exterior wall & 301 grade 24 gauge interior wall, stainless steel, 3/4 HP, 120v/60/1-ph, 11 amps, 1800 watts, NEMA 5-20P, NSF, cULus (IRAC15)
1 each	2 each	Dinex Model No. DXDW1891 CUSTOM 18X91 WORK TABLE WITH ELECTRIC RACEWAY	This is a custom electrical hub that all Pod equipment plugs in to for electrical power supply. Allows the facility to provide power outlet to 1 location. 18x91" Custom work table with electric raceway to power the POD. Includes undershelf.
1 each	2 each	Dinex Model No. DXDWT3060 CUSTOM CONDIMENT TABLE	This is a custom condiment table used for each Pod to support tray assembly function. Custom condiment table, 30x60 with double rows of condiment bins on each side for POD.
2 each	4 each	Dinex Model No. DXIDT1C1520 TRAY RACK DISPENSER	This equipment is used to store trays that are need for meal assembly. Mobile Tray Dispenser, maximum. tray size 15" x 20", 150 capacity, solid shelf, open tubular frame, cantilever single self-leveling tray platform, removable carrier, adjustable lifting rate, (4) 5"HD nonmarking swivel casters (2 with brakes) & bumpers, stainless steel construction& push handle, NSF (IDT1C/1520)