




T350

Tow-Pro® Boom Lift



Key Specs

- **Horizontal Outreach:** 20 ft 2 in. / 6.15 m
- **Platform Capacity:** 500 lb / 226.80 kg
- **Platform Height:** 34 ft 5 in. / 10.49 m

Power Source

Batteries

4 x 6V 220 amp-hr

General

Capacity - Hydraulic Reservoir

4 gal. / 15.14 L

Maximum Ground Bearing Pressure

23 psi / 1.61 Kg/cm²

Machine Weight

3400 lb / 1542.21 kg

Performance

Frame Leveling

11 Degrees

Leveling Capability

11 Degrees

Outriggers or Stabilizers

Yes

Platform Capacity

500 lb / 226.80 kg

Swing

410 Degrees

Swing Type

Non-Continuous

Towing Speed Rating

65 mph / 104.61 km/h

Jib - Range of articulation

0 Degrees

Dimensional Data

Ground Clearance

1 ft 2 in. / 0.36 m

Ground Entry Height

10 in. / 0.25 m

Machine Height

6 ft 6 in. / 1.98 m

Machine Length

21 ft 9 in. / 6.63 m

Machine Width

4 ft 9 in. / 1.45 m

Outrigger Footprint Length

11 ft 7 in. / 3.53 m

Outrigger Footprint Width

10 ft 5 in. / 3.18 m

Platform Dimension A

2 ft 6 in. / 0.76 m

Platform Dimension B

4 ft / 1.22 m

Dimensional Data

Tire Size

205/75 R14 Pnuematic

Reach Specifications

Horizontal Outreach

20 ft 2 in. / 6.15 m

Platform Height

34 ft 5 in. / 10.49 m

Up and Over Height

15 ft / 4.57 m

Key Features

- Gasoline engine or 24V DC electric power
- Standard air and water lines to platform
- Accessory Mounting Tray accommodates your generator, air compressor or pressure washer

Reach

