

STATEMENT OF WORK

PURPOSE: To upgrade/replace dental chairs, stools in all Dental Treatment Rooms.

GOAL: To obtain a comfortable, reliable, streamlined, convenient dental chair system that makes each provider encounter seamless when it comes to operability. Package includes: **511 Dental Chair-**

- **Ultra-thin backrest that "flexes."** Enables you to comfortably tuck your knees under the chair—no hard metal back to worry about; cradles the patient in comfort and features upholstery thinner than 1" (25 mm) in some areas.
- **Double-articulating, gliding headrest.** Moves with the patient to improve comfort; adjusts easily with one hand.
- **Innovative hydraulic lift system.** Results in gentle stops and starts during patient positioning.
- **Integrated 300-watt power supply.** Provides more than enough power for the whole system; powers light and additional ancillary devices.
- **Expanded height range.** Offers a range from 13.5" (343 mm) to 31.5" (800 mm) so any doctor, regardless of height, can work comfortably.
- **60° swivel with brake.** Allows 30° rotation on each side of center.
- **Multi-position armrests.** Rotates out of the way to streamline patient entry and exit.
- **Cut-away, cast iron baseplate.** Allows you to roll your stool closer to the patient; provides six contact points for added stability on uneven floors.

532 TRAD Delivery System-

- **Innovative 4-position control block design.** Results in the industry's most reliable air-driven component with fewer parts, stronger corrosion-resistant materials, and a unique water flow system that eliminates stagnant water where bacteria can grow.
- **Left/right pivoting chair mount.** Provides both left- and right-handed doctors with ergonomic, efficient positioning of the control head.
- **Pivoting, centrally mounted control head.** Allows advanced instrument positioning and extended tubing reach.
- **Integrated fiber-optic system.** Provides independently adjustable voltage settings for up to four handpiece positions.
- **2-liter, self-contained water bottle.** Includes an integrated pickup tube to reduce the risk of cross-contamination and a quick-disconnect fitting that makes the bottle easy to remove and replace.

- **Data Communication System (DCS).** Enables reliable two-way communication between system circuit boards, which allows monitoring of all system functions; auto-detects new modules.
- **Wet/dry foot control with chip blower/accessory button.** Operates handpieces and integrated accessories like your A-dec intraoral camera in conjunction with the A-dec 500 deluxe touchpad.

551 Assistant's Instrumentation-

- **Assistant's holder choices.** Accommodates various combinations of vacuum instruments, syringe, and other accessories; includes electric holder options.
- **Adjustable holders.** Rotates as a group and pivot independently customizing instrument positioning.
- **Integrated A-dec 500 standard touchpad.** Provides secondary control of chair, dental light, and cuspidor (or accessory) functions; serves as a sturdy handle for positioning the assistant's arm.
- **Easy left/right conversion.** Accommodates both left- and right-handed operators.
- **Vacuum tower.** Rotates to improve HVE and saliva ejector tubing management; includes a large-capacity solids collector to simplify routine cleaning.

571L LED Dental Light-

- **Three-axis, 540° spherical rotation light head adjustment.** Provides unlimited positioning.
- **Three light intensity settings.** Features three intensity settings of 15,000, 25,000, and 30,000 lux.
- **Cure-safe mode.** Enables the dental team to work effectively without curing photo-initiated resins.
- **Auto On/Off function.** Turns the dental light on automatically when the chair reaches the treatment position and turns it off in the entry/exit position when combined with the A-dec 500 and A-dec 300 systems.
- **Remote touchpad activation.** Allows you to toggle between settings and turn the dental light on and off without having to touch the light head.
- **Local switching.** Enables easy change of mode by the entire dental team when the touchpad is not available.
- **Long-lasting LEDs.** Uses about 1/5th the power of a traditional quartz halogen light with a life expectancy of up to 40,000 hours, or nearly 20 years of daily use.

521 522 Doctor's/ASST Stool-

Stool features: **Tilt Seat**

Distributes weight from seat to feet allowing proper circulation.

Contoured Backrest

Cradles the spine, while encouraging blood flow. Contoured backrest is standard on the A-dec 521 doctor's stool and optional on the A-dec 522 assistant's stool.

Whisper Quiet Casters

New design provides smooth, ultra-quiet movement on both carpet and hard flooring.

Adjustment Controls

Numbered paddles are easy to access for quick adjustments and easy cleaning.

Backrest Height Control

A push button makes access and one handed adjustments easy.

Upholstery

Minimal seams make clean up easy.

Standard Foot Ring (A-dec 522 Assistant's Stool)

Helps practitioner maintain correct posture.

581 Monitor Mount-

- **Tilt and swivel mechanism.** Offers multiple viewing angles for comfortable patient viewing from both the seated and supine positions.
 - **Easy-grip handle.** Allows you to easily maneuver and tilt the monitor with one hand.
 - **VESA compatible.** Accommodates 15" (381 mm), 17" (432 mm), and 19" (483 mm) medical-grade monitors up to 20 pounds (9 kg).
1. Information System Officer, Information Protection: The contractor **will not** have access to VA Desktop computers they will not have access to online resources belonging to the government.
 2. Privacy Officer: The Contractor **will not** have access to protected Patient Health Information (PHI) nor will they have capability of accessing patient information during the services provided to the VA and if removal of equipment from the VA is required, any memory storage device will remain in VA control and will not be removed from VA custody. All research data available for Contractor analysis is de-identified.
 3. Records Manager:
 - a. Citations to pertinent laws, codes and regulations such as 44 U.S.C chapters 21, 29, 31 and 33; Freedom of Information Act (5 U.S.C. 552); Privacy Act (5 U.S.C. 552a); 36 CFR Part 1222 and Part 1228.
 - b. Contractor shall treat all deliverables under the contract as the property of the U.S. Government for which the Government Agency shall have unlimited rights to use, dispose of, or disclose such data contained therein as it determines to be in the public interest.

- c. Contractor shall not create or maintain any records that are not specifically tied to or authorized by the contract using Government IT equipment and/or Government records.
- d. Contractor shall not retain, use, sell, or disseminate copies of any deliverable that contains information covered by the Privacy Act of 1974 or that which is generally protected by the Freedom of Information Act.
- e. Contractor shall not create or maintain any records containing any Government Agency records that are not specifically tied to or authorized by the contract.
- f. The Government Agency owns the rights to all data/records produced as part of this contract.
- g. The Government Agency owns the rights to all electronic information (electronic data, electronic information systems, electronic databases, etc.) and all supporting documentation created as part of this contract. Contractor must deliver sufficient technical documentation with all data deliverables to permit the agency to use the data.
- h. Contractor agrees to comply with Federal and Agency records management policies, including those policies associated with the safeguarding of records covered by the Privacy Act of 1974. These policies include the preservation of all records created or received regardless of format [paper, electronic, etc.] or mode of transmission [e-mail, fax, etc.] or state of completion [draft, final, etc.].
- i. No disposition of documents will be allowed without the prior written consent of the Contracting Officer. The Agency and its contractors are responsible for preventing the alienation or unauthorized destruction of records, including all forms of mutilation. Willful and unlawful destruction, damage or alienation of Federal records is subject to the fines and penalties imposed by 18 U.S.C. 2701. Records may not be removed from the legal custody of the Agency or destroyed without regard to the provisions of the agency records schedules.
- j. Contractor is required to obtain the Contracting Officer's approval prior to engaging in any contractual relationship (sub-contractor) in support of this contract requiring the disclosure of information, documentary material and/or records generated under, or relating to, this contract. The Contractor (and any sub-contractor) is required to abide by Government and Agency guidance for protecting sensitive and proprietary information.

DELIVERY:

S.T.V.H.C.S. – Logistics Service Warehouse
7400 Merton Minter Blvd.
San Antonio, TX 78229

COST AND ESTIMATE:

Attached to e-CMS