

SCOPE OF WORK

OVERLAY AND SEALCOAT ROADWAYS **GREAT LAKES NATIONAL CEMETERY, HOLLY, MI 48442**

- A. **The Contractor:** Shall furnish all labor, material, equipment, and supervision to verify existing conditions, repair existing damaged asphalt roadway/parking lot surfaces, sealcoat existing roadways/parking lots, and restripe parking lots and roads at the Great Lakes National Cemetery per project specifications and drawing.
- B. **The Work:** The Work shall include, but shall not be limited to the following (not necessarily in the order indicated):
1. Contractor shall field verify existing conditions, i.e., location and size of areas of asphalt pavement surface and road base failure, location and lengths of existing roadway surface cracks needing repair and filling, and areas where asphalt pavement sealer (coal tar emulsion sealer with necessary and recommended additives and aggregate (silica sand) is to be applied at Great Lakes National Cemetery in accordance with all applicable codes and regulations.
 2. Contractor shall provide all supervision, labor, materials, tools, and equipment to prepare existing asphalt roads and parking lots for repairs and make the necessary repairs; provide all supervision, labor, materials, tools, and equipment required to apply coal tar emulsion sealer with recommended additives and silica sand aggregate; and provide all supervision, labor, materials, tools, and equipment required to restripe parking lots and roads.
 2. Haul away & dump debris and waste to an approved disposal site.
 3. Thoroughly clean up the work area at the end of each day's work, and at completion of the project. Leave premises clean and free of waste, scrap, used equipment, or other material intentionally or incidentally delivered to the site by Contractor or Contractor's personnel.
- C. **Time of Completion:** The project shall be completed within 30 calendar days after contract award.
- D. **Code Compliance:** All work shall be performed in accordance with all applicable local, state and federal regulations.
- E. **Contractor Quality Control:** The Job Site Superintendent will: a) review and approve submittals, b) inspect the quality of work performed, and c) certify the completed work for payment and other purposes.
- F. **Availability/Constraints of Site:** See attachments: Specification Section 010000, "General Requirements", Specification Section 013323, "Shop Drawings, Product Data, and Samples", Specification Section 321216, "Asphalt Paving Sealing", and "*Great Lakes National Cemetery - Additional Information and Requirements.*"
- G. **Submittals After Award:** Reference Specification Section 013323, "Shop Drawings, Product Data, and Samples".
- H. **Plans/details:** Site Plan.
- I. **POC:** The Contracting Officer's Technical Representative (COTR) for this project is: John Schilling, Jr.
- J. **Project completion:** The project site shall be protected and/or restored to a condition equal to that existing prior to the commencement of work.

END OF SCOPE OF WORK