



- GENERAL NOTES:**
1. REFER TO SHEET E001 FOR GENERAL ELECTRICAL AND INSTALLATION NOTES.
 2. REFER TO SHEET E002 FOR ONE LINE DIAGRAM.
 3. REFER TO SHEETS E501 AND E502 FOR ELECTRICAL SCHEDULES.
 4. ALL THE NORMAL EQUIPMENTS OF BUILDING 411 & 412 WILL BE FED FROM PANEL RP-1, RP-3 RESPECTIVELY UNLESS NOTED OTHERWISE.
 5. PROVIDE DISCONNECTS FOR ALL PTAC UNITS. COORDINATE LOCATION WITH MANUFACTURER AND ARCHITECT. DISCONNECT TO BE INSTALLED UNDER COVER OR ON THE SIDE OF UNIT TO BE INCONSPICUOUS.
 6. COORDINATE EXACT MOUNTING HEIGHT OF THE EQUIPMENTS WITH THE ARCHITECT.
 7. EACH FAN COIL UNIT HAS AN ASSOCIATED FLOW SELECTOR POWERED FROM THE RESPECTIVE FCU. PROVIDE WIRING AND CONDUIT AND WIRE PER MANUFACTURER RECOMMENDATION.
- KEYNOTES:**
1. STARTER/CONTROLLER PROVIDED BY MANUFACTURER.
 2. COORDINATE THE INSTALLATION AND WIRING OF GARAGE DOOR AND CONTROLS WITH MANUFACTURER.
 3. FOR EXACT LOCATION OF ACCESS CONTROL HARDWARE REFER TO TECHNOLOGY DRAWINGS.
 4. DISCONNECT AND CONTROLLER BY MANUFACTURER. PROVIDE SHUNT TRIP FOR COOK TOP INTERLOCK WITH HOOD.
 5. COORDINATE WITH VA DEVICE LOCATION.
 6. PROVIDE BOILERS EMERGENCY POWER OFF. PUSH BUTTON WITH COVER.
 7. PROVIDE WIRING AND CONDUIT FOR BOILER PUMPS P-1 AND P-2. CONNECT INTO BOILER PER MANUFACTURER WIRING DIAGRAMS. FIELD COORDINATE PUMP LOCATIONS.
 8. CONTRACTOR SHALL WIRE MOTORIZED BLINDS AND CONTROLS.



1 FIRST FLOOR ELECTRICAL POWER PLAN - BLDG. 411



2 FIRST FLOOR ELECTRICAL POWER PLAN - BLDG. 412

Construction Documents ACCOMPANYING AMENDMENT VA69D-17-B-0889-A00004

Revisions:	Date

CONSULTANTS:

O'BrienEngineering, Inc.
Hydraulics - Hydrology - Civil Engineering



Texas Firm Registration No. 8856
1225 N Loop W, Suite 800
HOUSTON, TX 77008
713.864.2900

ARCHITECT/ENGINEERS:

COX DESIGN ASSOCIATES

ARCHITECTURE PLANNING INTERIORS
Austin 5121 Bee Caves Road, Suite 203 Chicago 820 Davis St., Suite 432
Austin, Texas 78746 Evanston, IL 60201
T:312 - 327 - 4149 F:312 - 454 - 9434
F:312 - 327 - 7679 bcox@coxdesignassociates.com bcox@coxdesignassociates.com

Approved: Chief of MH

Date: _____
Approved: Director _____
Date: _____

Approved: Chief of FMS

Date: _____
Approved: VA Energy Engineer _____
Date: _____

Drawing Title
FIRST FLOOR ELECTRICAL POWER PLANS - BLDG. 411 & 412

Location
TOMAH VAMC
500 E. VETERANS STREET
TOMAH, WI. 54660

Project Name
VA Tomah CLC Homes

Building Number
411 & 412

Checked
RHC

Drawn
MAG

Project Number
676-324

Date
10/12/2017

Drawing Number
1-E-301

Dwg.

Office of
Construction
and Facilities
Management

